BANGALORE WATER SUPPLY
AND
SEWERAGE BOARD
CAUVERY BHAVAN, KEMPEGOWDA ROAD,
BANGALORE – 560 009

SHORT TERM TENDER FOR THE

Work of providing & laying UGD sub-main of 400mm dia, lateral linking along with manual jacking in Herohalli village coming under 110 villages of BBMP and other works.

Office of the Chief Engineer (Project)
BANGALORE WATER SUPPLY & SEWERAGE BOARD
3rd floor, Cauvery Bhavan,
K G road, Bangalore 560009.
Telephone – 080 22945108

e-mail – cep@bwssb.gov.in

TENDER REFERENCE :	:	BWSSB/CE(P)/ACE(Cst-DCW)/ 2038/2024-25 Dt: 18.1.2025
DATE OF PUBLICATION IN KPP-PORTAL	:	20.1.2025
LAST DATE FOR SUBMISSION OF TENDER IN KPP PORTAL	:	29.01.2025 upto 1300 hrs
PRE-BID MEETING DATE	:	24.01.2025 at 1430 hrs
TIME AND DATE OF OPENING OF TECHNICAL TENDER	:	30.01.2025 at 1400 hrs
PLACE OF OPENING OF TECHINCAL TENDER	:	Office of the Chief Engineer (Project), 3rd floor, Cauvery Bhavan, K G road, Bangalore 560009.
TIME AND DATE OF OPENING OF PRICE TENDERS	:	Will be intimated to the Qualified Tenderers
PLACE OF OPENING OF PRICE TENDER	:	Will be intimated to the Qualified Tenderers
ADDRESS FOR COMMUNICATION	:	**Chief Engineer (Project)** 3rd floor, Cauvery Bhavan, K G road, Bangalore 560009. Telephone – 080 22945108 e-mail – cep@bwssb.gov.in

Contractor
Employer

Contents

Section No.	Description	Page
1	INVITATION FOR TENDERS (IFT)	3
2	INSTRUCTIONS TO TENDERERS (ITT)	7
3.	QUALIFICATION INFORMATION	23
4.	FORM OF TENDER, LETTER OF ACCEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM	27
5.	CONDITIONS OF CONTRACT (CC)	31
6.	CONTRACT DATA	51
7	SPECIFICATIONS	55
8	DRAWINGS	106
9.	BILL OF QUANTITIES	107
10.	FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT	108

SECTION 1:

BANGALORE WATER SUPPLY AND SEWERAGE BOARD
Office of the Chief Engineer (Project)
3rd Floor, Cauvery Bhavan, K.G. Road, Bangalore 560009
Website www.bwssb.kar.gov.in email cep@bwssb.gov.in
Telephone: +91-80- 22945108

INVITATION FOR SHORT TERM TENDER
(ONLY THROUGH KPP PORTAL)
(https.kppp.karnataka.gov.in)

IFT No.: BWSSB/CE(P)/ ACE(Cst-DCW)/ 2038/2024-25 Dated: 18.01.2025

1. The **Office of the Chief Engineer (Project)** invites tender from eligible tenderers, for the construction of work detailed in the Table below through KPPP process with two stages tender procedure in line with the Rule 28 of the KTPP Act. The details regarding their qualification to take the tender (as detailed in ITT Clause 3) and the price tender shall be uploaded in the website of the e-procurement wizard. Technical details will be opened on the date and time mentioned in IFT clause 5 and evaluated. The price tender of the Tenderer, who is found to be qualified to execute the tendered works, will be opened on the date notified later. The Tenderers are advised to note the minimum qualification criteria specified in Section -2 Clause 3 of the Instructions to Tenderers (ITT) to qualify for award of the contract.

2. Tender documents may be downloaded through the KPPP wizard which will link to www.karnataka public procurement portal from **20.01.2025 to 29.01.2025** on payment of fee indicated in the Table below, using online mod through KPP portal only**.** Interested tenderers may obtain further information at the Office of e-procurement. Tenderers will be issued a password and authorized for accessing the tender document in the website with URL: **www.karnataka public procurement portal**

3. The Bidders can download the e-tender document using their user ID –password, by accessing **www.karnataka public procurement portal** where electronic tender form is provided. Additional information related to e-tender process can be

obtained through the above mentioned website. The electronic tender will be operated as Two stage Tender system by opening the Technical details first and financial portion of the eligible tenderers later.

4. Tenders must furnish Earnest Money Deposit specified through KPPP only.

5. Contractors should have registration in KPWD of State Government organization, public sector under takings, other state Governments and the documentary evidence towards the same shall be furnished.

BANGALORE WATER SUPPLY AND SEWERAGE BOARD

Office of the Chief Engineer (Project)

3rd Floor, Cauvery Bhavan,
KG Road, BANGALORE 560 009

NO.BWSSB/CE(P)/ ACE(Cst-DCW)/2038 /2024-25

Dated: 18.01.2025

INVITATION FOR SHORT TERM TENDER (IFT)
(Through KPP Portal Only)

BWSSB, invites item rate e-Tenders in Two Stage Tender system from eligible contractors through KPP Portal for the following work:

Sl. No	Name of Work	Cost of Tender Document including	Appro. Amount put to Tender in Lakh Rs.	Bid Security in lakh (Rs.)	Period of completion	Eligibility Criteria during last 5 years (2019-20, 2020-21, 2021-22, 2022-23 & 2023-24)

		Taxes Rs.	(excluding GST)			Turnover (in all classes of Civil Engineering construction works) for any of the two years Rs. in Lakhs	Performance & Work Qualification
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
1	Work of providing & laying UGD sub-main of 400mm dia, lateral linking along with manual jacking in Herohalli village coming under 110 villages of BBMP and other works.	To be specified by e-procurement cell.	351.44	5.28	15 months (Including monsoon period)	663.52	i. As prime As prime contractor should have satisfactorily completed at least one similar work of not less than Rs.67.41 lakh. ii. As prime contractor should have satisfactorily completed at least one similar building work with compound wall construction of not less than Rs.139.95 lakh. iii.The tenderer should have installed & commissioned the lift with provision for minimum 6

							person's capacity. iv. Executed in any one year, the following minimum quantities: • Earth work excavation: 1653 cum • DWC/DI pipes of 200mm dia & above- 300m • M20 & above design mix- 283 cum • Steel reinforcement- 36 tons

Note: 1.a. The amount put to tender Rs. 351.44 lakh is excluding the GST at 18 %.

b. The tenderer shall quote the rates excluding GST and the GST will be reimbursed as per actual.

2. The financial bid evaluation will be based on 1(a) of above note.

The tender documents can be downloaded through website www.karnataka public procurement portal from **20.1.2025 to 29.1.2025.** The Last date for submission of completed tender documents through kpp portal is **29.1.2025** upto **1300 hrs** and date of opening of tender on **30.1.2025** after **1400 hrs.**

The details of work / eligibility of contractor etc can be had from website www.karnataka public procurement portal Further particulars may be obtained from the above office during office hours & also from website www.karnataka public procurement portal

-Sd/-
Chief Engineer(Project)
BWSSB

Contractor
Employer

"ADOPT RAIN WATER HARVESTING SYSTEM AND SAVE WATER"

6. The bids will be opened at the office mentioned in para no.12 on **30.01.2025 at 1400 hrs** in the presence of bidders or their authorized representatives. If the bid opening day remains as public holiday, Bids will be opened on the next working day at the original stipulated time.
7. Bidders can access tender documents from the website and upload the required details; those are mentioned in different sections in the bid document in to electronic tender box on the website. Scanned documents those are required to be furnished as per Section 2, 3 & 4 of the bid document shall be submitted through e-portal preferably in **PDF** format for clear vision.
8. The cost of the tender document once paid will not be refunded.
9. Applications / requisitions from joint venture Firms are not acceptable.
10. The cost of the tender document once paid will not be refunded.
11. The successful bidder would be required to give performance **bank guarantee of 5%** of the contract amount plus additional security for unbalanced bid amount from a Nationalized / Scheduled Indian Bank, with jurisdiction at Bangalore as specified in the clause no.29 of ITT, towards guarantee for completion of work within the stipulated period.
12. Bangalore Water Supply and Sewerage Board reserve the right to cancel or annul the entire or part of this process of invitation at any time without assigning any reason.
13. For any additional information regarding the above tender, the firms who are interested to quote, may contact office of the undersigned at the office address given below on all working days during office hours 1030hours to 1700 hours.

The Chief Engineer (Project),
Bangalore Water Supply and Sewerage Board
3rd Floor, Cauvery Bhavan D- Block,
Kempe Gowda Road, Bangalore - 560009
Karnataka, India.
Telephone: +91-80- 22945108
e-mail ID: cep@bwssb.gov.in
Or **visit Website** www.karnataka public procurement portal

14. List of documents to support qualification of bidder is to be uploaded to the e-Portal website www.karnataka public procurement portal

15. Bidders shall submit offers that comply with the requirements of the bid document, including the basic technical design as indicated in the drawing and specifications. Alternatives will not be considered. The attention of the bidders is drawn to clause 23 regarding the rejection of the bids, which are not substantially responsive to the requirement of the bid document.

16. Other details can be read from the tender documents.

17. Corrigendum/ Modification / Corrections, if any will be published in the website only.

-Sd/-
Chief Engineer (Project)
BWSSB.

SECTION 2:

INSTRUCTIONS TO TENDERERS (ITT)

Table of Clauses

		Page No.
A.	**General**	
	1. Scope of Tender	9
	2. Eligible Tenderers	9
	3. Qualification of the Tenderer	9
1	4. One Tender per Tenderer	11
2	5. Cost of Tendering	11
3	6. Site Visit	11
B.	**Tender Documents**	
1	7. Content of Tender documents	11
2	8. Clarification of Tender Document	11
	9. Amendment of Tender documents	12
C.	**Preparation of Tenders**	
	10. Documents comprising the Tender	12
	11. Tender prices	13
	12. Tender validity	13
	13. Earnest money deposit	14
	14. Format and signing of Tender	14
D.	**Submission of Tenders**	
	15. Sealing and marking of Tenders	15
	16. Deadline for submission of Tenders	16
	117. Late Tenders 16	
	18. Modification and Withdrawal of Tenders	16
E.	**Tender opening and evaluation**	
1	19. Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers	17
	20. Opening of Second Cover Tenders of qualified Tenders and evaluation	17
	21. Process to be confidential	18
	22. Clarification of Tenders	18
	23. Examination of Tenders and determination of responsiveness 19	
	24. Correction of errors	19
	25. Evaluation and comparison of Tenders	19
F.	**Award of contract**	
	26. Award criteria	20
	27. Employer's right to accept any Tender and to reject any or all Tenders	20
	28. Notification of award and signing of Agreement	20
	29. Security deposit	21
	30. Advance payment and Security	21

31 Corrupt or Fraudulent Practices 21

A. General

1. Scope of Tender

1.1 ***The Chief Engineer(Project), BWSSB,*** (Referred to as Employer in these documents) invites tenders following Two Cover e-procurement procedure, from eligible Tenderers, for the construction of work (as defined in these documents and referred to as "the work") detailed in the Table given in the Invitation for Tenders (IFT).

2. Eligible Tenderers

2.1 Tenderers shall not be under a declaration of ineligibility for corrupt and fraudulent practices issued by the Government of Karnataka

2.2 Tenders from Joint ventures are not acceptable.

3. Qualification of the Tenderer:

1 3.1 All Tenderers shall provide the requested information accurately and in sufficient detail in Section 3: Qualification information.

1 3.2 **To qualify for award of this contract, each Tenderer in its name should have in the last five years i.e. 2019-20 to 2023-24).**

2

(a) i. Achieved in at least two financial years a minimum financial turnover (in all classes of civil engineering construction works only) of **Rs.663.52 lakh.**

(b) i. As prime contractor should have satisfactorily completed at least one

similar work of not less than Rs.67.41 lakh.

ii. As prime contractor should have satisfactorily completed at least one similar building work with compound wall construction of not less than Rs.139.95 lakh.

iii. The tenderer should have installed & commissioned the lift with provision for minimum 6 person’s capacity.

(c) Executed in any one year, the following minimum quantities of

work:

a. Earth work excavation: 1653 cum

b. DWC/DI pipes of 200mm dia& above- 300 m

c. M20 & above design mix- 283 cum

d. steel reinforcement- 36 tons

(d). The Tenderer or his identified sub-contractor should possess required valid electrical license for executing building electrification works and should have executed similar electrical works totaling Rs. 5.04 Lakhs in any one year.

(e). The Tenderer or his identified sub-contractor should possess valid license for executing water supply/sanitary engineering works and should have executed similar water supply/sanitary engineering works totaling Rs.6.34 Lakhs in any one year.

0 3.3 **Each Tenderer should further demonstrate**:

0 Each Tenderer should further demonstrate:

a. Availability by owning 50% of the required / specified key & critical equipment for this work & remaining 50% can be deployed on lease / hire basis for all works provided, the relevant documents (commitment agreements etc.,) for availability for this work shall be furnished. Some of the equipments are as follows:

Sl No.	Details	Nos
1	Crane or Hydra(10ton)	1
2	Excavators(1m3)	1
3	Tipper/Dumper Trucks(10m3)	1
4	Tractors	1
5	Pipe laying accessories like tripod, chain pully etc.,	2
6	Road cutting machine	1

[In case of hiring, agreement copy for such arrangement shall be furnished]

b. Liquid assets and /or availability of credit facilities of no less than **Rs.116lakh** (Credit lines/letter of credit/certificates from Nationalized / Schedule banks in India for meeting the fund requirement etc.,

3.4 To qualify for a package of contracts made up of this and other contracts for which tenders are invited in this IFT,

the Tenderer must demonstrate having experience and resources to meet the aggregate of the qualifying criteria for the individual contracts.

3.5 Sub-contractors' experience and resources shall not be taken into account in determining the Tenderer's compliance with the qualifying criteria except to the extent stated in 3.2 (d) and (e) above.

1 3.6 Tenderers who meet the above specified minimum qualifying criteria, will only be qualified, if their available tender capacity is more than the total tender value. The available tender capacity will be calculated as under:

Assessed available tender capacity = (A*N*1.5 - B)> Rs. 414.70 lakh

where

A = Maximum value of civil engineering works executed in any one year during the last five years (updated to **2024-25** price level) taking into account the completed as well as works in progress.

N = Number of years prescribed for completion of the works for which tenders are invited.

B = Value, at **2024-25** price level, of existing commitments and on-going works to be completed during the next 15 months

Note: The statements showing the value of existing commitments and on-going works as well as the stipulated period of completion remaining for each of the works listed should be countersigned by the Employer in charge, not below the rank of an Executive Engineer or equivalent.

3.7 Even though the Tenderers meet the above criteria, they are subject to be disqualified if they have:

- made misleading or false representations in the forms, statements and attachments submitted in proof of the qualification requirements; and/or
- record of poor performance such as abandoning the works, not properly completing the contract, inordinate delays in completion, litigation history, or financial failures etc.; and/or
- participated in the previous Tender for the same work and had quoted unreasonably high tender prices and could not furnish rational justification.

4. One Tender per Tenderer:

4.1 Each tenderer shall submit only one tender for one package. A tenderer who submits or participates in more than one Tender (other than as a sub-contractor or in cases

of alternatives that have been permitted or requested) will cause all the proposals with the Tenderer's participation to be disqualified.

5. Cost of Tendering:

5.1 The tenderer shall bear all costs associated with the preparation and submission of his tender, and the Employer will in no case be responsible and liable for those costs.

6. Site visit:

6.1 The Tenderer at his own responsibility and risk is encouraged to visit and examine the Site of Works and its surroundings and obtain all information that may be necessary for preparing the Tender and entering into a contract for construction of the Works. The cost of visiting the Site shall be at the Tenderer's own expense.

B. Tender documents

7. Content of Tender documents

7.1 The set of tender documents shall have all the Sections given in Page 2:

7.2 Both the sets should be completed and returned with the tender.

8. Clarification of Tender Documents

8.1 A prospective tenderer requiring any clarification of the tender documents may notify the Employer in writing or e-mail only at the Employer's address indicated in the invitation to tender. The Employer will respond to any request for clarification which he receives earlier than 15 days prior to the deadline for submission of tenders. Copies of the Employer's response will be forwarded to all purchasers of the tender documents through e-mail, including a description of the enquiry but without identifying its source. Same will available in the website of e-procurement www.karnataka public procurement portal

8.2 Pre-tender meeting:

8.2.1 The tenderer or his authorized representative is invited to attend a pre-tender meeting which will take place at Office of the Chief Engineer (Project), Bangalore Water Supply & Sewerage Board, 3rd floor, Cauvery Bhavan, K.G.Road, Bangalore -560009 on **24.01.2025 at 2.30PM**

8.2.2 The purpose of the meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage.

8.2.3 The tenderer is requested to submit any questions in writing or by cable to reach the Employer not later than one week before the meeting.

8.2.4 Minutes of the meeting, including the text of the questions raised (without identifying the source of enquiry) and the responses given will be transmitted without delay to all purchasers of the tender documents. Any modification of the tender documents listed in Sub-Clause 7.1 which may become necessary as a result of the pre-tender meeting shall be made by the Employer exclusively through the issue of an Addendum pursuant to Clause 9 and not through the minutes of the pre-tender meeting.

8.2.5 Non-attendance at the pre-tender meeting will not be a cause for disqualification of a tenderer.

9. Amendment of Tender documents

9.1 Before the deadline for submission of tenders, the Employer may modify the tender documents by issuing addenda.

9.2 Any addendum thus issued shall be part of the tender documents and shall be communicated in writing or by cable to all the purchasers of the tender documents.

9.3 To give prospective Tenderers reasonable time in which to take an addendum into account in preparing their tenders, the Employer shall extend as necessary the deadline for submission of tenders, in accordance with Sub-Clause 16.2 below.

C. Preparation of Tenders

10. Documents comprising the Tender

10.1 The tender submitted in KPP portal by the Tenderer shall contain the documents as follows:

(a) Scanned copy of Earnest Money Deposit made ;
(b) Scanned copies of Qualification Information as per formats given in Section 3;
(c) The Tender (in the format indicated in Section 4)
(d) Priced Bill of Quantities (Section 9);

and any other materials required to be completed and submitted by Tenderers in accordance with these

instructions. The documents listed under Sections 3, 4, 6 and 9 shall be filled in without exception. The Earnest Money Deposit shall be submitted to the Tender inviting authority on or before the time of submission mentioned in IFT. PHOTOCOPIES OF THE DOCUMENTS SHOULD BE NOTARISED.

(e) The Form of Tender (in the format indicated in Section 4) (Mandatory)

10.2 Deleted.

11. Tender prices

11.1 The contract shall be for the whole works as described in Sub-Clause 1.1, based on the priced Bill of Quantities submitted by the Tenderer.

11.2 The bidder shall fill in the unit rates in figures for all items of the Works described in the Bill of Quantities. The system will automatically convert the unit rates mentioned in figures to words and also calculate the amount of that item as well as the total Bid value. *Items for which no rate is entered by the bidder will not be paid for by the Employer when executed and shall be deemed covered by the other rates in the Bill of Quantities*

11.3 All duties, taxes, and other levies payable by the contractor under the contract, or for any other cause, shall be included in the rates, prices and total Tender Price submitted by the Tenderer.

11.4 Deleted

12. Tender validity

12.1 Tenders shall remain valid for a period not less than **ninety days (90)** after the deadline date for tender submission specified in Clause 16. A tender valid for a shorter period shall be rejected by the Employer as non-responsive.

12.2 In exceptional circumstances, prior to expiry of the original time limit, the Employer may request that the Tenderers may extend the period of validity for a specified additional period. The request and the Tenderers' responses shall be made in writing or by e-mail. A Tenderer may refuse the request without forfeiting his earnest money deposit. A Tenderer agreeing to the request will not be required or permitted to modify his tender, but will be required to extend the validity of his earnest money deposit for a period of the extension, and in compliance with Clause 13 in all respects.

13. Earnest money deposit

13.1 The Tenderer shall furnish, as part of his tender, earnest money deposit in the amount as shown in column 2 of the Table of IFT for this particular work. This earnest money deposit shall be in favour of ***Chairman, BWSSB*** through KPPP, payable at *BANGALORE* from any Nationalised / Scheduled Indian banks.

13.2 Instruments having fixed validity issued as earnest money deposit for the tender shall be valid for 45 days beyond the validity of the tender.

13.3 Any tender not accompanied by an acceptable earnest money deposit and not secured as indicated in Sub-Clauses 13.1 and 13.2 above shall be rejected by the Employer as non-responsive.

13.4 The earnest money deposit of unsuccessful Tenderers will be returned within 30 days of the end of the tender validity period specified in Sub-Clause 12.1.

13.5 The earnest money deposit of the successful Tenderer will be discharged when the Tenderer has signed the Agreement and furnished the required Performance Security.

13.6 The earnest money deposit may be forfeited:

(a) if the Tenderer withdraws the Tender after tender opening during the period of tender validity;
(b) if the Tenderer does not accept the correction of the Tender Price, pursuant to Clause 24; or
(c) in the case of a successful Tenderer, if the Tenderer fails within the specified time limit to
    (i) sign the Agreement; or
    (ii) furnish the required Security deposit

14. Format and signing of Tender

14.1 The completed bid comprising of documents indicated in ITB 10, should be uploaded in the **Karnatka Public procurement portal** through the website **Karnatka Public procurement portal** along with scanned copies of requisite certificates those are mentioned in different sections in the bid document and scanned copy of Bid Security / EMD in case it is provided in the form of Banker’s cheque/ Demand draft/Pay Order

14.2 All the documents should be uploaded to the **Karnatka Public procurement portal**. Tenderer should take a

print out of the declaration letter provided in the website on company letter head and should sign, stamp and upload the same to the tender wizard of BWSSB.

14.3 Deleted

D. Submission of Tenders

15. Up-loading & submission of tenders

15.1 The tenders should be uploaded only through **e-procurement portal**. Tender should contain

A. Technical Tender consisting of following:

a. All the documents with required details in prescribed format; those are mentioned in different sections in the Tender. Form of Tender, Declaration statement regarding Customs/ Excise duty exemption for materials/ construction equipment brought to site as mentioned in Section 2, etc., shall be downloaded, filled with required details, signed, scanned & uploaded to the KPP portal website **www.kppp.karnataka.gov.in** **only** on or before the time and date indicated in notification /Section I IFT.

b. **Tender security.** Tender security can be paid to through KPP Portal only.

The above documents along with notarized copies of documentary evidences as indicated in Section—II ITT, Section-III Qualification information & Section IV Forms of Tender shall be scanned and uploaded through the KPPP website compulsorily, failing which tender will be rejected in view of incomplete bid document and

B. Financial Tender consisting of Bill of Quantities (file name: BOQ.xls). The tenderer shall down load the bill of quantities and key in the rates (in figures only) in the Bill of Quantities sheet and upload the same file on to the website on or before the time and date indicated in notification /Section I IFT.

Scanned copy of Bid security (as cited in IFT Para No.2)paid through KPP portal is to be uploaded before **14:00 hrs on, Dt : 30.01.2025.** In case of failure of the tenderer to submit the same within stipulated time, their tender will be rejected.

NOTE:

1. URL of the Website for tender submission through KPP portal is as follows:

i www.karnataka public procurement portal**.**

ii **Chief Engineer (Project)**
Bangalore Water Supply and Sewerage Board,
3rd Floor, Cauvery Bavan,
K.G. Road, Bangalore560009
Karnataka, India.
Telephone: +91-80- 22945108

2. The details related to submission of tenders, downloading / uploading of documents or other details are available online in the help wizard, Vendor manual & FAQ of above website. The same is provided along with sample formats in Annexure-I of the Bid document for ready reference.

15.2 Deleted

15.3 Unique Identification Number will be automatically generated by the server with time - stamp and sent to the account of the bidder as an acknowledgement after bidder finally uploads the bids.

15.4 Deleted.

16. Deadline for submission of the Tenders

16.1 Tenders must upload all the tender documents in the KPP procurement portal not later than **29.01.2025 Upto 1300 Hrs**. In the event of the specified date for the submission of tenders being changed / postponed by the Employer due to unforeseen circumstances, the corrigendum will be issued in the news paper & the deadline for submission of tenders will be intimated accordingly.

16.2 The Employer may extend the deadline for submission of tenders by issuing an amendment/corrigendum in accordance with Clause 9, in which case all rights and obligations of the Employer and the Tenderers previously subject to the original deadline will then be subject to the new deadline.

17. Late Tenders

17.1 The software of e-procurement system will not allow the Bidder to upload the documents after expiration of the stipulated date & time of Bid submission. The Bidder shall refer the server time, which will be displayed in the e-procurement portal of BWSSB. Employer will not be responsible for non-receipt of bids on the stipulated date & time prescribed in clause 16, due to Internet Problems, improper uploading or any other related problems. In case

of connectivity problems, Tenderer may contact Helpdesk of the e-tender service provider and may also draw the attention of tender inviting authority.

18. Modification and Withdrawal of Tenders

18.1 Tenderers may "modify" and "withdraw" their tenders multiple numbers of times, until the deadline for submission of tenders by operating the relevant provision made in e-tendering. If the Tenderer withdraws the tender before the deadline for submission of tenders and later if he is interested to submit the tender once again, may do so within the stipulated date & time as mentioned in Clause 16. In this case within the stipulated date & time, the tenderer can once again submit the requisition to the officer inviting tenders for access to the withdrawn tender document for resubmission. For this tenderer need not make any additional payment towards the cost of tender document. Communication of modification / withdrawal by other means will not be accepted.

18.2 Deleted.

18.3 No Tender may be modified after the deadline for submission of Tenders.

18.4 Withdrawal or modification of a Tender between the deadline for submission of Tenders and the expiration of the original period of Tender validity specified in Clause 12.1 above or as extended pursuant to Clause 12.2 may result in the forfeiture of the earnest money deposit pursuant to Clause 13.

18.5 Tenderers may offer discounts for individual items by simply modifying the quoted unit price in the Bill of Quantities. Also, Tenderer may enter their overall discount, at specified location in the Bill of Quantities only, by submitting tender modifications in accordance with this clause. Communication of discount by other means will not be accepted.

E. Tender opening and evaluation

19. Opening of Technical portion of Tenders and evaluation to determine qualified Tenderers:

19.1 The Employer will open the Technical details of all the Tenders received (except those withdrawn), including modifications made pursuant to Clause 18, in the presence of the Tenderers or their representatives on **30.1.2025 after 1400 hrs.** In the event of the specified

date of Tender opening being declared a holiday for the Employer, the Tenders will be opened at the appointed time and location on the next working day.

19.2 WITHDRAWAL proposal submitted pursuant to clause 18 shall be read out first and their bids shall not be opened.

19.3 The Tenderers names, the presence or absence of earnest money deposit (amount, format and validity), the submission of qualification information and such other information as the Employer may consider appropriate will be announced by the Employer at the opening.

19.4 The Employer shall prepare minutes of the Tender opening, including the information disclosed to those present in accordance with Sub-Clause 19.3.

19.5 The Price Tenders of all the Tenderers including modifications for Financial tenders cannot be opened as this is programmed to open later after evaluation of the Technical details of the participating Tenderers.

19.6 The Employer will evaluate and determine whether each tender (a) meets the eligibility criteria defined in ITT Clause 2; (b) is accompanied by the required earnest money deposit as per stipulations in ITT Clause and (c) meets the minimum qualification criteria stipulated in ITT Clause 3. The Employer will draw out a list of qualified Tenderers.

20. Opening of Price Tender of qualified Tenderers and evaluation:

20.1 The Employer will inform all the Qualified Tenderers the time, date and venue fixed for the opening of the price Tenders. The Employer will open the price tender of Qualified Tenderers at the appointed time and date in the presence of the Tenders or their representatives who choose to attend. In the event of the specified date of Price tender opening being declared a holiday for the Employer, the price tenders will be opened at the appointed time and location on the next working day.

20.2 Deleted.

20.3 The Tenderers' names, the Tender prices, the total amount of each Tender, any discounts, and withdrawals, and such other details as the Employer may consider appropriate, will be announced by the Employer at the opening. No Tender shall be rejected at Tender opening.

20.4 The Employer shall prepare minutes of the Price Tender opening, including the information disclosed to those present in accordance with Sub-Clause 20.3.

21. Process to be confidential

21.1 Information relating to the examination, clarification, evaluation, and comparison of Tenders and recommendations for the award of a contract shall not be disclosed to Tenderers or any other persons not officially concerned with such process until the award to the successful Tenderer has been announced. Any effort by a Tenderer to influence the Employer's processing of Tenders or award decisions may result in the rejection of his Tender.

22 Clarifications of Tenders

22.1 To assist in the examination, evaluation, and comparison of Tenders, the Employer may, at his discretion, ask any Tenderer for clarification of his Tender, including breakdowns of unit rates. The request for clarification and the response shall be in writing or by cable, but no change in the price or substance of the Tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the Employer in the evaluation of the Tenders in accordance with Clause 24.

22.2 Subject to sub-clause 22.1, no Tenderer shall contact the Employer on any matter relating to its Tender from the time of the Tender opening to the time the contract is awarded. If the Tenderer wishes to bring additional information to the notice of the Employer, it should do so in writing.

22.3 Any effort by the Tenderer to influence the Employer in the Employer’s Tender evaluation, Tender comparison or contract award decisions may result in the rejection of the Tenderers’ Tender.

23. Examination of Tenders and determination of responsiveness

23.1 Prior to the detailed evaluation of Tenders, the Employer will determine whether each Tender; (a) has been properly signed; and; (b) is substantially responsive to the requirements of the Tender documents like [(a)Form of Tender, (b)Declaration statement regarding Customs/ Excise duty exemption for materials/ construction equipment brought to site as mentioned

in Section 2 etc.,] Scanned / uploaded [including documents those are required to be furnished as per Section 2, 3 & 4 of the tender,]; (c) is accompanied by the required securities and; (d) is substantially responsive to the requirements of the tendering documents.

23.2 A substantially responsive Tender is one which conforms to all the terms, conditions, and specifications of the Tender documents, without material deviation or reservation. A material deviation or reservation is one (a) which affects in any substantial way the scope, quality, or performance of the Works; (b) which limits in any substantial way, inconsistent with the Tender documents, the Employer's rights or the Tenderer's obligations under the Contract; or (c) whose rectification would affect unfairly the competitive position of other Tenderers presenting substantially responsive Tenders.

23.3 If a Tender is not substantially responsive, it will be rejected by the Employer, and may not subsequently be made responsive by correction or withdrawal of the nonconforming deviation or reservation.

24. Correction of errors

24.1 (a) Once the Tenderer key in the rates in figures, in the Bill of quantities provided, rate in words will be auto generated by the system.

(b) Once the Tenderer key in the rates in figures, in the Bill of quantities provided, the system will automatically calculate the amount of that item as well as the total Bid value.

24.2 Deleted

25. Evaluation and comparison of Tenders

25.1 The Employer will evaluate and compare only the Tenders determined to be substantially responsive in accordance with Clause 23.

25.2 Deleted.

25.3 The Employer reserves the right to accept or reject any variation, deviation, or alternative offer. Variations, deviations, and alternative offers and other factors which are in excess of the requirements of the Tender documents or otherwise result in unsolicited benefits for the Employer shall not be taken into account in Tender evaluation.

25.4 The estimated effect of the price adjustment conditions under Clause 41 of the Conditions of Contract, during the implementation of the Contract, will not be taken into account in tender Evaluation

25.5 If the tender of the successful tenderer is seriously unbalanced in relation to the Employer's estimate of the cost of the work to be performed under the contract, the Employer may require the Tenderer to produce detailed price analyses for any or all items of the Bill of Quantities, to demonstrate the internal consistency of those prices with the construction methods and schedule proposed. After evaluation of the price analyses, the Employer may require that the amount of the performance security set forth in Clause 29 be increased at the expense of the successful Tenderer to a level sufficient to protect the Employer against financial loss in the event of default of the successful under the contract.

F. Award of Contract

26. Award criteria

26.1 Subject to Clause 27, the Employer will award the Contract to the Tenderer whose Tender has been determined to be substantially responsive to the Tender documents and who has offered the lowest evaluated Tender Price, provided that such Tenderer has been determined to be (a) eligible in accordance with the provisions of Clause 2, and (b) qualified in accordance with the provisions of Clause 3.

27. Employer's right to accept any Tender and to reject any or all Tenders

27.1 Notwithstanding Clause 26, the Employer reserves the right to accept or reject any Tender, and to cancel the Tender process and reject all Tenders, at any time prior to the award of Contract, without thereby incurring any liability to the affected Tenderer or Tenderers or any obligation to inform the affected Tenderer or Tenderers of the grounds for the Employer's action.

28. Notification of award and signing of Agreement

28.1 The Tenderer whose Tender has been accepted will be notified of the award by the Employer prior to expiration of the Tender validity period by cable, telex, e-mail or facsimile confirmed by registered letter. This letter (hereinafter and in the Conditions of Contract called the "Letter of Acceptance") will state the sum that the Employer will pay the Contractor in consideration of the execution, completion, and maintenance of the Works by the Contractor as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price").

28.2 The notification of award will constitute the formation of the Contract, subject only to the furnishing of Security deposit in accordance with the provisions of Clause 29.

28.3 The Agreement will incorporate all agreements between the Employer and the successful Tenderer. It will be kept ready for signature of the successful Tenderer in the office of Employer within 30 days following the notification of award along with the Letter of Acceptance. Within 20 days of receipt, the successful Tenderer will sign the Agreement and deliver it to the Employer.

28.4 Upon the furnishing by the successful Tenderer of the Performance Security, the Employer will promptly notify

the other Tenderers that their Tenders have been unsuccessful.

29. Security deposit

29.1 Within 20 days of receipt of the Letter of Acceptance, the successful Tenderer shall deliver to the Employer a Security deposit in the form of Bank Guarantee for an amount equivalent to 5% of the Contract price plus additional security for unbalanced tenders in accordance with Clause 25.5 of ITT and Clause 44 of the Conditions of Contract. :

1 - Bank guarantee in favour of ***Chairman, BWSSB*** payable at ***Bangalore***

2 in the form given in Section 10;

29.2 If the security deposit is provided by the successful Tenderer in the form of a Bank Guarantee, it shall be issued either by a Nationalized/Scheduled bank.

29.3 The security deposit if furnished in cash or demand draft can, if requested, be converted to interest bearing securities at the cost of the contractor.

29.4 Failure of the successful Tenderer to comply with the requirements of Sub-Clause 29.1 shall constitute sufficient grounds for cancellation of the award and forfeiture of the Earnest money deposit.

30 Advance Payment and Security:

30.1 The Employer will provide an advance payment on the contract price as stipulated in the Conditions of Contract, subject to the maximum amount as stated in the Contract Data.

31. Corrupt or Fraudulent practices

31.1 The GOK requires that the Tenderers/Suppliers/Contractors, observe the highest standard of ethics during the procurement and execution of such contracts. In pursuance of this policy, GOK :

(a) will reject a proposal for award if it determines that the Tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;

(b) will declare a firm ineligible, either indefinitely or for a stated period of time, to be awarded a GOK contract if it at any time determines that the firm has

engaged in corrupt or fraudulent practices in competing for, or in executing, a GOK contract.

31.2 Furthermore, Tenderers shall be aware of the provision stated in sub-clause 50.2 of the Conditions of Contract.

SECTION 3:

QUALIFICATION INFORMATION

The following form is to be downloaded, particulars are to be filled, scanned & uploaded by the Bidder, to the tender wizard of BWSSB **"**www.eproc.karnataka.gov.in**"** along with the Bid.

Note: The detailed procedure for downloading / uploading the documents will be available in Help wizard, Vendor manual & FAQ of the above mentioned Website.

The information to be filled in by the Tenderer hereunder will be used for purposes of computing Tender capacity as provided for in Clause 3 of the Instructions to Tenderers. This information will not be incorporated in the Contract.

1.1 Constitution or legal status of Tenderer [Attach copy]
Place of Registration
_____
(Attach Copy)

Principal place of business:
_____

1.2 Total value of civil engineering construction 2019-20
_____
works executed and payments received in the 2020-21
_____
last five years (in Rs. Lakhs)[1] 2021-22
_____
(Attach turnover certificate from Chartered Accounted along with 2022-23_____
balance sheets and P/L statement). 2023-24_____

1.3 Work performed as Prime Contractor (in the same name) on works of similar nature over during the five years specified in 1.2 above.

Project Name	Name of Employer	Description of Work	Contract Number	Value of contract Rs. Lakhs	Date of issue of work order	Specified period of completion	Actual date of completion	Remarks explaining reasons for delay in completion of

[1] Attach Certificate from Chartered Account by uploading the scanned copies

								work
1	2	3	4	5	6	7	8	9

1.4 Quantities of work executed as prime contractor (in the same name) during the last five years specified in 1.2 above:

Year	Name of Work	Name of Employer	Quantity of work performed (cum)[2]			Remarks (Indicate contract reference)
			Cement Concrete	Masonry	Earthworks	
2019-20						
2020-21						
2021-22						
2022-23						
2023-24						

1.5 Information on works for which Tenders have been submitted and works which are yet to be completed as on the date of this Tender.

(A) <u>Existing commitments and on-going works:</u>

Description of Work	Place& State	Contract No. & Date	Name and Address of Employer	Value of Contract (Rs. lakhs)	Stipulated period of completion	Value of works[3] remaining to be completed (Rs. lakhs)	Anticipated date of completion
1	2	3	4	5	6	7	8

(B) <u>Works for which Tenders already submitted</u>:

Description of Work	Place & State	Name and Addres	Estimated value of works	Stipulated Date period of	when decision is	Remarks if any

[2] Items of work for which data is requested should tally with that specified in ITT Clause 3

[3] Contractor shall enclose / attach / up load all necessary certificates duly attested by the employer

		s of Employer	(Rs. lakhs)	completion	expected	
1	2	3	4	5	6	7

1.6. The following items of equipment are considered essential for successfully carrying out the works. The Tenderer should furnish all the information listed below.

Item of Equipment	Requirement[4]			Owned and available		Remarks
	No.	Capacity	Owned	Number/ Capacity	Age/ Condition	

1.7 Reports on the financial standing of the tenderer, such as profit and loss statements and auditor's reports for the last five years;

1.8 Qualification and experience of the key technical and management personnel in permanent employment with the tenderer and those that are proposed to be deployed on this contract, if awarded.

1.9. Name, address, and telephone, telex, and fax numbers of the Tenderers' bankers who may provide references if contacted by the Employer.

1.10 Evidence of access to financial resources to meet the qualification requirement specified in ITT Clause3.3 (b): Cash in hand, Letter of Credit etc. List them below and attach certificate from the Banker in the suggested format as under:

FORMAT OF BANKER'S CERTIFICATE /LINE OF CREDIT LETTER [TO BE ISSUED IN THE LETTER HEAD OF THE BANK BRANCH]

Reference Number (Sl No.) Place
Date
To
(Name & Address of the beneficiary)

This is to certify that Mr./ M/s. ..... [name of the customer] having is /their registered/administrative office at.....is a customer of our bank and are engaged

[4] The Item of equipment, required number and capacity should match with those in ITT Clause 3.3(a) (Filled scanned & uploaded)

in……(nature of activity). If the …..customer is allotted/awarded with ……(brief details of works], we may extend credit facilities upto Rs……. lakh, to meet his /their working capital requirement towards the execution of the said work order as per Loan policy of the Bank.

This credit is valid upto three months from the date of issue, that is upto dd/mm/yyyy.

Sd/-
Name of the Bank, Branch
Manger
Address:
……

1.11 Proposals for subcontracting components of works amounting to more than 20% of the contract price .

Item of Work	Value of Sub-Contract	Identified Sub-Contractor (Name and address)	Experience of similar work [5]

1.12 Information on litigations in which the Tenderer is involved:

Other Party (ies)	Employer	Details of dispute	Amount involved	Remarks showing present status

1.13 The proposed methodology and program of construction, backed with equipment planning and deployment, duly supported with broad calculations and quality control procedures proposed to be adopted, justifying their capability of execution and completion of the work as per technical specifications within the stipulated period of completion as per milestones.

[5] Attach Certificate from the respective Employers (scanned & Uploaded)

SECTION 4:

FORM OF TENDER, LETTER OF ACEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM

Form of Tender

Description of the Works: Work of providing & laying UGD sub-main of 400mm dia, lateral linking along with manual jacking in Herohalli village coming under 110 villages of BBMP and other works.

Tender

To

Chief Engineer (Project)
Bangalore Water Supply and Sewerage Board,
3rd Floor, Cauvery Bhavan,
K.G. Road, Bangalore560009
Karnataka, India.

GENTLEMEN,

We offer to execute the Works described above in accordance with the Conditions of Contract accompanying this Tender.

This Tender and your written acceptance of it shall constitute a binding contract between us. We understand that you are not bound to accept the lowest or any Tender you receive.

The advance payment is required Rs……

We undertake that, in competing for (and, if the award is made to us, in executing) the above contract, we will strictly observe the laws against fraud and corruption in force in India namely "Prevention of Corruption Act 1988".

We hereby confirm that this Tender complies with the Tender validity and Earnest money deposit required by the Tender documents.

We attach herewith our current income-tax clearance certificate.

Yours faithfully,

Authorized Signature:

Name & Title of Signatory:

_____

Name of Tenderer _____

Address: ----------

NOTE: This form shall be download, filled and printed on the Company letter head, Signed, Scanned and uploaded. Failure to furnish the signed copy will lead to Non-Responsive Tender. The disclosure of financial bid in technical bid, will be treated as technically non-responsive.

Letter of Acceptance

(letterhead paper of the Employer)

_____[date]

To:

_____
_____[name and address of the Contractor]

Dear Sirs,

This is to notify you that your Tender dated _____ for execution of the _____
_____ [name of the contract and identification number, as given in the Instructions to Tenderers] for the Contract Price of Rupees ——_____ (_____) [amount in words and figures], as corrected and modified in accordance with the Instructions to Tenderers is hereby accepted by our Agency.

You are hereby requested to furnish Security deposit plus additional security for unbalanced tenders in terms of Clause 25.5 of ITT, in the form detailed in Clause 29.1 of ITT for an amount of Rs. ———— within 20 days of the receipt of this letter of acceptance valid up to 30 days from the date of expiry of Defects Liability Period i.e. up to ..... and sign the contract, failing which action as stated in Para 29.4 of ITT will be taken.

Yours faithfully,

Authorized Signature
Name and Title of Signatory
Name of Agency

Issue of Notice to proceed with the work

(letterhead of the Employer)

———— (date)

To
————————————— (name and address of the Contractor)
—————————————

——————————————————

Dear Sirs:

Pursuant to your furnishing the requisite security deposit as stipulated in ITT Clause 29.1 and signing of the contract agreement for the construction of ————————[name of the contract] a Tender Price of Rs.————————, you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

(Signature, name and title of signatory authorized to sign on behalf of Employer)

Agreement Form

Agreement

This agreement, made the _____day of _____20_____, between_____ _____[name and address of Employer] (hereinafter called "the Employer") of the one part and _____ _____ _____ _____ __ _____[name and address of contractor] (hereinafter called "the Contractor") of the other part.

Whereas the Employer is desirous that the Contractor execute _____ _____ _____ _____[name and identification number of Contract] (hereinafter called "the Works") and the Employer has accepted the Tender by the Contractor for the execution and completion of such Works and the remedying of any defects therein at a contract price of Rupees.....

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
   i) Letter of Acceptance;
   ii) Notice to proceed with the works;
   iii) Contractor's Tender;
   iv) Contract Data;

v) Conditions of contract (including Special Conditions of Contract);
vi) Specifications;
vii) Drawings;
viii) Bill of Quantities; and
ix) Any other document listed in the Contract Data as forming part of the contract.

5. Jurisdiction of Courts/Arbitration: The sitting of arbitration shall be held at Bangalore only and nowhere else.

6. Dispute of any kind arising out of the contract shall be resolved within the jurisdiction of Bangalore City only and the parties agree and clearly understand that the courts/tribunals situated at Bangalore Metropolitan City have exclusive jurisdiction for the redressal of the disputes arising out of the contract and at no other place.

7. The Parties further agree and understand that the place or places of issue of bank guarantee other than Bangalore will have no jurisdiction to resolve dispute of any kind relating to enforcement of the bank guarantees submitted by the contractor at Bangalore for the execution of the contract at Bangalore.

8. The contractor shall comply with all the legal requirements in the matter of employment of workmen and provide all safety gadgets to the workmen while working in the hazards place or conditions during the execution of the contract.

9. Contractor shall be fully responsible in the event of death of employee/workman during the execution of the work and liable to pay adequate compensation to the dependents of employee/workman as per law.

10. On his/their failure, if the Board is made to pay compensation the same shall be recovered by the Board from the contractor out of the amounts due to the contractor or by appropriate legal action.

11. If death of any employees occurs during execution of work due to negligence of contractor, the contract will be liable for termination.

12. In the event of such termination, the employer may consider blacklisting of firm after due notice.

13. In case of any death or accident the contract will be cancelled after following due process.

14. The Board will be entitled to claim exemplary damages from the contractor in case of death of any work man / employees of the

contractor in any of the BWSSB works as it damages the reputation of the Board.

15. Road cutting machine should be used mandatorily while executing the work.

16. Any utilities encountered during execution if damaged by the contractor, the same need to be rectified immediately without any delay at his own cost with due approval from the concerned.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of _____
was hereunto affixed in the presence of:
Signed, Sealed and Delivered by the said
_____
_____
_____

in the presence of:
Binding Signature of Employer
_____
Binding Signature of Contractor
_____

SECTION 5:

CONDITIONS OF CONTRACT

Table of Contents

A. General **Page No.**

1. Definitions 35
2. Interpretation 36
3. Law governing contract 36
4. Employers decisions 36
5. Delegation 37
6. Communications 37
7. Subcontracting 37
8. Other Contractors 37
9. Personnel 37
10. Employer's and Contractor's risks 37
11. Employer's risks 37
12 Contractor's risks 38
13. Insurance 38
14. Site Investigation Report 39
15 Query about Contract Data 39
16 Contractor to construct the Works 39
17. The Works to be completed by Intended Completion Date 39
18 Approvals by the Employer 39
19. Safety 39
20. Discoveries 39
21. Possession of the Site 39
22. Access to the Site 40
23. Instructions 40
24. Procedure for resolution of disputes 40

B. Time Control

25. Program 40
26. Extension of the Intended Completion Date 40
27. Delays ordered by the Employer 41
28. Management meetings 41

C. Quality Control

29. Identifying defects 41
30. Tests 41
31. Correction of defects 41
32. Uncorrected defects 41

D. Cost Control

33 Bill of Quantities (BOQ) 42
34 Variations 42
35. Payment for Variations 42
36. Submission of bills for payment 43
37 Payments 43

38. Compensation events 43
39. Tax 44
40 Price Adjustment 44
41. Liquidated damages 44
42. Advance Payments 45
43. Securities 45
44. Cost of repairs 44

E Finishing of Contract
45. Completion 45
46. Taking Over 46
47. Final account 46
48. As built drawings and/or Operating and Maintenance Manuals 46
49. Termination 46
50 Payment upon termination 47
51. Property 47
52. Release from performance 47

F Special Conditions of Contract 48

Conditions of Contract

A. General

1. Definitions

1.1 Terms which are defined in the Contract Data are not also defined in the Conditions of Contract but keep their defined meanings. Bold letters are used to identify defined terms.

Bill of Quantities means the priced and completed Bill of Quantities forming part of the Tender.

Compensation events are those defined in Clause 38 hereunder.

The **Completion Date** is the date of completion of the Works as certified by the Employer in accordance with Sub Clause 46.1.

The **Contract** is the contract between the Employer and the Contractor to execute, complete and maintain the Works. It consists of the documents listed in Clause 2.2 below.

The **Contract Data** defines the documents and other information which comprise the Contract.

The **Contractor** is a person or corporate body whose Tender to carry out the Works has been accepted by the Employer.

The **Contractor's Tender** is the completed Tender document submitted by the Contractor to the Employer.

The **Contract price** is the price stated in the Letter of Acceptance and thereafter as adjusted in accordance with the provisions of the Contract.

Days are calendar days; months are calendar months.

A **Defect** is any part of the Works not completed in accordance with the Contract.

The **Defects liability period** is the period named in the Contract Data and calculated from the Completion Date.

The **Employer** is the party who will employ the Contractor to carry out the Works.

Equipment is the Contractor's machinery and vehicles brought temporarily to the Site to construct the Works.

The **Initial Contract price** is the Contract Price listed in the Employer's Letter of Acceptance.

The **Intended Completion Date** is the date on which it is intended that the Contractor shall complete the Works. The Intended Completion Date is specified in the Contract Data. The

Intended Completion Date may be revised only by the Employer by issuing an extension of time.

Materials are all supplies, including consumables, used by the contractor for incorporation in the Works.

Plant is any integral part of the Works which is to have a mechanical, electrical, electronic or chemical or biological function.

The **Site** is the area defined as such in the Contract Data.

Specification means the Specification of the Works included in the Contract and any modification or addition made or approved by the Employer.

The **Start Date** is given in the Contract Data. It is the date when the Contractor shall commence execution of the works. It does not necessarily coincide with any of the Site Possession Dates.

A **Subcontractor** is a person or corporate body who has a Contract with the Contractor to carry out a part of the work in the Contract which includes work on the Site.

A **Variation** is an instruction given by the Employer which varies the Works.

The **Works** are what the Contract requires the Contractor to construct, install, and turn over to the Employer, as defined in the Contract Data.

2. Interpretation

2.1 In interpreting these Conditions of Contract, singular also means plural, male also means female or neuter, and the other way around. Headings have no significance. Words have their normal meaning under the language of the Contract unless specifically defined. The Employer will provide instructions clarifying queries about the Conditions of Contract.

2.2 The documents forming the Contract shall be interpreted in the following order of priority:

(1) Agreement
(2) Letter of Acceptance, notice to proceed with the works
(3) Contractor’s Tender
(4) Contract Data
(5) Conditions of Contract
(6) Specifications
(7) Drawings
(8) Bill of quantities and
(9) any other document listed in the Contract Data as forming part of the Contract.

3. Law governing contract

3.1 The law governing the Contract is the Laws of India supplanted by the Karnataka Local Acts.

4. Employer's decisions

4.1 Except where otherwise specifically stated, the Employer will decide contractual matters between the Employer and the Contractor.

5. Delegation

5.1 The Employer may delegate any of his duties and responsibilities to other people after notifying the Contractor and may cancel any delegation after notifying the Contractor.

6. Communications

6.1 Communications between parties which are referred to in the conditions are effective only when in writing. A notice shall be effective only when it is delivered (in terms of Indian Contract Act).

7. Subcontracting

7.1 Deleted

8. Other Contractors

8.1 The Contractor shall cooperate and share the Site with other contractors, public authorities, utilities, and the Employer.

9. Personnel

9.1 The Contractor shall employ the technical personnel (of number and qualifications) as may be stipulated by GOK from time to time during the execution of the work. The technical staff so employed shall be available at site as may be stipulated by the Employer.

9.2 If the Employer asks the Contractor to remove a person who is a member of the Contractor's staff or his work force stating the reasons, the Contractor shall ensure that the person leaves the Site within seven days and has no further connection with the work in the Contract.

10. Employer's and Contractor's risks

10.1 The Employer carries the risks which this Contract states are Employer's risks, and the Contractor carries the risks which this Contract states are Contractor's risks.

11. Employer's risks

11.1 The Employer is responsible for the excepted risks which are:

(a) rebellion, riot commotion or disorder unless solely restricted to employees of the Contractor or his Sub-Contractors arising from the conduct of the Works; or

(b) a cause due solely to the design of the Works, other than the Contractor's design; or

(c) any operation of the forces of nature (in so far as it occurs on the Site) which an experienced contractor:
(i) could not have reasonably foreseen; or
(ii) could reasonably have foreseen, but against which he could not reasonably have taken at least one of the following measures;
(A) prevent loss or damage to physical property from occurring by taking appropriate measures or
(B) insure against such loss or damage

12. Contractor's risks

12.1 All risks of loss of or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract other than the excepted risks are the responsibility of the Contractor.

13. Insurance:

13.1 The Contractor shall prior to commencing the works, effect and thereafter maintain insurances , in the joint names of the Employer and the Contractor, (cover from the first working day after the Start Date to the end of Defects Liability Period), in the amounts stated in the Contract Data :
(a) for loss of or damage to the Works, Plants and Materials and the Contractor's equipment;
(b) for liability of both Parties for loss, damage, death and injury to third parties or their property arising out of the Contractor's performance of the Contract including the Contractor's liability for damage to the Employer's property other than the Works and
(c) for liability of both Parties and of any Employer's representative for death and injury to the Contractor's personnel except to the extent that liability arises from the negligence of the Employer, any Employer's representative or their Employees.

13.2 Policies and certificates for insurance shall be delivered by the Contractor to the Employer for his approval before the Start Date. All such insurance shall provide for compensation to be payable to rectify the loss or damage incurred. All payments received from insurers relating to loss or damage shall be held jointly by the Parties and used for the repair of the loss or damage or as compensation for loss or damage that is not to be repaired.

13.3 If the Contractor fails to effect or keep in force any of the insurances referred to in the previous sub-clauses or fails to provide satisfactory evidence, policies or receipts, the Employer

may without prejudice to any other right or remedy, effect insurance for the cover relevant to such default and pay the premiums due and recover the same as a deduction from any other monies due to the Contractor. If no payment is due, the payment of the premiums shall be a debt due.

13.4 Alterations to the terms of insurance shall not be made without the approval of the Employer.

13.5 Both Parties shall comply with any conditions of the insurance policies.

14. Site Investigation Reports:

14.1 The Contractor, in preparing the tender, shall rely on any site investigation reports referred to in the Contract data, supplemented by any information available to the Tenderer.

15. Queries about the Contract Data

15.1 The Employer will clarify queries on the Contract Data.

16. Contractor to construct the Works

16.1 The Contractor shall construct the Works in accordance with the Specification and Drawings.

17. The Works to be completed by the Intended Completion Date

17.1 The Contractor may commence execution of the Works on the Start Date and shall carry out the Works in accordance with the program submitted by the Contractor, as updated with the approval of the Employer, and complete them by the Intended Completion Date.

18. Approval by the Employer:

18.1 The Contractor shall submit Specification and drawings showing the proposed Temporary Works to the Employer, who is to approve them if they comply with the Specifications and Drawings.

18.2 The Contractor shall be responsible for the design of Temporary Works

18.3 The Employer’s approval shall not alter the Contractor’s responsibility for design of the Temporary Works.

18.4 The Contractor shall obtain approval of third parties to the design of third parties to the design of the temporary Works where required.

18.5 All Drawings prepared by the Contractor for the execution of the temporary or permanent Works, are subject to prior approval by the Employer before their use.

19. Safety

19.1 The Contractor shall be responsible for the safety of all activities on the Site.

20. Discoveries

20.1 Anything of historical or other interest or of significant value unexpectedly discovered on the Site is the property of the Employer. The Contractor is to notify the Employer of such discoveries and carry out the Employer's instructions for dealing with them.

21. Possession of the Site

21.1 The Employer shall give possession of all parts of the Site to the Contractor. If possession of a part is not given by the date stated in the Contract Data the Employer is deemed to have delayed the start of the relevant activities and this will be Compensation Event.

22. Access to the Site

22.1 The Contractor shall allow the Employer and any person authorized by the Employer access to the Site, to any place where work in connection with the Contract is being carried out or is intended to be carried out and to any place where materials or plant are being manufactured / fabricated / assembled for the works.

23. Instructions

23.1 The Contractor shall carry out all instructions of the Employer which comply with the applicable laws where the Site is located.

24. Procedure for resolution of Disputes:

24.1 If the Contractor is not satisfied with the decision taken by the Employer, the dispute shall be referred by either party to Arbitration within 30 days of the notification of the Employer’s decision.

24.2 If neither party refers the dispute to Arbitration within the above 30 days, the Employer’s decision will be final and binding.

24.3 The Arbitration shall be conducted in accordance with the arbitration procedure stated in the Special Conditions of Contract.

B. Time Control

25. Program

25.1 Within the time stated in the Contract Data the Contractor shall submit to the Employer for approval a Program showing the general methods, arrangements, order, and timing for all the activities in the Works.

25.2 The Employer's approval of the Program shall not alter the Contractor's obligations. The Contractor may revise the Program and submit it to the Employer again at any time. A revised Program is to show the effect of Variations and Compensation Events.

26. Extension of the Intended Completion Date

26.1 The Employer shall extend the Intended Completion Date if a Compensation Event occurs or a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date.

26.2 The Employer shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor asking the Employer for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information.

27. Delays ordered by the Employer

27.1 The Employer may instruct the Contractor to delay the start or progress of any activity within the Works.

28. Management meetings

28.1 The Employer may require the Contractor to attend a management meeting. The business of a management meeting shall be to review the progress achieved and the plans for remaining work.

28.2 The responsibility of the parties for actions to be taken is to be decided by the Employer either at the management meeting or after the management meeting and stated in writing to be distributed to all who attended the meeting.

C. Quality Control

29. Identifying defects

29.1 The Employer shall check the Contractor's work and notify the Contractor of any Defects that are found. Such checking shall not affect the Contractor's responsibilities. The Employer may instruct the Contractor to search for a Defect and to uncover and test any work that the Employer considers may have a Defect

30. Tests

30.1 If the Employer instructs the Contractor to carry out a test not specified in the Specification to check whether any work has a Defect and the test shows that it does, the Contractor shall pay for the test and any samples. If there is no Defect the test shall be a Compensation Event.

31. Correction of defects

31.1 The Employer shall give notice to the Contractor of any Defects before the end of the Defects Liability Period, which begins at Completion and is defined in the Contract Data. The Defects Liability Period shall be extended for as long as Defects remain to be corrected.

31.2 Every time notice of a Defect is given, the Contractor shall correct the notified Defect within the length of time specified by the Employer’s notice.

32. Uncorrected defects

32.1 If the Contractor has not corrected a Defect within the time specified in the Employer’s notice, the Employer will assess the cost of having the Defect corrected, and the Contractor will pay this amount.

D. Cost Control

33. Bill of Quantities (BOQ)

33.1 The BOQ shall contain items for the construction, installation, testing, and commissioning work to be done by the Contractor.

33.2 The BOQ is used to calculate the Contract Price. The Contractor is paid for the quantity of the work done at the rate in the BOQ for each item

34. Variations

34.1 The Employer shall have power to order the Contractor to do any or all of the following as considered necessary or advisable during the progress of the work by him

(a) Increase or decrease of any item of work included in the Bill of Quantities (BOQ);
(b) Omit any item of work;
(c) Change the character or quality or kind of any item of work;
(d) Change the levels, lines, positions and dimensions of any part of the work;
(e) Execute additional items of work of any kind necessary for the completion of the works; and
(f) Change in any specified sequence, methods or timing of construction of any part of the work.

34.2 The Contractor shall be bound to carry out the work in accordance with any instructions in this connection, which may be given to him in writing by the Employer and such alteration shall not vitiate or invalidate the contract.

34.3 Variations shall not be made by the Contractor without an order in writing by the Employer, provided that no order in writing shall be required for increase or decrease in the quantity of an item appearing in the BOQ so long as the work executed conforms to the approved drawings.

34.4 The Contractor shall promptly request in writing the Employer to confirm verbal orders and the officer issuing oral instructions shall confirm it in writing with in 30days, failing which the work shall be carried out as though there is no variation. In case variation is approved, it shall be accompanied by BOQ, failing which the contractor shall be responsible for deviation, if any.

35. Payments for Variations

35.1 Payment for increase in the quantities of an item in the BOQ up to 25% of that provided in the Bill of Quantities shall be made at the rates quoted by the Contractor.

35.2 For quantities in excess of 125% of the tendered quantity of an item as given in the BOQ, the Contractor shall be paid at the rate entered in or derived from in the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract.

35.3 If there is no rate for the additional, substituted or altered item of the work in the BOQ, efforts would be made to derive the rates from those given in the BOQ or the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) and if found feasible the payment would be made at the derived rate for the item plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract

35.4 If the rates for additional, substituted or altered item of work cannot be determined either as at 35.1 or 35.2 or 35.3 above, the Contractor shall be requested to submit his quotation for the items supported by analysis of the rate or rates claimed, within 7 days.

1 35.5 If the Contractor's quotation is determined unreasonable, the Employer may order the Variation and make a change to the Contract Price which shall be based on Employer’s own forecast of the effects of the Variation on the Contractor's costs.

35.6 If the Employer decides that the urgency of varying the work would prevent a quotation being given and considered without delaying the work, no quotation shall be given and the Variation shall be treated as a Compensation Event.

35.7 Under no circumstances the Contractor shall suspend the work on the plea of non-settlement of rates for items falling under this Clause.

36. Submission of bills for payment

36.1 The Contractor shall submit to the Employer monthly bills of the value of the work completed less the cumulative amount paid previously.

36.2 The Employer shall check the Contractor's bill and determine the value of the work executed which shall comprise of (i) value of the quantities of the items in the BOQ completed and (ii) valuation of Variations and Compensation Events.

36.3 The Employer may exclude any item paid in a previous bill or reduce the proportion of any item previously paid in the light of later information.

37. Payments

37.1 Payments shall be adjusted for deductions for advance payments, other recoveries in terms of the contract and taxes, at source, as applicable under the law. The Employer shall pay the Contractor the within 60 days of submission of bill. The Contractor shall be liable to pay liquidated damages for shortfall in progress. For Progress beyond the agreed program, payment is subject to availability of the grants.

37.2 Items of the Works for which no rate or price has been entered in will not be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

38. Compensation events

38.1 The following are Compensation events unless they are caused by the Contractor:

(a) The Employer does not give access to a part of the Site by the Site Possession Date stated in the Contract Data.
(b) The Employer orders a delay or does not issue drawings, specifications or instructions required for execution of works on time.
(c) The Employer instructs the Contractor to uncover or to carry out additional tests upon work which is then found to have no Defects.
(d) The Employer gives an instruction for dealing with an unforeseen condition, caused by the Employer, or additional work required for safety or other reasons.
(e) The effect on the Contractor of any of the Employer’s Risks.
(f) The Employer unreasonably delays issuing a Certificate of Completion.
(g) Other Compensation Events listed in the Contract Data or mentioned in the Contract.

38.2 If a Compensation Event would cause additional cost or would prevent the work being completed before the Intended Completion Date, the Contract Price shall be increased and/or the Intended Completion Date is extended. The Employer shall decide whether and by how much the Contract Price shall be increased and whether and by how much the Intended Completion Date shall be extended.

38.3 As soon as information demonstrating the effect of each Compensation event upon the Contractor's forecast cost has been provided by the Contractor, it is to be assessed by the Employer and the Contract Price shall be adjusted accordingly. If the Contractor's forecast is deemed unreasonable, the Employer shall adjust the Contract Price based on Employer’s own forecast. The Employer will assume that the Contractor will react competently and promptly to the event.

38.4 The Contractor shall not be entitled to compensation to the extent that the Employer's interests are adversely affected by the Contractor not having given early warning or not having cooperated with the Employer.

39. Tax

39.1 The rates quoted by the Contractor shall be deemed to be inclusive of the sales and other taxes that the Contractor will have to pay for the performance of this Contract. The Employer will perform such duties in regard to the deduction of such taxes at source as per applicable law.

40. Price Adjustment:

40.1 Contract price shall be adjusted for increase or decrease in rates and prices of materials, fuels and lubricants in accordance with the following principles and procedures and as per formulae given in the Contract Data.

1 (a) The price Adjustment shall apply for the work done from the date of commencement up to the end of original period of completion or extensions granted by the Employer and shall not apply to work carried out beyond the stipulated period of completion for reasons attributable to the Contractor;
2
3 (b) Price Adjustment shall be admissible from the date of opening of tenders (original or extended)
4 (c) The price adjustment shall be determined during each quarter from the formulae given in Contract Data.
5 (d) Following expressions and meanings are assigned to the work done during the quarter:

R = Total value of work done during the quarter. It will exclude value for works executed under variations for which price adjustment (if any) will be worked out separately based on the terms mutually agreed.

40.2 To the extent that full compensation for any rise or fall in costs to the contractor is not covered by the provisions of this or other Clauses in the Contract, the unit rates included in the contract shall be deemed to include amounts to cover the contingency of such other rise or fall in costs.

41. Liquidated damages

41.1 The Contractor shall pay liquidated damages to the Employer at the rate per day stated in the Contract Data for each day that the Completion Date is later than the Intended Completion Date (for the whole of the works or the milestone as stated in the

Contract Data). The total amount of liquidated damages shall not exceed the amount defined in the Contract Data. The Employer may deduct liquidated damages from payments due to the Contractor. Payment of liquidated damages does not affect the Contractor's liabilities.

41.2 If the Intended Completion Date is extended after liquidated damages have been paid, the Employer shall correct any overpayment of liquidated damages by the Contractor by adjusting the next payment of bill.

42. Advance Payments:

42.1 The Employer shall make payment to the Contractor of the amounts stated in the Contract Data by the date stated in the Contract Data, against provision by the Contractor of an unconditional bank guarantee in a form acceptable to the Employer issued by a Nationalized/Scheduled Bank in amounts equal to the advance payment. The guarantee shall remain effective until the advance payment has been repaid, but the amount of the guarantee shall be progressively reduced by the amounts repaid by the Contractor. Interest will not be charged on the advance payment.

42.2 The Contractor is to use the advance payment only to pay for Mobilization expenses required specifically for execution of the Works. The Contractor shall demonstrate that advance payment has been used in this way by supplying copies of invoices or other documents to the Employer.

42.3 The advance payment shall be repaid by deducting proportionate amounts from payments otherwise due to the Contractor, following the schedule of completed percentages of the Works on a payment basis. No account shall be taken of the advance payment or its repayment in assessing valuation of the work done, variations, price adjustments, compensation events or liquidated damages.

43. Securities:

43.1 The Security deposit (including additional security for unbalanced tenders) shall be provided to the Employer no later than the date specified in the Letter of Acceptance and shall be issued in an amount and form and type of instrument acceptable to the Employer. The Security deposit shall be valid until a date 30 days from the date of expiry of Defects Liability Period and the additional security for unbalanced tenders shall be valid until a date 30 days from the date of issue of the certificate of completion.

44. Cost of Repairs:

44.1 Loss or damage to the Works or Materials to be incorporated in the Works between the Start Date and the end of the Defects Correction periods shall be remedied by the Contractor at the Contractor's cost if the loss or damage arises from the Contractor's acts or omissions.

E. Finishing the Contract

45. Completion

45.1 The Contractor shall request the Employer to issue a Certificate of Completion of the Works and the Employer will do so upon deciding that the Work is completed.

46. Taking over

46.1 The Employer shall take over the Site and the Works within seven days of issuing a certificate of Completion.

47. Final account

47.1 The Contractor shall supply to the Employer a detailed account of the total amount that the Contractor considers payable under the Contract before the end of the Defects Liability Period. The Employer shall issue a Defect Liability Certificate and certify any final payment that is due to the Contractor within 90 days of receiving the Contractor's account if it is correct and complete. If it is not, the Employer shall issue within 90 days a schedule that states the scope of the corrections or additions that are necessary. If the Final Account is still unsatisfactory after it has been resubmitted, the Employer shall decide on the amount payable to the Contractor and make payment within 60 days of receiving the Contractor’s revised account.

48. As built drawings and /or Operating and Maintenance Manuals

48.1 If “as built”[6] Drawings and/or operating and maintenance manuals are required, the Contractor shall supply them by the dates stated in the Contract Data.

48.2 If the Contractor does not supply the Drawings by the dates stated in the Contract Data, or they do not receive the Employer’s approval, the Employer shall withhold the amount stated in the Contract Data from payments due to the Contractor.

49. Termination

[6] Completion Drawings

49.1 The Employer may terminate the Contract if the other party causes a fundamental breach of the Contract.

49.2 Fundamental breaches of Contract include, but shall not be limited to the following:

(a) the Contractor stops work for 45 days when no stoppage of work is shown on the current Program and the stoppage has not been authorized by the Employer;

(b) The Contractor becomes bankrupt or goes into liquidation other than for a reconstruction or amalgamation;

(c) the Employer gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Employer;

(d) the Contractor does not maintain a security which is required;

(e) the Contractor has delayed the completion of works by the number of days for which the maximum amount of liquidated damages can be paid as defined in the Contract data; and

(f) if the Contractor, in the judgment of the Employer has engaged in corrupt or fraudulent practices in competing for or in the executing the Contract.

For the purpose of this paragraph : “corrupt practice” means the offering, giving, receiving or soliciting of any thing of value to influence the action of a public official in the procurement process or in contract execution. “Fraudulent practice” means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Borrower, and includes collusive practice among Tenderers (prior to or after Tender submission) designed to establish Tender prices at artificial non-competitive levels and to deprive the Borrower of the benefits of free and open competition.”

49.3 When either party to the Contract gives notice of a breach of contract to the Employer for a cause other than those listed under Sub Clause 49.2 above, the Employer shall decide whether the breach is fundamental or not.

49.4 Notwithstanding the above, the Employer may terminate the Contract for convenience.

49.5 If the Contract is terminated the Contractor shall stop work immediately, make the Site safe and secure and leave the Site as soon as reasonably possible.

50. Payment upon Termination

50.1 If the Contract is terminated because of a fundamental breach of Contract by the Contractor, the Employer shall prepare bill for the value of the work done less advance payments received up to the date of the bill, less other recoveries due in terms of the contract, less taxes due to be deducted at source as per applicable law and less the percentage to apply to the work not completed as indicated in the Contract Data. Additional Liquidated Damages shall not apply. If the total amount due to the Employer exceeds any payment due to the Contractor the difference shall be a debt payable to the Employer.

50.2 If the Contract is terminated at the Employer's convenience or because of a fundamental breach of Contract by the Employer, the Employer shall prepare bill for the value of the work done, the reasonable cost of removal of Equipment, repatriation of the Contractor's personnel employed solely on the Works, and the Contractor's costs of protecting and securing the Works and less advance payments received up to the date of the certificate, less other recoveries due in terms of the contract, and less taxes due to be deducted at source as per applicable law and make payment accordingly.

51. Property

51.1 All materials on the Site, Plant, Equipment, Temporary Works and Works are deemed to be the property of the Employer, if the Contract is terminated because of a Contractor’s default.

52. Release from performance

52.1 If the Contract is frustrated by any event entirely outside the control of either the Employer or the Contractor the Employer shall certify that the Contract has been frustrated. The Contractor shall make the Site safe and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which commitment was made

F. Special Conditions of Contract

1. Labour :

The Contractor shall, unless otherwise provided in the Contract, make his own arrangements for the engagement of all staff and labour, local or other, and for their payment, housing, feeding and transport.

The Contractor shall, if required by the Employer, deliver to the Employer a return in detail, in such form and at such intervals as the Employer may prescribe, showing the staff and the numbers of the several classes of labour from time to time employed by the Contractor on the Site and such other information as the Employer may require.

2. Compliance with labour regulations :

During continuance of the contract, the Contractor and his sub contractors shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the State or Central Government or local authority and any other labour law (including rules), regulations, bye laws that may be passed or notification that may be issued under any labour law in future either by the State or the Central Government or the local authority. The Contractor shall keep the Employer indemnified in case any action is taken against the Employer by the competent authority on account of contravention of any of the provisions of any Act or rules made there under, regulations or notifications including amendments. If the Employer is caused to pay or reimburse, such amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated in the notifications/bye laws/Acts/Rules/regulations including amendments, if any, on the part of the Contractor, Employer shall have the right to deduct any money due to the Contractor including his amount of security deposit. The Employer shall also have right to recover from the Contractor any sum required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor and the Sub-Contractor in no case shall be treated as the employees of the Employer at any point of time.

3. Protection of Environment:

The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor and his sub-contractors shall abide at all times by all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect

in future by the State or Central Government or the local authority.

4. Arbitration (Clause 24)

4.1 General Conditions of Dispute Adjudication Board Agreement.

If any dispute arises between the parties in connection with, or arising out of , the Contract or the execution of the works shall be adjudicated by the DBA comprising of 3 members constitute by:

a. Additional Chief Engineer, BWSSB as Employer representative,
b. The " Contractor", and
c. The "Member" third party who is being identified/nominated jointly by both Employer and Contractor.

If either party is dissatisfied with the DAB's decision, then either Party may, within 28days after receiving the decision, give Notice to the other party of its dissatisfaction. If the DAB fails to give its decision within period prescribed, then either party may, within 28 days after this period has expired, give Notice to the other Party of its dissatisfaction. Then only the procedure of 4.2 shall be initiated.

4.2 The procedure for arbitration shall be as follows:

(a) In case of dispute or difference arising between the Employer and the Contractor relating to any matter arising out of or connected with this agreement it shall be settled in accordance with the Arbitration and Conciliation Act 1996. The disputes or differences shall be referred to a Sole Arbitrator. The Sole Arbitrator shall be appointed by agreement between the parties; failing such agreement, by the Appointing Authority (any one of the Organizations as per list enclosed in Annexure)

(b) Arbitration proceedings shall be held at ***Bangalore***, Karnataka, India

(c) The cost and expenses of arbitration proceedings will be paid as determined by the Arbitrator. However the expenses incurred by each party in connection with the preparation, presentation, etc., shall be borne by each party itself.

(d) Performance under the contract shall continue during the arbitration proceedings and payments due the Contractor by the Employer shall not be withheld, unless they are the subject matter of the arbitration proceedings.

Annexure:

LIST OF ORGANIZATIONS WHO ARE CONSIDERED AS APPOINTING AUTHORITY FOR APPOINTMENT OF ARBITRATORS

1 1. Indian Council of Arbitration, India;
2 2. International Centre for Alternative Disputes Resolution (India);
3 3. Indian Roads Congress;
4 4. Indian Building Congress;
5 5. Indian Institute of Bridge Engineers;
6 6. Indian Institute of Public Health Engineers;
7 7. Institute of Water Works

5 Contractor to Co-ordinate his Work with Other Contractors

5.1 The Contractor has to co-ordinate with the other concerned Contractors as already specified in Conditions of Contract for all such works as per the directions of Engineer in charge at no extra cost.

6 **Continuation of Work:**

6.1 In case of the death of a contractor after executing the agreement / commencement of the work, his legal heir, if any eligible registered contractor and willing, can execute and complete the work at the accepted tender rates irrespective of the cost of the work.

7.0 The contractor shall ensure the ESI and Provident Fund registration of the workers/labourers engaged in the work as per the Labour laws.

7. **Jurisdiction of Courts /Arbitration**: The sitting of Arbitration shall be held at Bangalore only and nowhere else. Dispute of any kind arising out of the contract shall be resolved within the jurisdiction of Bangalore City only and the parties agree and clearly understand that the courts / tribunals situated at Bangalore Metropolitan City have exclusive jurisdiction for the redressal of the disputes arising out of the contract and at no other place.
8. The parties further agree and understand that the place or places of issue of Bank Guarantee other than Bangalore will have no jurisdiction to resolve dispute of any kind relating to enforcement of the bank guarantees submitted by the contractor at Bangalore for the execution of the Contract at Bangalore.
9. The contractor shall comply with all the legal requirements in the matter of employment of workmen and provide all safety gadgets to the workmen while working in the hazards place or conditions during the execution of the contract.

10. On his / their failure, if the Board is made to pay compensation the same shall be recovered by the Board from the contractor out of the amounts due to the contractor or by appropriate legal action.
11. If death of any employees occurs during execution of work due to negligence of contractor, the contract will be liable for termination. In the event of such termination, the employer may consider blacklisting of firm after due notice.

12. In case of any death or accident the contract will be cancelled after following due process:

    1) Any utilities encountered during execution if damaged by the contractor, the same need to be rectified immediately without any delay at his own cost with due approval from the concerned.
    2) If any undue incidents with respect to non compliance to safety at site per decease, the contractor has to pay Rs. 10.00 Lakh immediately, failing which the Board will pay and the same will be recovered by the contractor.

13. The Bidder Should not have applied for or are now part of Corporate Debt Restructure (CDR) / SDR in the last 5 Financial Years.

14. The Contractor shall use tertiary treated water from BWSSB wherever available for Construction, Flow testing at the prevailing rates of BWSSB.
15. The Hard Rock obtained during execution, will not be auctioned by Board (Because of the restriction in stocking of hard rock in site and safety issues). However Rs.70.00 per cum + applicable GST of Hard Rock will be recovered from the firm in Running bills.
16. Designated qualified safety officer/Engineer shall be deployed at site from the firm.
17. The Tenderer should have not been black listed by any Central / State Government Institutions in last 3 Financial Years.
18. Tenderer should inspect the site to know the existing Utilities if any before quoting.
19. In respect of Conditions of Contract of Section-C-Quality Control, Clause.35 of 35.1 under Payments for Variations above 125% of BOQ- The BOQ rates is compared with SR of year of award plus TP rates and lesser among them is considered for quantities exceeding 125% of BOQ in the work slip.
20. The contractors are being informed to quote their rate excluding GST. The GST, at the prevailing rate will be reimbursed
21. **Restrictions on public procurement from bidders of certain countries**- The bidder/Tenders from a country which

shares a land border with India will be eligible to bid in any procurement of works (including turnkey projects) only if the bidder fulfils the criterion's as per the Government order No. FD 455 Exp-12/2020, Bengaluru, dated: 28.8.2020.

22. **GFC –** The construction work shall be commencement only after approval of GFC drawings from CE (P) like structural, architectural, electrical pump house GA.
23. The contractor need to submit the final GFC drawing as per the directions of Competent authority

SECTION 6:

CONTRACT DATA

CONTRACT DATA

Items marked "N/A" do not apply in this Contract.

The following documents are also part of the Contract: Clause Reference

1 • The Schedule of Operating and Maintenance Manuals [48]
2
3 • The Methodology and Program of Construction [25]

4 • Site Investigation Reports [14]
5
6 • The Schedule of Key and Critical Equipment to be deployed on the work as per agreed program of construction. [25]

The Employer is :
Name: ***Chief Engineer (Project), BWSSB.*** [1.1]

Address: 3rd ***Floor, Cauvery Bhavan,***
Kempegowda Road,
Bangalore 560 009
Ph: 080-22945108

Name of authorized Representative: ***Executive Engineer (Cst)***

Bangalore Water supply & Sewerage Board

Suvarna Bhavan,Malleshwaram,18th cross, Bangalore.

The name and Identification number of the Contract is :	Work of providing & laying UGD sub-main of 400mm dia, lateral linking along with manual jacking in Herohalli village coming under 110 villages of BBMP and other works.

The Works involves providing & laying of DI pipe line, construction of division office, compound wall and allied works

The start date shall be the date of issue of notice to proceed with the work. [1.1]
The Intended Completion Date for the whole of the Works is Nine **(15) *Months***[7] with the following milestones [17, 26]

[7] Fill in the exact date of completion at the time of agreement

Milestone dates:

	Physical works to be completed	**Period from the date of issue of Notice to proceed with the work**
Milestone-1	• Providing and laying of 40% sub main work & other allied works • Sub-Division & service station Office-Upto lintel level • Complete construction of Compound wall -50%	Eight months from the date of agreement.
Milestone-2	• Completion & commissioning of sub-main • Sub-Division & service station Office building completion as per contract & finishing in all respects and handing over. • Construction of Compound wall -100%	Fifteen months from the date of agreement.

The Site Possession Date is: **After Issue of work order** [21]

The Site is located at Blue jay layout of Karivobanahalli village [1.1]

Defects Liability Period is 365 days.
[31]

Insurance requirements are as under:
[13]

	Type of Cover	Minimum cover for Insurance
(i)	Works and of Plant and materials	The sum stated in the Agreement plus 20%
(ii)	Loss or damage to equipment	Full replacement cost
(iii)	Loss or damage to property of Third Party	Full replacement cost
(iv)	Personal injury or death	Rs. 50.00 Lakhs

	insurance (a) for Third Party	
	(b) for Contractor's employees or labour	In accordance with the statutory requirements applicable to Karnataka

Payment Terms.

The employer will make the payment to the items of pipelines on the following terms-(Clause 43 GCC).

70% of the contract price	After supply of pipes for work site.

Price Adjustment Formula

[40]

Not Applicable

The liquidated damages for the whole of the works are Rs. ***0.1%.*** per day .

The maximum amount of liquidated damages for the whole of the works is ten percent of final contract price.

[41]

The amounts of the advance payment are: **Not applicable**

[42]

Repayment of advance payment for mobilization : **Not applicable.**

[42]

The date by which "as-built" drawings (in scale **1:1000**) in 2 sets are required is within 30 days of issue of certificate of completion of Whole or Section of the Work as the case may be. [48]

The date by which Operating and Maintenance Manuals are required is within 30 days of issue of certificate of completion of Whole or Section of the Work as the case may be. [48]

The amount to be withheld for failing to supply "as built" drawings or supply of Operation and Maintenance Manuals by the date required is Rs.2,00,000-00 [48]

The following events shall also be fundamental breach of the contract : [49.2]

The contractor has contravened Sub-clause 7.1 and Clause 9 of CC.

The percentage to apply to the value of the work not completed representing the Employer's additional cost for completing the Works shall be ***50*** percent. [50.1]

SECTION 7:

TECHNICAL SPECIFICATIONS

Specifications as per relevant IS codes and Bill Of Quantities

Contractor
Employer

TECHNICAL SPECIFICATIONS

I. GENERAL

EARTH WORK

1.0 INDIAN STANDARD

Work shall be carried out to Indian Standards and Code of Practices, in absence International Standards shall be followed. These shall be latest issue. List given hereunder is not to be considered as conclusive and is for reference and guidance only. Any discrepancies/conflict noticed shall be directed to the officer incharge for his direction /approval. However as a general rule more stringent specification shall take precedence.

(1) IS 1200 Method of measurement of Building and Civil Engineering works.

(2) IS 1498 Classification and Identification of soils for general engineering purpose

(3) IS 2720 Method of test of soil

(4) IS 3764 Safety code for excavation work

(5) IS 4081 Safety code for blasting and related drilling operation

(6) IS 6313 Part 1 Code of practice for anti termite measures in buildings:

Constructional measures.

Part 2 Code of practice for anti termite measures in buildings:

Pre constructional chemical treatment measures

(7) SP 27 Hand book of method of measurement of building works

(8) Explosive Rule 1940

2.0 SITE CLEARANCE

2.1 Prior to the start of any activity of earthwork, the area under construction shall be cleared of shrubs, vegetation, grass, brushwood, trees and saplings of girth upto 30 cm measured at a height of 1 metre above ground level. All rubbish must be removed and stacked at a distance of 50m outside the periphery of the area under clearances or location as decided by the officer Incharge

2.2 The rate of such clearance is to be included in the rate of other earthwork items and no separate rate shall be paid.

3.0 SETTING OUT

3.1 The contractor shall prepare detailed setting out drawings based on the layout of Architectural drawings and those shall be submitted to the Incharge prior to commencement of work. Bench Marks and Reference Lines shall be established, by the contractor with approval of the Incharge

3.2 The contractor shall do the setting out with the use of theodolite and like instruments at site, based on details given to him. He shall erect timber profiles, masonry pillars, burjis, etc. for his use. All markings on these shall be painted with red colour and they shall be maintained for the entire duration of the project. Setting out shall be approved by the Incharge before the commencement of any work.

3.3 The rate for the earthwork items shall include expenses for all such work including labour, material and equipment/ instruments, etc. No additional payment shall be eligible on this account.

4.0 EXCAVATION IN SOILS

4.1 Excavation over area

Excavation exceeding 1 m in width as well as 10 sq m in plan and 30 cm in depth shall be considered as excavation

4.2 over area.

Surface dressing

Trimming of natural ground, excavated surfaces, and filled up areas to remove vegetation and/or small inequalities not

4.3 exceeding 15 cm in depth shall be described as surface dressing.

Rough excavation

Excavation not requiring dressing of sides and bottom and

4.4 reduction to exact levels, such as winning earth from borrow pits, hill side cuttings, etc. shall be described as rough excavation.

4.5 Surface excavation

Excavation exceeding 1 m in width as well as 10 sq m on plan but not exceeding 30 cm in depth shall be considered as surface excavation.

Trenches for pipes/cables

It shall be detailed with nominal dia of pipe/cable. Required bottom width, allowance for concrete foundation for laying

4.6 pipes, working area, grip required for socketed pipe, return fill, ramming and removal of surplus soil shall be part of this

item unless otherwise specified. It shall generally be measured in cubic metres unless specified specifically as running meter in the BOQ.

4.7 Post holes

4.7.1 Independent post holes (or similar holes) each not exceeding 0.5cum shall generally be enumerated. Rate shall include return fill, ramming and removal of surplus soil. However this shall be in cubic meters as part of excavation items.

4.7.2 General

The excavated earth, shall be thrown or disposed off beyond 50 m periphery of the building. Earth suitable for backfilling shall be stacked separately.

4.7.3 Subsequent disposal of the surplus and unsuitable material shall be as per the respective items. Foundations, trenches shall be dug out to the exact dimensions as shown in the drawings or as directed by the Incharge

In firm soil, the sides of the trench shall be kept vertical upto a depth of 2 m. If the trench is to be deeper, it shall be in the form of steps of 50 cm, at every 2m depth. This shall be suitably increased or decreased as per site conditions and type of soil met with. This shall be to the approval of the

4.7.4 Incharge. Sloping of sides also may be adopted.

The bed of trenches shall be firmly consolidated and leveled by watering and ramming of the soft soil. Defective spots shall be dug out and filled with concrete of the same mix as of PCC or as directed by the Incharge. Cost of digging and filling with concrete shall be paid extra if excavation and PCC is measured separately.

If excavation is done to a depth greater than that required, excess depth shall be back filled with the same mix as of PCC or as directed. Cost of such concrete shall be to the contractor's account.

Excavated trenches shall have to be approved by the INCHARGE prior to laying of PCC or any other Permanent Work.

4.7.5 Excavation for drains shall be carried out with extra care to cut the sides and bottom exactly to the required shape, slope and gradient.

4.7.6 Filling for excess deeper excavation shall be done at the contractor's cost in consultation with the Incharge

4.7.7 Excavated materials shall not be placed within 1 m of the edge of the trench or half the depth of the trench, whichever is more.

4.8 Excavations for column footings shall be carried to depths indicated in the drawings. Safe bearing capacity at such

4.8.1 depth shall be verified to comply design requirements. If

ordered by the Incharge, appropriate tests shall be carried out by the contractor.

4.8.2 Protection

Fencing and/or other suitable measures for protection against risk of accidents due to open excavation shall be provided by the contractor at his cost.

5.0 Where excavation is to be carried out below the foundation level of an adjacent structure, and to avoid underpinning, precautions such as shoring and strutting, etc. must be taken. No excavation should start till such measures are taken to the satisfaction of the Incharge. Payments for such work shall not be made separately unless specified otherwise.

5.1

5.2

EXCAVATION IN SOFT ROCK

6.0 This shall be carried out by crowbars, pickaxes or pneumatic drills or any other suitable means. Blasting may be permitted if the contractor so desires but no extra money shall be paid for blasting. Measurements shall be in cubic meter.

6.1

6.1.1

6.1.2 Other general details same as clause 4.7. and its sub clauses.

EXCAVATION IN HARD ROCK

General

6.1.3 On meeting hard rock that requires blasting, the contractor shall inform the Incharge On approval in writing, blasting operation shall start if the contractor feels it necessary and so desires.

6.1.4

6.2 The contractor shall obtain the necessary license from the District Authorities for undertaking blasting work and explosive storing as per Explosives Rules 1940, and as updated. Explosives shall only be procured from an authorised dealer. He shall be responsible for the safe

6.2.1

custody and proper accounting of explosives. The Incharge shall have access to the store.

6.2.2 The contractor shall be responsible for any accident to those working on the site, to the public or to property due to blasting operations.

Measurements shall be in cubic meter by stacking rock and applying predetermined deduction for voids.

Precautions

Safety measures to be adhered to shall be as detailed in IS 4081, Safety Code of Blasting (as amended from time to time, and to related drilling operations). Also digest No.37 of C.R.R.I and I.R.C.A. Road tariff No.18 shall be adhered to.

Blasting operation shall be carried out under the supervision of a responsible authorised agent of the contractor. Timings shall be as approved by the Incharge in writing. Lunch break will be preferred. The authorised agent of the contractor should be well conversant with the rules and regulations of blasting operations. Further the contractor shall employ licensed blasters for actual operation.

6.2.3 All proper precautions for safety shall be taken. All persons shall be moved away to a distance not less than 200 m. All entries shall be sealed and red flags displayed at prominent places.

6.2.4 Blasting shall be done only with gunpowder. Dynamite, gelignite, or any other high explosive shall be used only with written permission of the Incharge.

6.2.5 The number of charges to be fired and the actual number of shots heard shall be counted and the contractor's agent shall satisfy himself by examining that all charges have exploded. Only then shall workmen be allowed to start work.

6.2.6 Unexploded charges shall be flooded with water, a new hole drilled and exploded again.

7.0

7.1 The Incharge shall be informed about all misfires, their causes and the remedial steps taken.

CLASSIFICATION

All soils comprising any of the following :

(a) Vegetable or organic soil, turf, sand, silt, loam, clay, mud, peat, black cotton soil, soft shale or loose murrum.

(b) Any mixture of soils in (a).

(c) Mud concrete below ground level.

(d) Generally any material which yields to the ordinary application of a pickax and shovel or to phawra, rake or other ordinary digging implement and not affording resistance to digging greater than mentioned in (a) to (c).

7.2

(e) Stiff heavy clay, hard shale, or compacted murrum requiring close application of a grafting tool or pick or both and shovel.

Gravel and cobblestone (cobblestone is a rock fragment), usually rounded, having maximum dia in one direction of 75-300 mm.

Soft rock comprising any of the following

(a) Soling of roads, paths, etc. and hard core.

(b) Macadam surfaces of any description (water bound, grouted, tarmac, etc.)

(c) Lime concrete, stone masonry, in lime mortar and brick work in lime or cement mortar, below ground level.

(d) Soft conglomerate, where the stones may be detached from the matrix with picks, crow bars, wedges, etc.

(e) Limestone, sandstone, laterite, hard conglomerate or other soft or disintegrated rock which may be quarried or split with a crowbar.

Unreinforced cement concrete which may be broken up with crowbars or pickaxes and stone masonry in cement mortar, below ground level.

(g) Boulders not requiring blasting, rock fragments usually rounded by weathering, disintegration and exfoliation or abrasion by water or ice, having maximum dia length in any direction of 500 mm, found loose, embedded, etc.

(h) Other varieties of rock which would normally be removed with

pick, crowbars, wedges and hammer with only a little difficulty.

7.3 Hard rock comprising any of the following

(a) Any rock or cement concrete in excavation for which the use of mechanical equipment or blasting is required.

(b) Reinforced cement concrete.

(c) Boulders bigger than 1/2 cubic meter requiring blasting.

(d) Hard rock as in (a) to (c) requiring blasting but prohibited from doing so for any reason and excavation has to be carried out by chiseling, wedging or any other agreed method.

8.0

8.1 **FILLING**

Filling shall be done where required with approved quality of earth. It may be from excavation and, where possible, cutting and filling shall be done simultaneously to avoid

8.2 double handling.

Filling shall be done in layers not exceeding 15 cm in depth. Earth used shall be free from roots, grass and rubbish and all lumps and clods exceeding 8 cm in any direction shall be broken down. Each layer shall be watered with optimum moisture content to achieve 95% Procter density. Consolidation shall be done by mechanical roller of

8.3 minimum 12 tonnes weight. The roller shall pass a minimum of 10 runs evenly to achieve dense consolidation. All undulation made up and final layer re-rolled.

Measurement shall be for compacted volume in Cubic Meter.

8.4 Sand filling

The sand shall be free from any organic and deleterious materials as detailed in IS. It should be suitable for compaction. Filling shall be in layers of 15 to 20 cm watered with optimum moisture content and mechanical rammers.

Measurement shall be for compacted volume in Cubic Meter.

Rubble soling

9.0

Good quality 150 mm to 230 mm thick rubble soling shall be carried out depending upon the grade of soil. Rubble used shall be at least 100 mm for 150 mm thick soling and 150 mm for 230 mm thick soling. Stone shall be hand packed as close as possible and bedded firmly with the broadest face downwards and the greatest length across, voids filled with chips and small stones. These shall be hammered down to achieve packing and the complete filling of interstices. To achieve the desired levels and slopes, pegs at suitable intervals (about 12m) shall be fixed.

10.0

Soling shall be watered and again packed with sand or murrum to fill interstice's created by watering. Then it shall be rolled with 10 (on roller or vibratory compactor. Filling sand or murrum, watering and rolling shall continue till full compactness is achieved to satisfaction of the Incharge.

10.1 Measurement shall be in Square Meter.

PLANKING AND STRUTTING

In case of deep trenches where the soil is soft and not capable of being retained without the help of support, planking and strutting as required shall be carried out. It shall be the responsibility of the contractor to take steps to prevent slide/collapse. Method of planking/strutting will be largely influenced by the type of soil encountered and as

approved by the Incharge.

DISPOSAL OF SURPLUS EARTH

Surplus earth shall be used to the maximum extent in the compound. Earth useful for filling shall be separately stacked as directed by the Incharge from time to time.

Approved quality earth shall be used in the filling. It shall be consolidated as detailed and approved by the Incharge.

10.2 Rate for excavation shall include sorting out of useful materials.

10.3 All surplus and unusable earth shall be disposed off outside the plot but at a location approved by local authority and conforming to their specification. The contractor shall quote his rate for disposing off or carting away the items considering requirements and standards of the local authority with whose permission surplus and unusable earth shall have to be disposed off.

11.0 DEWATERING

Bailing or pumping out of water that may have accumulated due to rains, subsoil seepage, or any other means shall be carried on continuously and the area shall be kept dry for the following operations:

(a) Measurements

(b) Concreting or masonry work

(c) Shuttering and reinforcement

(d) Backfilling

12.0 (e) Line out

12.1

(f) Any other reason deemed fit by the In charge.

MEASUREMENT

The following shall not be measured separately and allowance for the same shall be deemed to have been made in description of the main item.

(a) Setting out works, erecting profiles, etc,

(b) Site clearance such as clearing of shrubs, brushwood, small trees not exceeding 30 cm in girth measured at one meter above ground.

(c) Unauthorised battering or benching of excavations.

(d) Forming (or leaving) DEAD MEN or TELL-TALES in borrow pits and their removal after measurements.

(e) Forming or leaving steps in the sides of deep excavations and their removal after measurements.

12.2

(f) Excavations for insertion of planking and strutting.

(g) Removing slips or falls in excavations.

(h) Dewatering by bailing or pumping out of water in excavations from rains, sub-soil water, tides, undercurrents, etc.

(i) Slinging or supporting pipes, electric cables, etc. met during excavation or while carrying out any other item of work.

(j) Dressing, trimming of sides, leveling, or grading and ramming of bottoms.

Soils, soft rocks, hard rocks shall be measured as per SP 27 Part I except for the followings :

(a) Filling shall be in cubic meter for consolidated volume. The lift shall be considered from made-up ground level.

(b) Planking and strutting required to be left in position shall be measured separately. Incharge's permission in writing shall have to be obtained for this. In no other case shall payment be made for planking and strutting, if carried out.

(c) Lead and lifts shall be as per the BOQ.

st 200 mm diameter. graduated such that the test pressure is at least 75 % of the full-scale reading shall be used, If necessary different gauges shall be supplied for different pipeline sections. Two gauges shall be provided for the sole use of the Engineer and shall remain in Engineer's possession for the duration of the Contract. All gauges shall be dead weight tested and calibrated at the commencement of work and at regular intervals as required by the Engineer.

The Contractor's arrangements for testing shall include a suitable means of quick installation and removal of the Engineer's gauges during testing.

16. Hydraulic Testing Pipelines

The Sectional Hydraulic Test shall be carried out after the pipeline section to be tested has been laid, Jointed and backfilled to a depth sufficient to prevent floatation, but leaving the joints exposed which have not been tested, the sections to be tested shall be to the approval of the Engineer and shall not be longer than 2000 m or 500 m when either the pipeline is laid adjacent to or underneath the carriageway or when section includes an air valve chamber. The joints between each tested section shall be left exposed until the pipeline has passed the Test on Completion,

In addition to the above requirements the Contractor shall perform a hydraulic test on the first 200 m length of pipeline to be laid under the contract. This test shall be undertaken within one month of the Contractor commencing the laying of pipes. Should the pipeline fail the test or the Contractor fails to undertake the test, all laying work shall come to a halt until that section of pipeline passes a hydraulic test.

Each length of the pipeline to be tested shall be capped or blanked off at each end and securely strutted or restrained to withstand the forces which will be exerted when the test pressure is applied. Testing against closed valves will not be permitted. Washout valves shall be fitted with blank flanges and these together with in-line valves shall be left open. Air valves already fitted shall be permitted to function during the test.

Proposals for testing where thrusts on structures are involved, even where thrust flanges on the piping are installed, shall be submitted,

with the calculations of the forces to be carried, to the Engineer for approval.

The method of filling the pipeline with water shall be approved by the Engineer. The length under test shall be filled making certain that all air is displaced through an air valve installed at the top of the blank flange situated at the high end of the line. The length shall then remain under constant moderate pressure, 10 to 20m head of water, for a period of several hours until the pressure can be maintained without additional pumping.

The pressure shall then be slowly increased at a maximum rate of I bar per minute to the full test pressure and pumping discontinued for 3 hours or until the pressure has dropped by 10m, whichever occurs earlier. Thereafter pumping shall be resumed and continued until the test pressure has been restored. The quantity of water pumped to restore the pressure shall be the measure of leakage from discontinuation of pumping until its resumption.

The pipe length shall pass the test if the leakage is not more than 1.079 litres per mm diameter per kilometre per 24 hours for each 100m head of pressure applied and the full test pressure has been sustained for at least eight hours.

Notwithstanding the satisfactory completion of the hydraulic test, if there is any discernible leakage of water from any pipe or joint the Contractor shall, at his own cost, replace the pipe, repair the pipe or re-make the joint and repeat the hydraulic test.

No pipeline shall be accepted until the leakage on any length is not more than the rate of leakage specified above and all sources of leakage have been rectified.

The Test on Completion shall be carried out after all the pipeline sections have been satisfactorily tested and the Joints between each section completed to provide a continuous test length between contract interfaces.

Pipelines shall be tested as above except where the Engineer issues such instructions as are necessary for testing parts of the Works that have been designed for stresses limited by considerations other than those applying to the pipeline systems.

17. Test pressures

Test pressures are to be measured in bars at the centre of the blank flange situated at the lowest end of the pipeline under test. Unless otherwise specified or shown on the drawings pipeline test pressure shall be in accordance with the following:

DI /MS pipe and fittings without HSC	10 bar
DI /MS Pipes and fitting with HSC	05 bar

For testing of sections of pipeline containing air valve chambers the Contractor shall verify from manufacturer that the air valves are capable of operating under and sustaining the test pressure.

18. Chamber Markings

Details like valve type. size, cistern number shall be painted on all valve chambers as directed by Engineer. Where valve chambers are flush with the ground, suitable marker posts shall be provided adjacent to the chambers at a suitable location with all details approved by Engineer.

In case of the pipeline laid above ground details such as chainage, invert levels of pipe, saddle number, culvert number, anchor/thrust block number etc., shall be suitably painted either on the pipeline or the supporting structure in distinct colour.

19. Measurement and Payment

The measurement for pipes for items specified in Bill of Quantities shall be on running metres of net length along the centre line of the pipe excluding the length of specials and appurtenances. Payment for pipes shall be made in running metres after production of test certificates specified and directed by Engineer.

Payment for laying the pipes and specials shall be made after successful testing at site.

20. Location and Protection of Existing Public and Private Utilities.

Once permission to work has been obtained from the road authorities, and prior to excavation, the Contractor shall contact all utility companies and householders in roads where work is to take place and inform them of the nature of the work and its likely duration. Information should be obtained from utilities companies about the location of their utilities, preferably in the form of record drawings,

and the Contractor should carry out utilities tracing using electronic equipment to verify the positions of utilities. Trial excavations should also be carried by hand to further confirm locations of utilities. The Engineer will only permit trench excavation to proceed when he is satisfied that adequate efforts have been made to establish the alignments and depths of existing utilities.

All underground utilities such as water pipes, gas pipes, drains, sewers, electricity and telephone cables exposed in excavations, shall be properly supported and protected by the Contractor to the satisfaction of the Engineer so as to avoid damage to the utility or to the Works as a result of collapse of the utility. Similarly, poles carrying overhead electricity and telephone wires should be braced and supported where there is any likelihood of collapse as a result of excavation.

SECTION-II A

CONCRETE WORK

GENERAL

1.1 Standard

Work shall be carried out to Indian Standards and Code of Practices, in absence International Standards shall be followed. These shall be latest issue. List given hereunder is not to be considered as conclusive and is for reference and guidance only. Any discrepancies /conflict noticed shall be directed to the Incharge for his direction / approval. However as a general rule more stringent specification shall take precedence.

Specification for Ordinary and low heat, portland cement Specification for 43 grade ordinary portland cement Specification for 53 grade ordinary portland cement

(1)	IS 269	Specification for Ordinary and low heat, Portland cement
(2)	IS 8112	Specification for 43 grade ordinary Portland cement
(3)	IS 12269	Specification for 53 grade ordinary Portland cement
(4)	IS 383	Specification for Coarse and fine aggregates from natural sources for concrete
(5)	IS 456	Code of practice for plain and reinforced concrete

(6)	IS 460	Specification for test sieves (Part I, II & III)
	i)	Wire cloth test sieve
	ii)	Perforated plate test sieve
	ii)	Method of examination of test sieves
(7)	IS 515	Specification for natural and manufactured aggregates from natural sources for concrete.
(8)	IS 516	Method of test for strength of concrete
(9)	IS 875 (Part I, II & III)	Design loads for building structure.
(10)	IS 1199	Method of Sampling and analysis of concrete
(11)	IS 1791	Batch type concrete mixers.
(12)	IS 1893	Earthquake resistant design.
(13)	IS 2386	Method of test for aggregate for concrete (Part I, II & III)
	i)	Particle size and shape
	ii)	Estimation of deleterious materials and organic impurities
	iii)	Specific gravity, density, voids, absorption and bulking.
(14)	IS 2505	General requirements for concrete vibrators.
(15)	IS 2645	Specification for Integral cement water proofing compound.
(16)	IS 3025	Method of Sampling and test (Physical and Chemical for water)
(17)	IS 4326	Code of practice for earthquake resistant design and construction of building.
(18)	IS 4926	Specification for ready mixed concrete.
(19)	IS 7861	Code of practice for extreme weather concreting
	i)	Recommended practice for cold weather concreting
	ii)	Recommended practice for cold weather concreting
(20)	IS 9103	Specification for admixture for concrete
(21)	IS 12118	(Part I) Specification for two parts polysulphide based sealant: general requirements
(22)	SP 23	Hnadbook on concrete mix
(23)	SP 24	Explanatory handbook on Indian Standards code for plain and reinforced concrete (IS 456)
(24)	SP 27	Handbook of method of measurement of building works.

1.2 Quality Assurance

1.2.1 Concrete used on site shall comply to relevant parts of Standards, Codes of practices, technical specification given in particular or approved, designed mixes as prepared, approved and adopted for

works to give designed strength, serviceability, long term durability etc.

1.2.2 Provide and monitor quality control over materials received from suppliers / manufacturers to ensure that materials comply with standard specified and are as approved.

1.2.3 Provide experienced supervision and work force to ensure that workmanship is of specified quality.

1.2.4 Work shall not be subjected to harmful, dangerous, damaging or deleterious exposures while it is in progress or on completion during contract period.

1.2.5 Contractor to under take quality assurance by documenting.

- Test report for material used in producing concrete.
- Mix design details with laboratory test report, actual site trial mix test and accepted modified design if any
- Pour cards with approval of the Incharge prior to placement
- Control charts
- Non conformance reports, changes, orders etc.

1.3 Submittals

1.3.1 Submit samples of all materials such as cement, sand, aggregate, admixtures, water etc to be incorporated into concrete along with test certificates from recognized laboratories for the Incharge's approval.

1.3.2 Samples

During construction, the materials shall be sampled and tested as often as directed by the Incharge to the contractor. Samples shall be taken and tested in accordance with latest revisions of Indian standard specifications and the cost thereof shall be borne by the Contractor.

1.3.3 Shop Drawings

Contractor shall prepare and submit method, mode of casting of slabs, beams with details of construction and expansion joint for approval of the Incharge.

1.4.0 Examination of conditions

Contractor shall inspect and examine sub strata and confirm prior to start that.

- Substrate is acceptable and approved by Incharge
- Conditions are satisfactory
- Setting out/Layout is verified
- Corrective measures needed if any are within reach and contractor proceeds with full responsibility for work.

2.0

2.1 **MATERIALS**

Cement

Cement shall be ordinary Portland Cement conforming to IS and shall be of grade 53/43 for structural use or as specified in drawing.

It shall be received in bags of 50 kg or loose in tankers and each batch shall be accompanied with a test certificate of the factory.

2.2 Also it shall be tested before use to ascertain its strength, setting time, etc. In case cement has been stored for over 3 months or for

2.2.1 any reasons the stored cement shows signs of deterioration or contamination, it shall be tested as per the direction of the Incharge prior to use in the works.

Coarse aggregate

2.2.2 Coarse aggregate shall be obtained from natural sources such as stone, gravel, etc., crushed or uncrushed or a combination thereof from approved quarries. Aggregate shall be hard, strong, dense, durable, clean and free from veins and adherent coatings. It shall

be free from soft, feeble, thin, elongated or laminated pieces and shall be roughly cubical in shape. It shall consist of coarse material, most of which is retained on 4.75 mm IS sieve.

Coarse aggregate shall not contain any harmful material such as iron, pyrites, coal, mica, shale or similar laminated material; neither shall it contain clay, alkali, soft fragments, sea shells, organic impurities, etc. in such quantities that adversely affects

2.2.3 the strength and durability of the concrete. In addition to the above, in reinforced concrete the aggregate shall not contain any material which might attack the reinforcement. The maximum quantities of deleterious materials in the coarse aggregate, when determined in accordance with IS 2386 Part I and Part II "Method of test for aggregates for concrete" shall not exceed the limits laid down in table 1 of IS 383.

Aggregate crushing value, impact value, abrasion value and soundness of aggregate shall respectively be in accordance with para 3.3, 3.4, 3.5 and 3.6 of IS 383.

2.2.4 Grading of coarse aggregate shall be in conformity with the requirements laid down in IS 383. See table 2 and table 3.

The grading of coarse aggregate shall be such that not more than 5% shall be larger than the maximum size and not more than 10% shall be smaller than the smallest size. Between these sizes the coarse aggregates shall be well graded.

For heavily reinforced concrete the aggregate shall be subjected to tests in accordance with IS 2386 or and directed by the Incharge.

The maximum size of coarse aggregate should not be greater than one fourth of the minimum thickness of the member and it should be restricted to 5 mm less than the minimum clear distance between the main bars or 5 mm less than the minimum cover to the reinforcement.

Source of aggregate shall be from an approved Government

location. It shall be tested prior to the approval of the Incharge from an approved testing laboratory. In case available aggregates

2.2.5 do not meet certain requirements of IS 383 or any other specification, required processing shall be carried out by the contractor at his cost. No extra cost towards these processes, treatment or combination of both shall be paid. It shall be the

2.2.6 duty of the contractor to make sure that aggregate material received by him is from Government approved quarries and with fully paid royalties, taxes, duties, etc. as may be in force from

2.2.7 time to time for respective locations.

Coarse aggregate shall have a minimum specific gravity of 2.6. (Saturated surface dry basis). Aggregate below this specific gravity shall not be used without the special permission of the Incharge.

2.2.8 Once a specific source of supply of coarse aggregate is approved, the source shall not be changed without the prior approval of the Incharge.

Fine aggregate

Natural sand deposited by stream or glacial agencies as a result of disintegration of rock shall be used as fine aggregate. Fine aggregate shall pass through 4.75mm sieve in total. Crushed sand may be added to natural sand in approved proportions to achieve required grading. The fine aggregate (coarse sand FM above 2.25 & Fine sand F M more than 1.25) shall conform to following standards.

(i)	For plain and reinforced concrete	IS 383 Specification for coarse and fine aggregates from natural sources for concrete.
(ii)	Mortar and grout sand for	IS 2116 Specification for masonry

mortars.

Sand shall be hard, durable, clean and free from adherent coatings and organic matter and shall not contain any appreciable amount of clay. Sand shall not contain harmful impurities such as iron, pyrites, coal particles, lignite, mica shale or similar laminated material, alkali, and organic impurities in such form or quantities as to affect the strength or durability of concrete or mortar. Also it should not contain any material liable to attack the steel reinforcement.

When tested as per IS 2386 Part I and Part II, fine aggregate shall not exceed permissible quantities of deleterious materials as given in table 1 of IS 383.

Fine aggregate shall be thoroughly washed at site with clean fresh water such that the percentage of all deleterious material is within the permissible limits laid down.

2.2.9 Grading of fine aggregate shall conform to IS and shall fall within limits of one of the four zones given in table 4 of IS 383.

2.3.0 Due allowance for bulking due to damp and moist sand shall be made while preparing the mixes based on volume measurements.

2.4 It shall be determined as per IS 2386 Part III Appendix A.

2.4.1 Water

Water used for mixing and curing shall be clean, reasonably clear and free from objectionable quantities of silt, oils, alkalies, acids, salts so as not to weaken mortar, or concrete or cause efflorescence or attack the steel in RCC while curing. It shall be free of elements, which significantly affects the hydration reaction

2.4.2 or otherwise interferes with hardening of concrete during curing or those elements which produce objectionable stains or

2.4.3 deposits. Potable water is generally satisfactory but it shall be tested prior to use in the works.

Water tested shall be in accordance with IS 3025. Maximum permissible limits of deleterious materials in water as given in IS 456.

2.4.4 Suitability of water shall be ascertained by the compressive
2.4.5 strength and initial setting time test as specified under:

a) Average 28 days compressive strength of atleast three 15
2.5 cm concrete cubes prepared with water proposed to
2.5.1 be used shall not be less than 90% of the average strength of three similar concrete cubes prepared with distilled water. Preparation and testing to be in accordance with IS 516. b) The initial setting time of test blocks made with proposed cement and water to be used shall not
2.5.2 be less than 30 minutes and shall not differ by ± 30 minutes from the initial setting time of control test block prepared
2.5.3 with the same cement and distilled water. Preparation and testing of block shall be in accordance with IS 4031.

The PH value of water shall not be less than 6 and more than 9.

Water shall be tested and approved in writing by the Incharge prior to use in the works,Admixture

These are substances other than cement, aggregate and water and shall be permitted to be used to modify the properties of concrete for single, or a combination of purposes. This shall be used only on the written approval for specific purpose and at the cost of the contractor. Good concrete shall be achieved without the aid of any admixtures.

Admixtures shall be free from chlorides and sulphates which might affect concrete or any other material which may cause problems to the concrete in the due course of time. Also it shall have no effect on the reinforcement in case of Reinforced Cement Concrete.

Admixtures generally in use are classified as under:

a) Accelerators
b) Retarders
c) Workability agents
d) Water repelling agents
e) Air-entraining agents
f) Gas-forming agents
g) Corrosion inhibitor additive

2.5.4 These are manufactured and sold by various companies under brand names. The contractor proposing to use any one of them shall submit to the Incharge technical literature with its chemical composition, purpose of use and method recommended by the manufacturer and what he proposes to follow at site for strict control.

The contractor's proposal shall accompany the followings with his request to use admixture.

a) The trade name of the admixture, its source and the manufacturer's recommended method of use.

b) Typical dosage rates and the possible detrimental effects of under and over-dosage.

c) Whether the admixture contains chloride in any free form or any other chemical present as an active ingredient which is a likely cause of corrosion of reinforcement or deterioration of concrete.

2.6 d) The average expected air content of freshly mixed

2.6.1 concrete containing an admixture which causes air to be entrained when used at the

manufacturer's recommended rate of dosage.

2.6.2 Miscellaneous

Integral cement water proofing compound specified for specific

2.6.3 use shall conform to IS 2645.

2.6.4

Bituminous felts for waterproofing and damp proofing course shall conform to IS 1322.

Bituminous compounds for water proofing purposes shall conform

2.6.5 to IS 1580. Expansion joint filler

Bituminous impregnated premoulded preformed expansion joint filler board conforming to IS 1838 part (I) specification for preformed filler boards shall be of approved quality and thickness at designated locations.

Polysulphide sealants

1 Expansion, construction or other joints shall be sealed with approved quality polysulphide sealants.

2 One part gun grade polysulphide-based joint sealants shall

conform to IS 11433 (Part I). It shall be used with the approval of the Incharge and as per the manufacturer's instructions. Correct primer shall be used at the specified location.

3 Two part polysulphide based sealant gun grade or pouring grade shall conform to IS 12118 (part I). Pouring grade shall be used in horizontal joints. Gun grade shall be used in vertical, inclined and horizontal joints.

Specified primer shall be applied prior to the use of sealant. Use of sealant shall be as per instructions of the approved manufacturer.

4 Sealant shall be cured at ambient temperature and humidity when applied as per the approved manufacturer's instruction and received in suitable packs. Each package shall indicate

Manufacturer's name and trade mark
Weight of the components
Instructions for storage
Type and grade of sealants
Date of manufacture and expiry

2.6.6 Instructions for use

Water bar

PVC or rubber water bar of type, quality and width shall be used as approved by the Incharge. Water bar shall be continuous and fixed at the indicated locations. Water bar should be welded or Joined with the approved method. All angles and corners shall be

2.7 purpose-made and shall be joined with the approved method.

2.7.1 Delivery and Storage

It shall be received in bags of 50 kgs and each batch shall be accompanied with a test certificate of the factory. Reject damp or torn bags.

Cement shall be stored in dry and water proof shed so as to prevent deterioration due to moisture, dampness. Bags shall be stacked on rigid water-proof platforms about 15 to 20 cm clear

above the floors and 25 to 35 cm clear or away from the surrounding walls. A maximum high stack of 10 bags permitted. Stacks shall be so arranged that the first batches are used first, (FIFO) and that they permit easy access for inspection and

2.7.2 handling.

Loose cement received shall be stored in silo's. Silo's shall be equipped to receive cement by pump and manually. Silo's shall be water tight and damp proof to keep cement fresh.

Coarse Aggregates and Fine Aggregates

2.7.3 Aggregate shall be stored in such a way that it does not get mixed with mud, grass, vegetables and other foreign matter. The best way is to have a hard surface platform made out of

2.7.4 concrete, bricks or planks. It should be to the approval of the Incharge.

Water

3.0 Water storage tanks shall be such as to prevent any deleterious materials getting mixed with it.

Covered storages

Considering the atmospheric/ weather conditions at site storages, covering shall be arranged to take care of temperature controls at site.

CONCRETE

3.1 Concrete is prepared by mixing graded aggregate of stone or along with cement, in a specified proportion. Mixing shall be done by a mechanical mixer. Manual hand mixing shall be permitted in specific cases with the written permission of the Incharge on account of small quantity or location or any other reason acceptable to the Incharge.

Cement concrete

3.1.1 This shall be classified as plain cement concrete or reinforced cement concrete. Plain cement concrete shall be In leveling

3.1.2 course under foundations, floors, copings. etc. and shall include form work as part of the work.

Reinforced cement concrete shall be at all locations and comprises form work. reinforcement and concrete. Payment of

reinforced cement concrete may be composite or item wise as specified in the BOQ. In PCC, payment for form work shall not be made.

Concrete shall be classified by its compressive strength at the 28th day. The concrete grades shall be as designated in table 2 of IS 456 "Grade of concrete".

Design.mix

BOQ shall specify various types of concrete aimed to be used in works. It shall be the responsibility of the contractor to carry out design mixes and approval of the same shall be obtained from the Incharge atleast 35 days in advance from the actual pouring of concrete at site in the permanent works.

1. Mix design of concrete shall be done as per IS 10262 & SP 23,24. Following basic points shall be finalised.

- Characteristic compressive strength and targeted compressive strength required at design stage.
- Standard deviation factor based on site actual execution conditions.
- Minimum cement specified in BOQ or as per IS for strength and durability for location where concrete is to be used.
- Water cement ratio permitted by IS.
- Workability to be achieved for better workmanship and good quality concrete
- Admixtures to be used if any
- Aggregates being used are tested to IS383. Include for Alkali reactivity, chloride and sulphate contents independently and combination of cement and water.
- Water being used is tested.

Further the contractor shall ensure that designed mix meet minimum cement contents as specified in BOQ/drawings and proposed revision to IS 456 along with maximum water cement ratio, to different exposure condition from durability point of view. In addition contractor shall ensure

a) Alkali – reactivity

Aggregates containing material susceptible to attack by

alkali's (Na_2O and K_2O) originating from cement or other sources and producing expansive reaction shall not be used.

The aggregates source shall be initially tested for alkali reactivity prior to being used in design mix.

3.1.4.4 This design mix and trial mix hold good so long as the materials continue to be of the same quality and from the same sources. For any change, the Incharge may order fresh design mix and trial mixes to be carried out before the same Is used at site.

3.1.5 Mixing of concrete

3.1.5.1 Machinery and equipments.

a) Batching

Batching shall be done by weigh batchers conforming to IS 2722. A platform scale of capacity 300kg with fraction upto 100gms shall be at site.

For water supply to mixture through metering system shall be organised.

Design mix converted to volumetric may be permitted by Incharge. Accordingly suitable size of boxes equivalent to 1 bag of 50kg cement shall be prepared by the contractor.

b) Mixer

Mixers used shall conform to IS. Type Capacity shall be as per size, extent and nature of work.

c) Transportation

Wheel borrows, cranes, mini dumpers, truck, agitators, belt conveyors, pumps with piping etc. as per requirement depending upon location, size extent and nature of work shall be deployed by the contractor with prior approval of the Incharge.

d) Vibrators

3.1.5.2 Internal and external vibrators working on electricity, Pneumatic or petrol shall be approved by the Incharge. Vibrators shall conform to IS.

e) All machineries and equipments shall be maintained

regularly. Periodic calibration of all machines shall be done and records maintained in a register. As and when requested by the Incharge same shall be forwarded for his inspection.

At the start of mixing, mixer shall be rinsed/coated by loading with cement, sand, water of the same proportion of batch to be used. Loading the mixer/charging the mixer shall be done

3.1.5.3 mechanically and care to be taken that all material is fully loaded.

The mixer shall be run for a minimum period of 2 minutes after all materials are loaded in full quantity. The concrete produced shall be uniform in colour and consistency. Unless agreed by Incharge the first batch of concrete from mixer shall contain two-third of normal quantity of coarse aggregate.

Transportation

Concrete shall be transported to place of pour as far as possible in most efficiently, conveniently and without loss of concrete characteristic. Method of transportation shall depend upon the location, size and nature of work. Concrete should be placed within 1.5 hours of production i.e. prior to initial set.

Use of admixtures such as air entraining agent, retarders etc. shall be adopted and incorporated into design mix stage.

3.1.5.4 Concrete shall be kept in agitating state when ambient temperatures are high. This shall increase placing time to 1 % hrs after water is added.

Points to be taken care are

Method adopted do not permit segregation

Containers used are leak proof

Containers are well covered during rains, heavy winds

Concrete does not get contaminated by oil, dirt etc.

Placing

The placing temperature of concrete shall not be more than 34° C. If it is more, the Incharge may order addition of ice or chilled water to the concrete. Also the contractor shall take the following precautions :

3.1.5.5 a) Mixers and weigh batchers shall be painted with white

colour

b) Aggregate storing bins shall not be exposed to the Sun

c) Water shall be sprinkled on aggregates well before concreting to keep the temperature low.

d) Use chilled water for mixing or add flake ice as a proportion of the mixing water.

e) Place concrete at night.

f) Ready mix concrete (RMC)

a) Concrete

Ready mix concrete as approved only shall be used. It shall comply all requirements of concrete. Batching plant, mixture, truck mixture, pump etc shall conform to relevant Indian standard. Daily returns shall be provided showing total volume of each class of concrete received.

b) Pumping of concrete

Stationery or mobile pumps as per requirements shall be deployed. Concrete shall be continuous to avoid any blockage within pump. Concrete mix shall be with slump as desired by pump manufacturer and most desirable at site to pump operator / supervisor.

3.1.6 Required piping, bends, clamps, chutes etc. shall be well organised and placed in position prior to start so continuous concrete with minor changes will keep concrete flowing at predetermined location in approved manner.

Mix design adopted shall be approved by Incharge and shall

conform all test as detailed in specification.

3.1.7 Pump concrete shall flow quite fast and is placed with larger impact on formwork. Hence special precautions at design stage of formwork shall be taken and staging /scaffolds should be well restrained in all directions to withstand thrust.

Pumping shall be done with due care and safety. Recommendation of pump suppliers shall be

followed strictly.

Shrinkage cracks

Concreting shall be avoided in very warm weather. If necessary, it shall be covered with damped hessian within 2 hours of placing of concrete.

To achieve good results the concrete shall be immediately covered with a plastic sheet and not allowed any direct wind contact. This shall eliminate shrinkage cracks.

Laying of concrete

a) Concreting shall commence only after form work is approved, reinforcement is recorded and permission to proceed with concreting has been approved in writing from the Incharge.

b) Form work should be clean, free from sawdust, pieces of wood or any other foreign material. It should have been treated by form releasing agent prior to the laying of reinforcement and concrete. Prior to placing concrete against old concrete, masonry, rock all loose materials shall be removed and surfaces washed down. Concrete shall be worked around ties and bond and in open joints.

c) Concrete shall be as gently deposited as is practically possible, in its final position to avoid re-handling and shall be so deposited that segregation of aggregates does not occur. In case of deep trenches and footings, it may be done with the help of a chute. Columns and walls shall be so adjusted in form work so that maximum depth is 1.5 metre unless consented to by the Incharge. Concrete from wheel barrows shall not be dumped away from the face of concrete already in place. It shall be dumped into the face of concrete already in place. In excavations

3.1.8 prevent contamination of earth and concrete without

disturbing unsupported sides of excavation. Concrete shall not be placed in water except where specified.

d) Concrete onto a sloping surface shall be discharged by providing a chute with a baffle and a drop at its end so that the concrete remains on the slope.

e) Columns and walls shall be concreted in one operation to their full height to avoid any horizontal construction joint as far as possible.

All slabs, beams, wooden planks, and cat-walks shall be provided clear of reinforcement.

g) Concrete shall be placed in position within 30 minutes from the time it is produced. Concrete shall be laid during normal working hours. Concreting at night or on holidays shall be permitted only on the written approval of the Incharge.

3.1.9 h) Placing in each section shall be a continuous between construction joints. The contractor shall make provision for standby equipment. In case of delay or break down stop ends are to be provided or concrete placed to be removed as per direction of the Incharge.

i) Placing shall not take in open during storms or rains, strong winds. Contractor to organise and provide required protection.

Compaction of concrete

Concrete shall be thoroughly compacted as depositing shall proceed by means of able vibrators. The vibrators shall maintain the entire concrete under treatment in an adequate state of agitation and shall continue during the whole period occupied by placing of concrete. Care shall be taken not to over- vibrate the concrete. While withdrawing needles no holes should be visible in concreting. Compaction shall be completed before the initial setting time. Concrete already set shall not be disturbed by successive vibrations.

It shall be ensured that the needle vibrators are not applied on

reinforcement which may destroy the bond between concrete and reinforcement.

When electric vibrators are in use, the standby petrol vibrator must always be available at the concreting point.

3.1.10. Construction joints

In large pours, it is practically not possible to carry on concreting continuously. Hence construction joints shall be provided.

3.1.11 Location of construction joint shall be submitted by the contractor for approval of the Incharge. Such joints shall be kept to a minimum. The joints shall be at places where shear force is nil or minimum and these shall be straight and at right angles to the direction of the main reinforcement.

Stop ends provided shall be with necessary slots for reinforcement bars to pass freely without bending or any other obstruction. Also a trapezoidal fillet nailed on stop board shall be provided to form a regular keyed joint. Joints shall be straight and truly vertical or horizontal.

Before commencement of concrete, adjacent concrete stopper and surfaces shall be chipped and roughened to expose aggregate, then wire brushed and cleaned. The concrete surface shall be sprayed with water for 24 hours before casting and kept wet until casting.

True horizontal joints shall also be provided with a keyed joint by inserting planed greased timber.

Prepared joint shall be treated as above prior to the start of fresh concreting.

For vertical joints neat cement slurry shall be applied on the surface just before concreting. For horizontal joints, the surface shall be covered with a layer of mortar
about 10 to 15 mm thick composed of cement and sand in the same ratio as the cement and sand in the concrete mix. This layer

of cement slurry shall be freshly mixed and applied just before concreting.

Expansion joints

Expansion joints shall be formed and located as detailed in the drawing. Insert sealant to completely fill the joint and finish neat and smooth.

Curing

Curing of concrete is most important. There shall be no compromise on this activity and it is for the contractor to arrange for everything necessary to make sure that the concrete is cured to the complete satisfaction of the Incharge. As said above in clause 3.1.8, after concrete has begun to harden i.e. about 1 to 2 hours after laying,. it shall be protected from quick drying with moist or damped hessian cloth or any other material approved by the Incharge. After 24 hours of laying of the concrete, the surface shall be cured by flooding with water or covering with damp hessian cloth for a period of 7 days to keep it moist.

For the next 7 days the surface shall be kept wet all the time by sprinkling water continuously.

For membrane curing, details as listed in 12.5 of SP 24 shall be followed.

3.1.12 Finishing

Concrete shall be finished keeping in mind the next operation to be carried out over the surface. For guidance the following points shall be noted but the Incharge shall be consulted prior to start of concreting and his decision in this regard shall be final.

a) Roof slab shall be trowelled even and smooth with a wooden float.

b) The surface that will receive plaster shall be roughened immediately.

c) Surfaces that will be in contact with any masonry work shall be roughened immediately,

d) The surface that will receive mosaic floor or IPS or any other type of tiled work shall be roughened while it is green. Every care shall be taken not to disturb the freshly

3.1.13 laid concrete.

3.1.13.1 e) For dust proof (or hardened) finish, clean the concrete surface of oil and contamination and apply approved dust proof hardener as per manufacturers instructions.

Inspection and corrective measures

On removal of form work, the surface shall be examined by the Incharge. Till such time, no remedial measures shall be carried out by the contractor. All patching, rectification or chipping shall be done only on the Incharge's instructions. In case of any

3.1.13.2 violation of this rule, the concrete poured stands rejected. The decision of the Incharge in this regard shall be final and binding on all parties.

Sagged, bulged, patched, honeycombed work shall stand to be rejected for surfaces that are exposed, or require fair face finish or decorative textured finish. The Incharge may permit any work found structurally safe and areas of unexposed faces, for repairing. As directed by the Incharge these works shall be retained and the cost of repair shall be at the contractor's account.

Cracks observed shall be brought to the notice of the Incharge who shall examine them. It shall be kept under observation and a record shall be maintained for a period of 45 days. It shall be shown to (lie Structural Engineer and the following procedure shall be followed :-

a) Cracks not developing further and in the opinion of Structural Engineer not detrimental to the strength of the construction shall be grouted with non-shrinking cement slurry or as directed by the Incharge.

b) Cracks developing further and, in the opinion of the Structural Engineer, detrimental to the

strength of construction, shall be tested as per the relevant Indian standard.

c) Based on results of the test, the Incharge in consultation with the Structural Engineer shall order remedial measures or order the contractor to dismantle construction, cart away the debris, replace the construction and carry out all the consequential works thereto.

d) Cost of the above shall be borne by the contractor if the failure was on his part. In case it is due to design faults, it shall be borne by the employer.

e) The decision of the Incharge in this matter shall be final and binding on all parties. This decision shall not be open for arbitration.

3.1.14 Testing

3.1.14.1 Quantum of cubes and testing

The minimum frequency of cube casting shall be as follows. Each sample shall consist of 6 cubes.

Concrete quantity		Number of Samples.
Upto 5 cu m in a day	:	1
5 cu m to 15 cu m	:	2
15 cu m to 30 cu m	:	3
30 cu m to 50 cu m	:	4
More than 50 cu m	:	4 + one additional per each 50 cum or part thereof

3.1.14.2 Three cubes shall be tested on the 7th day and other three cubes on the 28th day.

Field Tests

It is the responsibility of the contractor to prepare and get the cubes tested and to provide all the material, labour, moulds, equipment, casting and curing facility, charges for testing, etc.

Further, the contractor shall have to provide and maintain all the equipment and staff at the site throughout to carry out the following tests in a small laboratory or get these tests from approved laboratories without extra cost to the contract.

3.1.14.3
a) Grading of coarse and fine aggregates
b) Silt content of sand
c) Moisture content of coarse and fine aggregates
d) Slump test of concrete
e) Concrete cube test

The contractor shall maintain full records of all above tests in a register. The format of records shall be prepared in consultation with the Incharge and either he or his representative shall have full access to the contractor's laboratory.

3.2 The contractor shall include charges for the above work in his rates and no extra whatsoever shall be admissible on this account of designing, testing, maintaining laboratory, etc.

3.2.1 Concreting under special conditions

3.2.2 Work in extreme weather conditions

During hot or cold weather the concreting should be done as per the procedure set out in IS 7861 Part I or IS 7861 Part II or as directed by the Incharge

Underwater concreting

The procedure set out under 13.2 of IS 456 shall be followed or as directed by the Incharge

3.2.3 Concreting in sea water

The procedure set out under 13.3 of IS 456 shall be followed or as directed by the Incharge.

3.2.4 Concreting in aggressive soils and water

Guidelines laid down in 13.4 of IS 456 shall be followed together with the Instructions of the Incharge.

3.3.0 Precast concrete

3.3.1 Precast concrete can be plain or reinforced. It shall meet all requirements and specifications of concrete as stated hereof. Precast concrete shall be done for cellular roof units, drainage or specially designed for specific use taking Into consideration

3.3.2 achievements In flexibility, speed and economy in construction.

Precast concrete units shall be cast in a suitable mould so as to make sure that they are,

a) Easy to lift

b) Easy to transport

c) Excellently finished

3.3.3 d) Handy to erect and Join at site

Units shall be sound and free from cracks or any other defects that would interfere with the proper placing of units or the strength or performance of units or the structure.

Precast units shall be lifted and handled with proper tools from points designated to avoid any cracking or developing of any undue stresses . If required, necessary tools and tackles shall be fabricated by the contractor. Precast units shall be removed from mould within 24 hours or the time allowed by the designer or as approved by the Incharge.

All units that are. in the opinion of the Incharge, cracked and unsafe, shall be removed forthwith and no arbitration on this

3.4.0 account shall be applicable.

Units shall be stored and stacked in the precasting yard in a proper manner. The date of casting shall be noted therein and wet curing for 15 days shall be done without fail. The yard shall have a duly dressed ground and sufficient supports at the required intervals to receive precast units.

Units shall be erected only after 28 days of casting and after the cubes of those days have given the strength specified.

Tolerances in units shall not be more than ±3 mm as approved by the Incharge taking into consideration the purpose and location of use.

Plum Concrete

Stone plums shall be used only when specified. Size of stone plums may be from 150 to 300mm.

Plums shall be hard, double clean and free from soft or loose pieces or deleterious material and should not have sharp corners.

Generally first layer of concrete of specified mix shall be of thickness 2.5 time thickness of maximum size of plums to be used. Plums shall be laid when concrete becomes stiff but top portion is still green. No plums shall be used for concrete laid under water. The thickness of next and successive layers shall be 2 times that of largest plums.

3.5.0 Measurements

1. All works shall be measured in the decimal system.

a) Dimensions shall be measured to the nearest 0.01 metre except for thickness of slab which shall be measured to the nearest 0.005 metre.

b) Areas shall be worked out to the nearest 0.01 sq m

c) Cubic contents shall be worked out to the nearest 0.01 cum

2. All measurements of cutting shall, unless otherwise stated, be held to include the consequent waste.

3. Cement concrete work shall be classified as under:

a) Concrete cast in-situ : Plain and reinforced

b) Precast concrete : Plain and reinforced

c) Prestressed concrete : Cast in-situ or pre-cast

4. All concrete, except as hereinafter provided, shall be measured in cubic metres.

5. The price of concrete shall include ingredient material, mixing, transporting, hoisting to any height and lowering to any depth, pouring or laying, consolidating, leaving pockets, holes, and protecting them till the next operation or completion of work, hacking the surface to provide key for further work including cleaning, wetting surface, etc. and preparing construction joints as described in clause 3.1.9. of this section.

6. Concrete processed in a special manner for any specific purpose, such as cooled, heated, water-proofed, acid-proofed, heat-resistant shall be measured separately and as per provision in BOQ.

7. Admixtures shall be used if necessary at the request of the contractor for workability and the price for that shall be deemed to be included in the contractor's quoted price of concrete.

8. No deductions shall be made for:

(a) Ends of dissimilar materials (for example beams, posts, girders, purlins, corbels and steps) upto 500 sq cm in section.

(b) Opening upto 0.1 sq m,

(c) Volume occupied by reinforcement.

(d) Volume occupied by drainage, water pipes, conduits, etc. not exceeding 100 sq cm, each in cross sectional area.

(e) Small voids each not exceeding 40 sq cm in section.

(f) Small moulds, drip moulds, chamfers, splays, rounded or covered angles, beads, grooves and rebates upto 10 cm in depth and width.

9. Expansion joints shall be measured in running metre or sq m as the case may be. Price shall include required shuttering, special treatment if any, filler and finishing material as detailed in drawing or the BOQ.
10. Water proofing of concrete shall be measured separately as an extra over ordinary concrete stating the quantity of water proofing material in litres or kilograms.
11. Surface treatment shall be measured in square metres stating number of coats and proportioning of water proofing liquid to water.
12. Grouting of holding-down bolts and providing temporary boxing or wedges to form holes shall be enumerated. The mix shall be specified. The price shall include required shuttering, grouting, etc.
13. To keep surface dry while concreting, dewatering due to rains and seepage shall be included in the price of concrete.

REINFORCEMENT WORK

1.0 GENERAL

1.1 Standard

Work shall be carried out to Indian Standards and Code of Practices. In absence International Standards shall be followed. These shall be latest issue. List given hereunder is not to be considered as conclusive and is for reference and guidance only. Any discrepancies/ conflict noticed shall be directed to the Incharge for his direction/approval. However as a general rule more stringent specification shall take precedence.

1. IS 226 Specification for steel standard quality.
2. IS 228 Methods for chemical analysis of steels.
3. IS 280 Specification for mild steel wire for general engineering purpose.
4. IS 432 Specification for mild steel and medium tensile

		steel burn and hard drawn steel wires for concrete requirement.
	Part 1	Mild steel and Medium tensile steel bars.
	Part 2	Hard drawn steel wire.
5.	IS 456	Code of practice for construction and design of reinforced concrete.
6.	IS 816	Code of practice for use of metal are welding for general construction in mild steel.
7.	IS 961	Specification for structural steel: high tensile steel bars
8.	IS 1566	Hard drawn steel wire fabric for concrete reinforcement.
9.	IS 1599	Method of Bend test
10.	IS 1642	General requirements for fire protection.
11.	IS 1785	Cold drawn stress relieved wire (part I)
12.	IS 1786	Specification for high strength deformed steel bars and wires for concrete reinforcement.
13.	IS 2751	Code of practice for welding of MS bars.
14.	IS 2502	Code of practice for bending and fixing of bars for concrete reinforcement.
15.	IS 2751	Code of practice for welding of MS Bars.
16.	IS 3696	Safety Code of scaffolds and ladders:
	Part I	Scaffolds
	Part 2	Ladders
17.	IS 4014	Code of practice for steel (Part 1 & 2) tubular scaffolding

18.	IS 4082	Recommendation on stacking and storage of construction materials at site.
19.	IS 5525	Recommendation for detailing of reinforcement in RCC work.
20.	IS 9417	Recommendation for welding cold worked steel bars for reinforced concrete construction.
21.	IS 10790	Method of sampling of steel for priestesses and reinforced concrete.

1.2 Quality Assurance

1.2.1 The Contractor shall procure and provide reinforcing steel bars conforming to IS specified and shall comply with all physical, chemical and mechanical test. Each type shall be from same manufacturer.

1.2.2 Steel manufacturers shall conform steel produced conforms IS requirements for reinforced cement concrete works.

Steel shall not react chemically with ingredient of reinforced cement concrete which are harmful to strength, durability of reinforced cement concrete.

1.2.3 Unit weights and diameter of rolled steel bars shall conform to IS.

1.2.4

Provide supervision and work force with minimum 5 (five) years experience to ensure workmanship of specified quality.

1.2.5 Contractor to undertake documenting of

- Test reports for steel brought at site for each lot
    a) Chemical composition from factory
    b) Mechanical
    c) Physical

- Barbending schedule for cutting and bending
- Record of laps and anchors / development length

1.2.6 Work shall not be subjected to harmful, dangerous and damaging exposures.

1.3 Submittals

1.3.1 Submit for approval of the Incharge all details of Material / Product which conforms the specification laid down in documents.

1.3.2 Submittals shall include

- Product data sheet
- Manufacturers certificates
- Test report of laboratories
- Alternative product if any with tabulation for conformation that alternatives proposed meets / exceeds specification.

1.3.3 Samples

Samples of type materials to be used. Further during construction samples shall be taken and tested by the Contractor as per specification and as directed / instructed by the Incharge. The cost of samples and test shall be borne by the Contractor within quoted prices.

1.3.4 Shop drawings

Contractor shall prepare and submit bar bending schedule based on structural detailed drawing prior to fabrication for approval of the Incharge.

Examination of Conditions

1.4 Contractor shall inspect and examine sub strata and confirm prior to start that.

- Substrate is acceptable and approved by Incharge
- Conditions are satisfactory
- Setting out/Layout is verified
- Corrective measures needed if any are within reach and contractor proceeds with full responsibility for work.

MATERIAL

Reinforcing Bars

2.0

2.1.0 Reinforcement bars used in construction shall be mild steel or medium tensile steel round bars and high strength deformed bars. Steel shall be fresh and new. It shall be free of defects and free of rust, oil, paints, grease, loose mill scale or any other deleterious material undesirable for RCC or prevent adhesion of concrete with reinforcement.

2.1.1

M S Plain

2.1.2 Rolled mild steel and medium tensile steel plain round bars used in concrete shall conform to IS 432 Part I. Steel received shall conform to the following IS with regard to manufacturing and chemical composition.

1. M.S. bar Grade I Steel designation Fe 410-S of IS 226

2. M.S. bar Grade II Steel designation Fe 410-0 of IS 1977

3. Medium Tensile Steel designation Fe 540 Steel bars W-HT IS 961

2.1.3 Nominal sizes and tolerances shall be as specified in IS 432 Part I. Physical requirements shall be determined in accordance with IS 1608, read in conjunction with IS 226. For

2.1.4 reference of minimum requirements, properties are tabulated in IS 432 Table 1 "Mechanical properties of bars mild steel & tensile steel bars".

2.1.5

Tor / TMT (Thermo-Mechanically-Treated) Steel

2.1.6 High-strength deformed bars for use as reinforcement in concrete shall be of grade Fe 415, Fe 500 and Fe 550 conforming to IS 1786.

2.1.7 Chemical composition shall conform to IS 1786 when made as a relevant part of IS 228.

Welding of cold work steel bars in reinforcement shall be permitted as per IS 2751 and 9417. (Recommendation for welding cold worked steel bars for RCC).

Nominal sizes, cross sectional areas and their mass shall be as specified in IS 1786, allowing due consideration for tolerances specified therein.

2.1.8 Physical properties

a) It shall satisfy IS 1599 test for bend and rebend test in conjunction with IS 226.

b) Bond requirements shall be deemed to have been satisfied if it meets clause 4.Oof IS 1786.

2.1.9 c) Tensile, proof stress and percent elongation shall be as per table 3 of IS 1786.

Material received at site shall have ISI certification mark. Each bundle or coil containing the bars shall be suitably marked with ISI certification mark. Also bars shall be marked to identify categories. This shall be done as per IS 1387.

In case bars are without ISI certification mark, the manufacturer shall give a certificate stating process of manufacture, chemical composition and mechanical properties. Each certificate shall indicate the number or identification mark of the batch production/ cast to which it

applies. Corresponding number or identification mark should

2.1.10 be found on the material.

All reinforcement material shall be free from loose mill scale, excessive rust, loose rust, pitting, oil, grease, paint, mud or any foreign deleterious material present on the surface.

2.1.11 Cleaning shall be done to the satisfaction of the Incharge.

Each batch brought at site shall be tested prior to use for respective specification / physical properties. Cost of all such tests shall be borne by the contractor. Material acceptable as per IS shall be allowed into the works. All rejected material shall be removed from site by the contractor within 3 days of rejection. If the same is not done, the Incharge shall impose a

2.2.0 penalty of Rs.500/- per metric ton per day. This will be without any appeal and shall not be subjected to arbitration.

Cover block

Cover blocks shall be of non-corrosive material such as plastic but not wooden or broken bricks or stone. Designed purpose made PVC cover spacers shall be used in the Works. Concrete cover spacers may be permitted by the Incharge. Such

2.3.0 concrete spacers shall be cast from concrete and not cement-mortar. Strength of these blocks shall be equal to the strength of concrete in use. These should be fully cured prior to use in works.

Binding Wire

2.4.0 Binding wire shall be 16 or 18 gauge annealed wire conforming to IS 280. It shall be free from rust, oil, paint, grease, loose mill scale or any other deleterious material undesirable for the reinforcement and concrete or which may prevent adhesion of concrete with reinforcement.

Mechanical Splices

Mechanical Splices fabricated out of steel pipes, sheets etc. capable of withstanding bending and compression stress equal to 1.25 times of those specified for reinforcing bars shall be used. Supplier of splices should submit details about quality of materials, mechanical test results and method of

splicing. Required hydraulic press and clipping equipments shall be arranged by the Contractor.

Sa Samples pieces shall be prepared at site and shall be tested for torsion.

Sample pieces results should give value of about 1.5 times than required for reinforcing bars.

2.5.0 Delivery and Storage

Reinforcing steel bars each batch should accompany manufacturers certificate. Reinforcement bars received at site shall be loaded and unloaded at site and stored with care such that it does not get bent or damaged. Steel received shall be as far as possible in straight length of 12 M. Steel shall be weighed in presence of representative of the contractor prior to delivery being received by him. Empty and loaded truck loads shall indicate correct quantity.

Reinforcement bars received at site shall be stored on hard concrete platform and clear of the ground with the use of timber sleeper, concrete sleeper or any other means. Reinforcement material shall be kept covered by tarpaulins or plastic to avoid excessive corrosion and other contamination. Each dia of bars shall be stacked separately. Bars without "ISI' / Tor marking shall not be brought to site.

3.0

3.1 **SCOPE OF WORK**

The contractor shall be responsible for

Material Procurement

a) The contractor will submit the Schedule of Procurement of steel in consultation with Incharge as specified and conforming to specifications detailed in drawings and bills of quantities.

The steel is free supply by the client to be delivered to site as per approved indent of the contractor to agreed schedule. However further all balance work to

complete the reinforcement bar item shall be same as materials are supplied by the Client.

b) Receive steel and stack with covering on firm platform free of contamination.

c) Collect samples of each type for every batch received and test as per IS for

- Unit weight per running meter
- Cross section area
- Bend / Rebend Test

3.2

- Ultimate tensile strength
- Yield stress
- Elongation

d) Procure binding wire, cover blocks splices etc.

Prepare bar bending / cutting schedule detailing schedule covering as under and obtain approval of Incharge.

3.3

- Cutting lengths

3.4

- Laps
- Rings for various locations and items

3.5

- Chairs

Transport, cut, bend and shift to site reinforcing bars.

Place in position and tie as detailed in drawing reinforcement with specified cover

Provide attendance to keep reinforcement in position during concreting.

3.6 Disposal of surplus reinforcement steel as per approval of the Incharge.

3.7 Providing required tools, plants, equipments such as

- Material cutting and bending tools
- Bending platform Bar cutting machine
- Bar bending machine
- Hydraulic clipping machines

Unit weights payable per metre shall be as follows-

3.8

1. 6mm : 0.22 kg/Rmt
2. 8 mm : 0.40 kg/Rmt
3. 10 mm: 0.62 kg/Rmt
4. 12 mm: 0.89 kg/Rmt
5. 16 mm: 1.58 kg/Rmt
6. 18 mm : 2.00 kg/Rmt
7. 20 mm : 2.47 kg/Rmt
8. 22 mm : 2.98 kg/Rmt
9. 25 mm : 3.85 kg/Rmt
10. 28 mm : 4.83 kg/Rmt
11. 32 mm : 6.31 kg/Rmt
12. 36 mm : 7.99 kg/Rmt
13. 40 mm : 9.85 kg/Rmt

WORKMANSHIP

4.0 Fabrication of reinforcement

4.1 Reinforcement shall be fabricated as per the drawing and approved bar bending schedule. Bending shall be done mechanically or with hand but to the correct radius, with proper tools and platform and shall conform to IS 2502. Bending of material shall be cold bending only. Material shall be inspected for visible defects such as cracks, brittle, excessive rust, loose mill scale, etc. Cracked ends of bars shall not be used in Works. Also the bars should be free from any deleterious material and hence the best practice shall be to hose down reinforcement just prior to concreting.

It is important that bending, straightening, cutting, etc. shall be carried out in a manner not injurious to the material and the safety of the persons working should be ensured.

4.2 Anchoring

Anchoring of bars and stirrup shall be provided exactly as detailed in the structural drawing or as directed by the Incharge.

4.3 Lapping of bar

Laps shall be strictly as per the drawing or as directed by the Incharge. For general guidance, the following principles shall

be followed as given in IS 456.

a) Splices shall be provided as far as possible away from sections of maximum stress and be staggered.

b) Not more than half of the total bars shall be spliced at a section.

c) Where more than one half of the bars are spliced at a section or where splices are made at points of maximum stress, special precautions shall be taken, such as increasing the length of lap and/or using spirals or closely spaced stirrups around the length of the splice.

d) Lap splices shall not be used for bars larger than 36 mm diameter: For larger diameters, bars may be welded. In cases where welding is not practical, lapping of bars larger than 36 mm diameter may be permitted and additional spirals should be provided around the lapped bars.

e) Lap length including anchorage value of hooks in flexural tension shall be Ld (as defined in 25.2,1 of IS 456) or 50 dia whichever is greater.

f) When splicing of welded wire fabric is to be carried out, lap splices of wires shall be made so that the overlap measured between the extreme cross wires shall be not less than the spacing of cross wires plus 10 cm.

4.4 Spacing of bars

Bars shall be placed in position as shown in the drawing. Following guidelines as given in IS 456 shall be followed in case of difficulties or shall be carried out as directed by the Incharge.

a) Horizontal distance between two parallel main reinforcing bars shall usually not be less than the greatest of the following:

1. The diameter of the bar, if the diameters are equal.

2. The diameter of larger bar, if the diameters are unequal, and

3. 5 mm more than the nominal maximum size of coarse aggregate (By using reduced size of aggregate in congested reinforced area, conditions given hereof should be overcome).

b) Greater horizontal distance should be provided. But when needle vibrators are used, distance between bars of a group may be reduced to two-thirds of the nominal maximum size of the coarse aggregate, provided sufficient space is left between groups of bars to enable the vibrator to be immersed.

c) Where there are two or more rows of bars, the bars shall be vertically in line and the minimum vertical distance between the bars shall be 15 mm, two-thirds the nominal maximum size of the aggregate or the maxim size of bar, whichever is more.

4.5 Cover to reinforcement

Reinforcement shall have concrete cover and the thickness of such cover (exclusive of plaster or other decorative finish) shall be as specified in drawing or as directed by the Incharge. The following guidelines are to be observed in the absence of the above.

a) At each end of the reinforcing bar, not less than 25 mm, nor less than

twice the diameter of such bar;

b) For a longitudinal bar in a column, not less than 40 mm, nor less than the diameter of such bar. In the case of columns of minimum dimension of 200mm or under, whose reinforcing bars do not exceed 12 mm, a cover of 25 mm.

c) For longitudinal reinforcing bar in beam, not less than 25 mm, nor less than the diameter of such bar.

d) For tensile, compressive, shear or other reinforcement in slab, not less than 15 mm, nor less than the diameter of such bar; and

e) For any other reinforcement, not less than 15 mm, nor less than the diameter of such bar.

f) Increased thickness shall be provided in case the concrete members are in the surrounding of harmful chemicals, saline atmosphere, etc. and the cover shall be 50 mm or more as directed by the Incharge.

g) For concrete members totally immersed in sea water, the cover shall be 40 mm more than specified above (a) to (f). This shall be 50 mm more for periodical immersion in seawater.

h h) Concrete cover should not exceed 75 mm in any case.Cover to reinforcement shall be as specified in the drawing or as directed by the Incharge.

Details given in sub para (a) to (h) are for guidance and shall be followed in absence of any specific direction.

4.6

Welded joints or mechanical connections

A) Welded joints or mechanical connections in reinforcement may be used but in all cases of important connections, tests shall be made to prove that the joints are of the full strength of the connected bars. Welding of reinforcement shall be done in accordance with IS recommendation. Welded joints shall preferably be located at points where steel will not be subject to more than 75 percent of the maximum permissible stresses and welds so staggered that, at any one section, not more than 33 percent of the rods are welded.

B) Welding rods used shall conform to IS 814 : covered electrodes for metal arc welding of structural steel. Work shall be carried out by a competent welder. Samples from work site shall be taken at regular intervals and tested. Frequency and number of samples shall be as directed

by the Incharge.

Fixing in position

Correctly cut and bent bars shall be accurately placed In position as detailed in the drawing. Unless otherwise specified by the Incharge, reinforcement shall be positioned within the tolerance as under:

a) for effective depth 200 mm or less, +10 mm

b) for effective depth more than 200 mm, +15 mm

But in no case shall the cover be reduced by more than 5 mm of that specified. There shall be no compromise on cover for foundation work.

Reinforcing bars shall be held in position during the placing of concrete by use of PVC or concrete cover blocks (made of equal strength of well-cured concrete in use), steel chair spacers, steel hangers, supporting wires, etc. and secured by tying with an annealed binding wire of 16 to 18 gauge as approved by the Incharge.

Layer of bars shall be separated by precast concrete spacer blocks or spacer bars. Reinforcement shall be in correct position prior to start of concreting. No reinforcing bar shall be placed on freshly laid concrete for adjusting bar spacing. Care shall be taken to maintain reinforcement in position and keep it clean, throughout the period till it is embedded in the concrete. For maintaining cover, pieces of broken stone or brick or wooden blocks shall not be used at any stage.

Where reinforcement bars are bent aside at construction joints and afterwards bent back into their original position, care should be taken to ensure that at no time is the radius of the bend less than 4 bar diameters in case of plain mild steel or 6 bar diameters for deformed bars. Care shall be taken when bending back bars to ensure that the concrete around is

not damaged/disturbed.

MEASUREMENTS

Reinforcement shall be measured as follows:

1. Lengths of different diameters of bars actually used including authorised overlaps shall be measured nearest to a centimeter and their weight calculated.

   a) If steel is procured by the contractor, weight per metre given in table 3.9 shall be used.

   b) If material is supplied by the client free of cost on tonnage basis to the project site, per metre weight for each diameter of the bar shall be fixed by the incharge from actual

   stocks of steel available at site or weight per meter given in

   table 3.9 shall be used.

2. Chairs and spacer bars shall not be measured and paid. For reconciliation purpose it will be taken into account.

3. In case of welded coupled joints, measurement for payment shall be equivalent to the length of overlap, as per design.

4. Price build-up shall include, in addition to cost of material,

   a) Cover blocks of PVC or concrete.
   b) Cutting, bending, placing and fixing in position.
   c) Binding wire as approved.
   d) Cleaning of bars.
   e) Unloading, weighing cost (to conform the weight of steel) and

   storing the same in proper forms and conditions

on platforms.

5. In case the material is supplied by the owner free-of-cost, it shall include the following in addition to 4a) to 4d) above.

Transportation from owner's store to work site and returning surplus material back to store.

6. For purpose of reconciliation, maximum wastage permitted shall be 3% of the actual material used (returnable to owner). Balance shall be charged at 1.5 times the actual market rates as penalty.

FORM WORK

1.0 GENERAL

1.1 Standards

Work shall be carried out to Indian Standards and Code of Practices. In absence International Standards shall be followed. These shall be latest issue. List given hereunder is not to be considered as conclusive and is for reference and guidance only. Any discrepancies/conflict noticed shall be directed to the Incharge for his direction/approval. However as a general rule more stringent specification shall take precedence.

1.	IS 303	Specification for plywood for general purpose.
2.	IS 456	Code of practice for construction and design of reinforced concrete.
3.	IS 2751	Code of practice for welding of M.S bars used for RCC

4.	IS 3696	Safety Code of scaffolds and ladders :
	Part 1	Scaffolds
	Part 2	Ladders
5.	IS 4014	Code of practice for steel (part 1 & 2) tubular scaffolding
6.	IS 4082	Recommendation on stacking and storage of construction materials
7.	IS 8989	Safety code of erection of concrete formed structures

1.2 Quality assurance

Contractor shall assume and take upon himself to

a) Design, construct, erect, maintain and struck form work proprietary or custom made

b) Form work shall provide required

- Shape, size and finish
- Rigidity and durability during placing(live levels)
- Rigidity and durability for receiving fresh concrete
- Leak proof water tight joints/junctions
- Easy removal without disturbing concrete
- Provide easy access for handling and placing

c) Form work shall provide safety and shall have adequate access for concreting

d) Workers shall work with required safety measures such as safety belts,

1.3 Experience

The contractor shall provide

a) Site supervisors and foremen qualified and experienced atleast 5(five) years on similar nature of form work.

b) Semi skilled/skilled labour shall be of minimum experience of 5(five) years in doing similar nature of form work

1.4 Examination of strata

The contractor shall examine, and convince himself prior to start of work that strata is firm, rigid and safe to erect scaffold. In absence, same shall be prepared by him and then work shall proceed. If it is not possible due site condition, method of erection support etc. shall be detailed and got approved from Incharge prior to start. In any case responsibility of formwork shall be that of the contractor.

2.0 MATERIAL

2.1 Timber

a) Jungle wood timber in form of planks, battens (runners), ballies, strong durable without cracks, able to sustain warping, twisting and distortion shall be allowed in work for type of requirements.

b) Teak wood /good quality jungle wood shall be used for special decorative moulds. Moulds may be smooth planed or finished with laminate

2.2 Steel

Standard rolled steel sections shall be used with due fabrication of standard special moulds, unitised form work scaffolds, staging etc.

2.3 System

Patented proprietary designed metal (Steel, aluminium or fiber glass) form work best suited for type of work under taken and its requirements shall be used.

2.4 Wire nails confirming to IS and mating needs shall be used.

2.5 Bolts / Nuts /Clamps

MS bolts, nuts, clamps standard or purpose made shall be used. Use of these shall not be harmful to concrete and shall be easily

removable or If left In concrete shall be inert to concrete in all respect.

2.6 Form release Agents

Emulsion and oil or chemical agent being used shall not react with reinforce concrete at any stage. No chemical reaction shall take place which may be harmful to reinforcement concrete for its durability strength. These shall not produce any stain and shall not stick to concrete surfaces which will reduce further bonding strength of masonry mortar, painting etc.

3.0 SCOPE OF WORK

3.1 Designing

The contractor shall draw, prepare and submit method of statement backed by designed calculations, taking into account the points noted in clause 1.2 here above at least six weeks prior to the starting of activity. Required drawing and sketches shall be enclosed along with statement for the proposed area to be taken up for working. The statement shall give

- Loadings considered
- Materials proposed
- Repetitions expected
- Staging/supporting arrangement
- Deployment of proprietary metal form work system.
- Method of handling

It shall be responsibility of the contractor to get the design approved from Incharge atleast four weeks prior to start of form work.

3.2 Equipments

The contractor shall provide required tools, plants, equipments including its proper maintenance during construction at site.

3.3 Proprietary metal formwork

The contractor shall arrange to provide proprietary system metal formwork applicable/adoptable to various areas of works. He shall be responsible to deploy with required mechanism for handling, shifting, transporting placing in position.

3.4 Supervision

The contractor shall be responsible to provide experienced foremen (atleast Five years) in supporting/executing similar nature and magnitude of work. He shall be able to read drawings and should be capable of guiding and getting work executed to quality.

3.5 Labour

The contractor shall provide experienced skilled carpenters to carryout work with system of formwork deployed and necessary plants and equipment shall be made available at site.

4.0 WORKMANSHIP

4.1 Form work shall be classified namely as follows :

a) Textured or decorative finish

b) Fair-faced finish

c) Rough finish

4.2 In BOQ, the contractor shall account for all material and labour etc. to achieve the above finishes to the satisfaction of the Incharge in his quoted price.

1. Erection of form work may be from pre-moulded, pre-fabricated, pre-assembled plates or forms reasonable enough to transport and erect at site to correct line and level as set out at site. Supports shall be firm and maintained in position by nails, cross bracings, tie rods, locking bolts and nuts. It shall be rigid and stiff so as to retain its shape during and after concreting.
2. Joints shall be water-tight and no cement slurry shall be allowed to slip through. In joints foamed tapes shall be used.
3. Pre-fabricated or site forms shall be assembled, so as to deshutter without any jerk to the green concrete. For this double wedges shall be used. Wedges shall be nailed, the heads reasonably left out, allowing easy removal while

deshuttering.

4. Pre-fabricated or on site fabricated forms shall be of sufficient thickness and with the required supporting runners in either direction. Supporting runners shall be standardised in size for easy replacement and universal use at site.

5. Props shall be of steel only. Teak ballies may be permitted with written permission of the Incharge for specific use. Size and verticality shall be approved by the Incharge. Its spacing shall be as per design. It shall be vertical and plumbed. Base shall be a proper steel plate or timber plank, for equal distribution of load.

6. In repeated use, panels shall be clearly marked for using at defined locations.

7. Successive lift shall be tightened with previous lift by fixing foamed strips at joints to avoid grout leakage.

8. In fill pieces and panels shall be well dressed, leveled and jointed with main formwork so as to achieve smooth, even natural finish.

9. Props, Soldiers, wallings, Shores, bearers, Clamps, wall & ties etc. shall be at required spacings.

10. Props, shores shall be securedly braced with firm bearing.

11. Provide and fix or fix only inserts pockets, to correct line and level and with sufficient rigidity to keep in position while concrete placing is in progress along with vibration.

12. Sloping, brackets, chajjas etc shall be well secured and firmly restrained.

13. Adequate access and working platform shall be arranged with required safety to avoid reinforcement displacement,

damage to shuttering and easy movement of concrete gang.

14. Props and scaffolds are to be erected to correct plumb, line, level and with required tie. Load carrying capacity of props shall be as per table of manufacturer.

15. Props and scaffolds shall not be loaded more than allowed by manufacturer of Props /scaffolds.

16. Heavy, medium and light duty props shall not be mixed up.

17. Beams and slabs shall have camber of 4 mm per metre or as directed by the Incharge.

18. All angles and corners shall be sharp and well defined. In places where concrete edges are permanently exposed and require no further treatment, they shall be chamfered in a triangle of 25x25mm.

19. Props of steel or timber (if approved in writing) shall be provided with adequate horizontal and cross - bracing. Steel props shall use steel pipes and steel couplers. If use of timber is permitted, planks of 100 x 25 mm shall be used and shall be secured by nailing them to timber props. No other material shall be permitted.

20. At the design and erection stage, the following additional points shall be considered and incorporated into the shutters.

    (a) Openings for cleaning prior to start of concreting.

    (b) Pouring points shall avoid high drops and provide easy access to vibrator needles.

21. Surfaces shall be treated with mould releasing oil or emulsion as approved by the Incharge prior to reinforcement laying.

22. The following point shall be observed very carefully:

    (a) Joints of moulds shall be water tight. It is easy to check from bottom and make sure that no light is visible.

(b) Props shall be on solid base, plumbed, in one straight line, and braced horizontally and cross.

(c) Tie bars in beams, walls and columns shall be at the correct place and fully tight.

(d) Wedges shall be fully secured and nailed with head left out for easy removal.

(e) All saw dust, dirt, shaving and any other unwanted materials shall be cleaned and hosed out.

(f) Provision shall be made for watching form work while concreting and any other platform needed for movement of workers without any disturbance to reinforcement.

23. Opening/inserts

All required openings and pockets shall be provided as detailed in the drawing. The contractor shall provide for the required material, labour for fixing and supporting during concreting, in his quoted price. It is imperative that all openings and pockets shall be deshuttered with care and all corners of openings shall be preserved. All openings/pockets shall be in a correct line and level. After concreting, the openings shall be secured by proper covering against any accident and guard rail and warning notice, if any will be incorporated.

24. In case of multistoried building, any upper floor shall be suitably supported on atleast one floor below the same or as approved by the Incharge. The concreting of upper floor shall be done only after lower floors have attained the strength.

4.3 Checking prior to concreting.

1. All props and struts are plumbed at right spacing properly tightened up and locked.
2. Formwork is correctly aligned and leveled.
3. Stop ends are properly secured and sealed.
4. All ties are properly tightened.

5. All inserts, pockets etc are at desired level and secured.

6. Joints are sealed and no possibility of leakage of grouts.

7. Reinforcement has proper covers and required spacers.

8. All forms are cleaned, free from rubbish, tie wires etc.

9. Proper access for concreting and compaction available.

10. Required guard rails, toe boards are provided.

4.4 Tolerances

4.4.1 Tolerance is a specified permissible variation from lines, grade or dimension given in drawings. No tolerances specified for horizontal or vertical building lines or footings shall be considered to permit encroachment beyond the legal boundaries. Unless otherwise specified, the following tolerances will be permitted.

4.4.2 Tolerances for RCC buildings

1. Variation from the plumb:

   (a) In the lines and surfaces of columns, piers, walls and in arises 3 mm per 2.5 m but not more than 10 mm.

   (b) For exposed corner columns and other conspicuous lines,

   In any bay upto 5 m maximum : 5 mm

   In 10m or more : 10mm

2. Variation from the level or from the grades indicated on the drawings,

   (a) In soffits of slab, ceilings, beam and in arises

   In 2.5 m 5 mm

   In any bay upto 5 m maximum 8 mm

In 10m or more	10 mm

(b) For exposed lintels, sills, parapets, horizontal grooves and other conspicuous lines,

In any bay upto 5 m maximum	5 mm
In 10m or more	8mm

3. Variation of the linear building lines from established position in plan and related position of columns, wall and partitions.

In any bay upto 5 m maximum	5mm
In 10 m or more	10 mm

4. Variation in the sizes and location of sleeves, openings in walls and floors 5mm (except in the case of and for anchor bolts).

5. Variation in cross-sectional dimensions of columns and beams and in the thickness of slabs and walls - 5 mm + 10 mm

6. Footings

a) Variation in dimension in plan • 5 mm + 50 mm

b) Misplacement or eccentricity

2% of footing width in the direction of misplacement but not more than 50 mm

c) Reduction in thickness

5% of specified thickness subject to a maximum of 50mm

7. Variation in steps

		Riser	Tread
a)	In a flight of stairs	3mm	5mm
b)	Consecutive steps	1.5 mm	3 mm

4.4.3 Tolerances in other concrete structures.

1. a) Variation of the constructed linear outline from established position in plan

   In 5 m : 5 mm

   In 10m or more : 10mm

   b) Variations of dimensions to individual structure features from established positions

   In 20m or more : 25mm

   In buried construction : 50 mm

   c) Variation from plumb, from specified batter or from curved surfaces of all structure

   upto 2.5 m : 3 mm

   2.5 m to 5 m : 8 mm

   5m to 10m or more : 12mm

   In buried construction : Twice the above

   d) Variation in cross sectional dimensions of columns, beams, buttresses, piers and similar members

   (-) 5mm (+) 10mm

   e) Variation in the thickness of slabs, walls, arch sections, and similar members.

   (-) 5 mm (+) 10 mm

2. Footings for columns, piers, walls, buttresses and similar members.

a) Variation of dimensions in plan

(-) 10 mm (+) 50 mm

b) Misplacement or eccentricity

2% of footing width in the direction of misplacement but not more than 50 mm

c) Reduction in thickness

5% of specified thickness subject to a maximum of 50mm

4.5 Removal of Form work

1. Forms shall not be struck until the concrete has reached strength at least twice the stress to which the concrete may be subjected at the time of removal of form work.

Under normal circumstances and where 53/43 grade 0.P.Cement is used, forms shall be removed after expiry of the following periods:

a)	Walls, columns and vertical faces	24 to 48 hrs
b)	Slabs (props left under)	3 days
c)	Beam soffits (props left under)	7 days
d)	Removal of props under slabs	
	(i) Spanning upto 4.5 m	7 days
	(ii) Spanning over 4.5m	14 days
e)	Removal of props under beams and arches	
	(i) Spanning upto 6 m	14 days
	(ii) Spanning over 6m	21 days

For other cements, the stripping time shall be suitably modified in consultation with the Incharge.

2. Where the shape of elements is such that the form work has re- entrant angles, the form work shall be removed as soon as possible after the concrete has set, to avoid shrinkage or cracking that might occur due to the restraint imposed.

3. For precast moulds, the stripping time shall be 24 hours. The mould may be lifted and stored in the yard within 24 hours to 48 hours as approved by the Incharge.

4.6 Maintenance

It shall be responsibility of the contractor to protect, maintain and handover to next contractor / Employer in finished condition. No additional cost due to this shall be paid by the Employer Providing and fixing inserts is part of this

a) On completion of concreting inserts shall be cleaned and required treatment such as oiling, greasing, covering with plastic/plywood boxes, painting etc. shall be carried out by the contractor to approval of the Incharge. Inserts and pockets shall be protected from weathering/or damage in course of construction.

b) Opening and pockets shall be deshuttered with due care not to damage edges, falling of debries within pockets etc. Further all opening and pockets shall be preserved, secured against accident by covering, putting up guard rails, warning notice etc. as approved by the Incharge. Guarding and protecting pockets shall be responsibility of the contractor at no extra cost to contract.

4.7 Cleaning/Stacking

All formwork deshuttered shall be cleaned with a stiff wire brush to remove dust, grout, concrete etc. and if required maintained/repaired prior to being reused. Steel plates, props, frames, proprietary formwork system shall be oiled, greased to protect against rusting, weathering etc.

Plywood and timber form shall also be applied with preservative agent if to be kept for long time without use. It shall be protected against heat, rains etc.

4.8 Measurements

Form work shall be paid for separately as per item details given in BOQ.

Wherever it is not specifically stated in description of the item that form work shall be paid for separately, the rate of R.C.C. item shall be deemed to be included in the cost of the form work.

1. Form work shall be measured as the area (in square meters) of shuttering in contact with the concrete.

2. It shall be measured to the nearest centimeter and the areas worked out corrected to second decimal places.

3. No deductions shall be made for openings upto 0.4 sq m in the plan.

4. Form work to secondary beams shall be measured upto sides of the main beams but no deduction shall be made from the form work of the main beam.

5. No deduction shall be made from the form work of column at intersection of the beam.

6. The quoted rate shall be applicable for all working conditions and at all heights, depths or lifts specified in the BOQ. The rate shall include the cost of materials and labour for various operations involved, such as,

a) Splayed edges, notching, allowance for overlaps and plastering at angles, battens, centering, shuttering, strutting, propping, bolting, nailing, welding, casing, striking and removal.

b) Filling to form stop chamfered edges or splayed external angles not exceeding 75 mm to footing and 25 mm to beams, columns and like.

c) Temporary openings in the forms for pouring concrete and removing rubbish.

d) Dressing with oil/approved emulsion/soap solution to prevent adhesion of concrete with shuttering.

e) Racking or cutting

f) Fixing inserts and openings at the correct line and level and any required stage to support the same at the directed height and place.

g) Platforms, if any, required to keep check on form while the concreting is in progress.

h) Filling and making joints water-tight to the satisfaction of the EIC.

i) Cleaning the shuttering.

7. Any work damaged through premature or careless removal of form shall be removed and reconstructed at the contractor's cost.

8. Holes for electrical conduits, hooks for fans and for plumbing are included in the price of items.

HOLLOW AND SOLID CONCRETE BLOCK MASONRY

1.0 Hollow and solid concrete blocks **– Shall conform to the requirements of IS: 2185. Specification for hollow and solid concrete blocks except with regard to the mix of cement concrete and sizes of aggregates which shall be as indicated. Hollow blocks shall be sound, free from cracks, broken edges, honey combing and other defects that would interfere with the proper placing of block or impair the strength or performance of construction.**

1.1 Dimensions and tolerances:

Concrete masonry building units shall be made in sizes and shapes to fit different construction needs. They include stretcher, corner, double corner or pier, jamb, header, bull nose, and partition block, and concrete floor units. Concrete block-hollow (open or closed cavity) or solid shall be referred to by its nominal dimensions. The nominal dimensions of concrete block shall be, as follows:

Length	**:**	**400, 500 or 600 mm**
Height	**:**	**200 or 100 mm**
Width	**:**	**50, 75, 100, 150, 200, 250 or 300 mm.**

In addition, block shall be manufactured in half lengths of 200, 250 and 300 mm to correspond to the full lengths.

The maximum variation in the length of the units shall be not more than +/- 5 mm and maximum variation in height and width of unit, not more than +/- 3mm.

1.2 Classification:

1.2.1 Hollow (open and closed cavity) concrete blocks.

The hollow (open and closed cavity) concrete blocks shall conform to the following three grades:

a) Grade ‘A’ - These are used as load bearing units and shall have a minimum block-density of 1500 kg / m3. These shall be

manufactured for minimum average compressive strengths of 3.5, 4.5, 5.5 and 7.0 N/mm2 respectively at 28 days (See Table 5).

b) Grade 'B' - These are also used as load bearing units and shall have a block density less than 1500 kg / m3 but not less than 1000 kg / m3. These shall be manufactured for minimum average compressive strengths of 2.0, 3.0 and 5.0 N/mm2 respectively at 28 days. (See Table 5).

c) Grade 'C' – These are used as non-load bearing units and shall have a block density less than 1500 kg / m3 but not less than 1000 kg / m3. These shall be manufactured for minimum average compressive strength of 1.5 N/mm2 at 28 days (see Table 5).

d) Grade 'D' – The solid concrete blocks are used as load bearing units and shall have a block density not less than 1800 kg/m3. These shall be manufactured for minimum average compressive strengths of 4.0 and 5.0 N / mm2 respectively (see Table 5).

1.2.2 Physical requirements:

1.2.2.1 Compressive strength – The average crushing strength of eight blocks, when determined in accordance with IS: 2185 shall not less than as specified in Table 3:

Table 5 Physical requirements

Type	Grade	Density of block Kg/mm³	Minimum Average compressive strength of units	Minimum strength of individual units N/mm²
Hollow (open & closed cavity) load bearing unit	A (3.5)	Not less than 1500	3.5	2.8
	A(4.5)		4.5	3.6
	A(5.5)	Not less than	5.5	4.4

	A(7.0)	**1500 but not less than 1000**	**7.0**	**5.6**
	B(2.0)		**2.0**	**1.6**
	B(3.0)		**3.0**	**2.4**
	B(5.0)		**5.0**	**4.0**
Hollow (open and closed cavity) non-load bearing units	**C(1.5)**	**Less than 1500 but not less than 1000**	**1.5**	**1.2**
Solid load	**D(5.0)**	**Not less than 1800**	**5.0**	**4.0**
Bearing Units	**D(4.0)**		**4.0**	**3.2**

1.2.2.2 Drying shrinkage – The drying shrinkage of the blocks (average of three blocks), when unrestrained, shall be determined in accordance with IS: 2185 and shall not be exceed 0.1 per cent.

1.2.2.3 Moisture movement – The moisture movement (average of three blocks), when determined as described in IS: 2185 shall not exceed 0.09 percent.

1.2.2.4 Water absorption – The water absorption (average of three blocks), when determined in the manner described in IS: 2185 shall be not more than 10 per cent by mass.

Face shells and webs shall increase in thickness from the bottom to the top of the unit. Depending upon the core moulds used, the face shells and webs shall be flared and tapered or straight tapered, the former providing a wider surface for mortar. The thickness of the face shell and web shell is not less than the values given in Table 4.

Table 6 Minimum face shell and web thickness

Nominal block length and width	**Face shell thickness**	**Thickness of web**	**Total web thickness per course in any 200 mm of**

			walling
	Min.	**Min.**	**Min.**
100 or less	**25**	**25**	**25**
Over 100 to 150	**25**	**25**	**30**
Over 150 to 200	**30**	**25**	**30**
Over 200	**35**	**30**	**38**

Subject to the tolerance as specified in 5.4.2.2 and 5.4.4.7, the face of masonry units shall be flat and rectangular, opposite face shall be parallel, and all arises shall be square. The bedding surfaces shall be at right angles to the faces of the blocks.

Blocks with special faces shall be manufactured and supplied as directed by the engineer.

1.2.3. Curing and drying **- The blocks shall be cured in an immersion tank or in a curing yard and shall be kept continuously moist for at least 14 days. When the blocks are cured in an immersion tank, the water of tank shall be changed at least every four days.**

After curing, the blocks shall be dried in shade before being used on the work. They shall be stacked with voids horizontal to facilitate through passage of air. The blocks shall be allowed to complete their initial shrinkage before they are laid in wall.

1.2.4 Construction of masonry **- For single storeyed buildings, the hollows of blocks in foundation and basement masonry shall be filled up with sand and only the top foundation course shall be of solid blocks. But for two or more storeyed buildings, solid concrete blocks shall be used in foundation courses, plinth, and basement walls, unless otherwise indicated. If hollow blocks are used, their hollows shall be filled up with cement concrete 1:3:6 using 12.5 mm nominal size aggregates.**

1.2.5 Wetting of blocks **- Blocks need not be wetted before or during laying in the walls. In case the climate conditions so require, the top and the sides of the blocks may only be slightly moistened so as to**

prevent absorption of water from the mortar and ensure the development of the required bond with the mortar.

1.2.6. Laying **- Blocks shall be laid in mortar, as indicated and thoroughly bedded in mortar, spread over the entire top surface of the previous course of blocks to a uniform layer of not less than 10 mm and not more than 12 mm in thickness.**

All courses shall be laid truly horizontal and all vertical joints made truly vertical. Blocks shall break joints with those above and below for not less than quarter of their length. Precast half length closers (and not cut from full size blocks) shall be used. For battered faces, bedding shall be at right angles to the face unless otherwise directed. Care shall be taken during construction to see that edges of blocks are not damaged.

1.2.7 Provisions for door and window frames **- A course of solid concrete block masonry shall be provided under door and window openings (or a 10 cm thick precast concrete sill block under windows). The solid course shall extend for at least 20 cm beyond the opening on either side. For jambs of very large doors and windows either solid unit are used, or the hollows shall be filled in with concrete of mix 1:3:6 using 12.5 mm nominal size aggregates.**

1.2.8 Provisions for roof **- The course immediately below the roof slab shall be built with solid blocks. The top of the roof course shall be built with solid blocks. The top of the roof course shall be finished smooth with a layer of cement and coarse sand mortar 1:3, 10 mm thick and covered with a thick coat of white wash or crude oil, to ensure free movement of slab.**

1.2.9 Intersecting walls **- When two wall meet or intersect and the course are to be laid up at the same time, a true masonry bond between at least 50% of the units at the intersection is necessary. When such intersecting walls are laid up separately, pockets with 20 mm maximum vertical spacing shall be left in the first wall laid. The corresponding course of the second wall shall be built into these pockets.**

1.2.10. Piers **- The top course of block in the pier shall be built in solid blocks. Hollow concrete block shall not be used for isolated piers, unless their hollows are specified to be filled with cement concrete.**

1.2.11. Fixtures, fittings, etc. shall be built into the masonry in cement and coarse sand mortar 1:3 while laying the blocks where possible. Hold fasts shall be built into the joints of the masonry during laying. Holes, chases, sleeves, openings, etc. of the required size and shape shall be formed in the masonry with special blocks while laying, for fixing pipes, service lines, passage of water etc. After service lines, pipes etc. are fixed, voids left, if any, shall be filled up with cement concrete 1:3:6 (1 cement : 3 coarse sand: 6 stone aggregate 20 mm nominal size) and neatly finished.

1.2.12 Finishes - Rendering shall not be done to the walls when walls are wet. Joints for plastering or pointing as specified shall be raked to a depth of 12 mm. Joints on internal faces, unless otherwise indicated, shall be raked for plastering. If the internal faces of masonry are not be plastered the joints shall be finished flush as the work proceeds or pointed flush where so indicated.

Annexure 5-A.1

BLOCK WORK- CONSTRUCTION PRACTICE

1. General

1.1. Introduction

Blocks are either hollow or solid. Generally they are of light weight compared to bricks. Concrete blocks to IS: 2185 (Part 1)-1979 may be used for both load bearing and non-load bearing walls. The wall thickness will vary.

For high thermal insulation, cavity walls having inner leaf of light weight concrete blocks to IS: 2185 (Part 2)-1983 may be used. Each leaf of cavity shall not be less than 100 mm.

Autoclave cellular concrete blocks to IS: 2185 (Part 3)-1984 shall not be used for foundations and for masonry below damp-proof course.

2. Mortars

2.1. Hollow concrete blocks:

Hollow concrete blocks shall be embedded with a mortar which is relatively weaker than the mix used for making blocks in order to avoid formation of cracks. A rich or strong mortar tends to make a wall too rigid thus localizing the effects of movements due to temperature and moisture variations, resulting in cracking of blocks. The recommended proportion of mortar measured by volume is given in Table 1

Table 7 Mix Proportion of mortar for hollow concrete blocks

Sl No Masonry	Type of work	Normal masonry (Cement:Lime:Sand)	Reinforced (Cement: Sand)
1.	Normal work	1 : 1 : 9 to 10	1 : 7 to 8
2.	Exposed to severe conditions; high intensity of loads; plasters; heavily loaded lintels and beams.	1 : 1 : 6 to 7	1 : 4 to 5
3.	Partitions of 10 cm	1 : 1 : 7 to 8	1 : 5 to 6

Note: All mortars shall have a slump of 75 mm.

2.2. Light weight blocks - Light weight blocks shall be embedded with a mortar mix, the strength of which is lower than mix for making blocks, to avoid formation of cracks. A 1:2:9 cement, lime, sand mortar may generally be used; for high intensity of load it shall be 1:1:6. Autoclaved blocks shall be embedded in mortar as specified in Table 1

3. Concrete

3.1. Concrete used for filling hollow concrete block masonry when reinforced shall be 1 cement, 2 ½ sand and 3 coarse aggregate of

size ranging from 4.75 mm to 10 mm. The water cement ratio shall not exceed 0.6. When cells exceed, 100 mm on the narrower side, the proportion of mix shall be 1of cement, 2 ½ of sand and 3 ½ of coarse aggregate for reinforced concrete and 1:3:6 plain concrete.

4. Thickness

4.1. For load bearing masonry built with hollow concrete blocks, the thickness of walls shall not be less than the values as obtained from IS: 1905-1987.

4.2. Light weight block in load bearing masonry for external walls in framed construction shall not be less than 200 mm. However, if they are suitably braced by lateral or vertical supports, the thickness can be 100 mm. Non-load bearing hollow block walls shall be not less than 100 mm.

4.3. Autoclaved block walls in framed construction shall also be as per above; except that for load bearing work, the minimum thickness shall be 200 mm; however it can be reduced to 150 mm if properly braced.

5. Lateral supports

Walls made of blocks shall have vertical or horizontal lateral supports at right angles to the face of the wall. Cross walls, plasters or buttress walls shall provide the lateral support.

6. Avoidance of crack formation

6.1. General

The major cracks in the walls or partitions in a structure constructed with blocks, whether they are of hollow of cellular types can be prevented. The preventive measures to be undertaken are covered.

6.1.1. Structural movements

Cracks may arise from alterations in length, the curvature or orientation due to load settlement, thermal expansion or changes in moisture content.

In the case of framed structures, erection of partitions and panel walls shall be delayed wherever possible until the frame has taken up, as much as possible, any deformation occurring due to structural movements.

a) **Floor deformation and movement – The floor upon which a partition is built may deflect under load brought on it after the partition is built. Such deflections tend to create a non-continuous bearing for the block leading to cracks in the partition. This can be avoided by embedding wires of 3 mm diameter of mild steel or galvanized steel or welded wire mesh strip in bed joints in cement mortar 1:2 after every 900 mm to 1200 mm height.**

b) **Ceiling deflection and movement – A ceiling above a partition will may deflect under loads applied after its erection or through thermal or other movements. To avoid cracking as a result of such deflection, the partition wall shall be separated from the ceiling by a gap or by a layer of resilient material or lean mortar. When this cannot be done as in the case of plastered finishes, the risk of cracking may be reduced by forming a cut between the ceiling plaster and the wall plaster.**

c) **Deflection or movement of structural abutments – The walls, columns or other structural elements against which the wall or partition abut, may deflect or move because of load, settlement, shrinkage or thermal effects. In order to avoid cracking of walls or partitions as a result of such movements, a slip joint shall be provided where possible, preferably packed with a resilient mortar or lean mortar.**

d) **Cracks in partition walls may occur at corners of door and window frames at lintel level or sill level. It may therefore be desirable to provide a nominal reinforced concrete band beam (see Fig. 1) at sill level and vertical reinforced concrete stud at either side of vertical members of frames which may in addition provide sufficient anchorage for hold fast.**

6.1.2. Control of wall movements accompanying temperature and moisture changes Cracking in concrete masonry walls is often due to tensile stresses which develop when wall movements accompanying

temperature and moisture change are restrained by other elements of the building or when concrete masonry places restraint on the movement of adjoining elements.

There are three methods of controlling cracking in concrete masonry structures :

(1). Specifying a limit on the moisture content of masonry units at the time of delivery and construction;

(2) Incorporating steel reinforcement either in the form of nominal bond beams or horizontal joint reinforcement and,

(3) Providing control joints to accommodate the movement of masonry. In all concrete masonry construction, it is essential to employ only moisture controlled units. Their use, combined with the provision of control joints is generally adequate to prevent cracking in concrete masonry walls. However, bond beams or joint reinforcement, or both in different locations as considered suitable may also be used in addition to the above.

6.1.3. Nominal bond beams - Bond beams, the use of which as structural members have been referred shall also serve as a means to crack control. Normal bond beams shall be built in the same manner as the structural bond beams with a minimum reinforcement of two 8 mm mild steel bars or two 6 mm dia high strength deformed bars. Their value for this purpose is due to increased strength and stiffness they provide to a masonry wall. As a means of crack control, the area of influence of bond beam shall generally be assumed to be extending 600 mm above and below its location in the wall. In walls without openings, they shall be placed at 1200 mm apart and may be of any length up to a maximum of 18 m (see Table 2).See Fig. 1.

Nominal bond beams shall be discontinuous at control joints, but practice here varies depending on the structural requirements.

Dummy joints shall be formed when a bond beam is continuous at a control joint.

6.1.4. Joint reinforcement - Horizontal joint reinforcement serves much the same purpose as bond beams in crack control. It increases stresses to cracking. Due to closer spacing adopted, joint reinforcement may be more effective in crack control than bond beams.

a) Joint reinforcement shall be preferably be fabricated from galvanized steel to IS 280:1978 and shall consist of two or more smooth or deformed longitudinal wires 3 mm dia or larger weld connected with 2.8 mm dia or larger cross wires. The out-to-out spacing of longitudinal wires shall be 30 mm less than the width of masonry skills. Cross wires shall be welded at a pacing of 150 mm for smooth wires and 400 mm for deformed wires. Where splice in wires is necessary, it shall be lapped to a length of at least 300 mm.

b) The reinforcement shall be embedded in horizontal joints at intervals of 900 mm to 1200 mm depending on panel length, height and the number and type of wall openings. (See Table -2)

c) Joint reinforcement shall be used in conjunction with cement mortar not weaker than 1:2 mixes. In walls exposed to action of weather, the reinforcement shall have a mortar cover of not less than 15 mm.

d) Notwithstanding the above, location of joint reinforcement shall be as follows :

1) Place the joint reinforcement in the first and second bed joints immediately above and below wall openings ;

2) It shall not extend less than 600 mm beyond the openings to end of the panel whichever is smaller ;

3) Place joint reinforcement within two or three courses immediately below the top of the wall ;

4) Joint reinforcement shall not be located closer to a bond beam than 600 mm ; and

5) Joint reinforcement shall be interrupted at control joints.

Notes: (1) When bond beams spaced at 1200 mm are used in place of joint reinforcement, control joints shall be spaced at 18 m. (2) Where reinforcement has not been provided, the ratio L / H of wall panel shall conform to IS: 1905-(1987)



$H \nless 80$ mm
$W \times H \nless 1\,200$ mm^2

Fig. 1 Nominal reinforced concrete bond beam at sill level

Table 2: Recommended length top height ratios for concrete block masonry

Sl	Wall panel	Vertical spacing of joint

No		reinforcement		
		900 mm	1000 mm	1200 mm
1	Length of panel (L) Irrespective of height (H) Max.	18 m	15 m	12 m
2	Ratio L/H, Max			
a)	200 mm thick wall	3.0	2.75	2.50
b)	300 mm thick wall	2.25	2.00	1.75

6.1.5. Control joints - Control joints are employed to reduce restraint by accommodating movement of masonry wall or movement of structural elements adjacent to the wall, and thus to control cracking. They are in fact vertical separations built into the wall at locations where cracking is likely due to excessive horizontal stresses. The spacing along the wall length depends upon:

(a) Expected movements of the wall and other elements

(b). Resistance of the wall to horizontal stresses

(c) The extent and location in the wall of doors, windows, recesses, chases and other causes of stress concentration. Some typical methods of control joints are shown in Fig 2 and Fig. 3.

6.2. Bonded beams and studs used on structural members

6.2.1. Reinforced concrete structural bond beams may be used in concrete block masonry to meet the requirements of unusual stress conditions. Examples are as below:

a) In buildings in earth-quake regions ;
b) In buildings in areas where severe wind storms occur ;
c) In buildings in areas where unfavorable soil movements and soil subsidence occur ; and
d) In buildings where walls are subjected to excessive vibration or to heavy loads.

In all such cases, it is necessary to provide more than nominal stability for all types of masonry walls.

6.2.2. Bond beams shall be built integrally with block masonry or with special U-shaped lintel blocks slung together with reinforcing steel placed in the core of hollow of blocks filled with M15 concrete. The reinforcement shall conform to IS: 456-2000; but in no case shall be less than two

12 mm dia mild steel bars. The beams are discontinuous at control joints; but the joints should be designed to transfer forces along the wall.

6.2.3. Bond beams may be provided at any of the following locations depending on the conditions as described in 6.2.1

(a) At floor level; (b) At top of all door and window openings (in which case they serve as lintels over them); (c) Below the sill in all window openings and (d) At plinth level.

6.2.4. Apart from the horizontal bond beams, vertical reinforced concrete studs may also be provided at corners, at wall openings and at regular intervals between wall openings. The studs shall be tied in with bond beams.

Non-structural use of bond beams is already covered 6.1.3

7. Preparatory works

Wetting of blocks

7.1. The blocks need not be wetted before or during the laying of the blocks. In case the climatic conditions so require, the top and sides of the blocks may be slightly moisture so as to prevent absorption of water from the mortar and ensure development of the required bond with the mortar.

7.2. Scaffolding - Scaffolding shall be on the same lines as brickwork, suitably modified where necessary.

8. Laying of Concrete Blocks

8.1. First Course - The first course of concrete block shall be laid with great care, making sure that it is properly leveled, aligned and plumbed, to assist in obtaining a straight and truly vertical wall. Before laying the first course, the alignment of the wall shall be marked on the d. p.c. The blocks for this course shall be laid dry, that is, without mortar along a string stretched between properly located corners of the wall in order to determine the correct position of blocks including those of the cross walls jointing it and also adjust their spacing. When the blocks are in proper position, the two corner blocks shall be removed, a mortar bed spread and these blocks re-laid back in place truly level and plumb. The string shall then be stretched tightly along the faces of two corner blocks and the faces of the intermediate blocks adjusted to coincide with the line. Thereafter each block shall be removed and re-laid over a bed of mortar. After every three or four blocks are laid the correct alignment and vertically be checked.

8.2. Construction - The construction of walls may be started either at the corners first or started from one end proceeding to the other end.

If the corners are built first, they shall be built four or five courses higher than the centre of the wall. As each course is laid at the centre, it shall be checked for alignment and level and for being plumb. Each block shall be carefully checked for alignment with a straight –edge to make sure that the faces of the blocks are in the same plane.

Fig. 2 – Control joints in concrete block masonry construction


ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
ALTERNATE COURSES
CONTROL JOINT
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL
METHOD A
ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
ALTERNATE COURSES
5 mm WIRES GREASED AND LAID IN EVERY OTHER COURSE
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL
METHOD B
ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
ALTERNATE COURSES
JAMB BLOCK
5 mm WIRES GREASED AND LAID IN EVERY OTHER COURSE
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL
METHOD C

8.2.1. Each course, in building the corners, shall be stepped back by a half-trick and the horizontal spacing of block shall be checked by placing a mason's level diagonally across the corners of the blocks. A storey rod or course pole, suitably marked provides an accurate method of finding the top of the masonry for each course.

8.2.2. When filling in the wall between corners, a mason's line shall be stretched from corner to corner for each course and the top outside edge shall be laid true to this line. The manner of handling

or gripping the block shall be such as to position the block properly with minimum adjustment.

8.2.3. To ensure satisfactory bond, mortal shall not be spread too far ahead of actual laying of the block as it will stiffen and lose its plasticity. As each block is laid, excess mortar extruding from the

Joints shall be cut off with a trowel and thrown back on the mortar board to be reworked into fresh mortar. If the work is proceeding rapidly, the extruded mortar cut from the joints may be applied to vertical face shells of the blocks just laid. If there be any delay long enough for the mortar to stiffen on the block, the mortar shall be removed to the mortar board and reworked. Dead mortar that has been picked up from the scaffold or from the floor shall not be used.


ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
5 mm WIRES BENT IN FORM OF U, GREASED AND LAID IN EVERY OTHER COURSE
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL
ALTERNATE COURSES

METHOD A

Fig. 3

8.3. Closure block - When installing a closure block, all edges of the openings and all four edges of the closure block shall be buttered with mortar.

The closure block shall be carefully lowered into place. If any mortar falls leaving an open joint, the closure block shall be removed, fresh mortar applied and the operation repeated.

9.1. Door and window frames shall be attached to the surrounding masonry either by conventional method or by 200 mm flooring nails with screwed ends fixed directly into the block, after the frame has been edged into the opening at every nailing position. The number of nails depends on the dimensions of the frames. The nails shall be spaced at a maximum of 400 mm apart and the first nail shall not be farther than 200 mm from the corner.

Frames may be attached to the masonry by holdfasts anchored in the vertical reinforced concrete studs provided to the frames.

9. Provision for door and window frames

10. Provision for roof

10.1. The top of the roof course shall be finished smooth with a thin layer of 1:3 cement mortars and covered with a coat of crude oil or craft paper or oil paper to ensure free movement of the roof.

11. Intersecting wall

11.1. Load bearing walls - When two load bearing walls intersect and courses are to be laid up at the same time, a true masonry bond between 50 per cent of the units at the intersection is necessary. When such walls are laid up separately, pockets with maximum 200 mm vertical spacing shall be left in the first wall laid. The corresponding course of the second wall shall be built in to these pockets.

11.2. For non-load bearing walls same bonding methods as for load bearing walls may be used.

12. Renderings and other finishes - All finishes shall be as specified in Section 12 Finishing Work, as the case may be.


ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
ALTERNATE COURSES
5 mm WIRES BENT IN FORM OF U, GREASED AND LAID IN EVERY OTHER COURSE
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL

METHOD B


ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
ALTERNATE COURSES
5 mm WIRES GREASED AND LAID IN EVERY OTHER COURSE
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL

METHOD C


ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
ALTERNATE COURSES
5 mm WIRES GREASED AND LAID IN EVERY OTHER COURSE
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL

METHOD D

Fig. 3


ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
ALTERNATE COURSES
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL
METHOD E
ON EXPOSED FACE OF WALL, RAKE OUT MORTAR TO 20 mm AND FILL WITH CAULKING COMPOUND
ALTERNATE COURSES
CAULKING COMPOUND OR MORTAR ON UNEXPOSED WALL
METHOD F

Fig. 3 – Plasters with control joints in concrete block masonry construction

Annexure 5-A.2

CONSTRUCTION PRACTICES OF IN-SITU WALLS WITH SOIL CEMENT

1. General

Contractor
Employer

1.1. This type of in-situ construction with soil cement shall be limited to single storey construction with a wall height not exceeding 3.2 mm and a minimum wall thickness of 300 mm for load bearing and 200 mm for non-load bearing walls.

1.2. The procedure described herein may also be followed for rammed in-situ wall construction with unstabilized soil, provided the surfaces of the wall are protected by a waterproof mud plaster.

2. Soil

2.1. Raw soil used for soil cement shall be free from deleterious contents, such as organic matter of vegetable origin, mica, etc. Black cotton soil may not be used from economy considerations.

Soil shall conform to the following requirements:

Sand content, percent by mass	**35, min**
Plasticity index, percent	**8.5 to 10.5**
Total soluble salts, percent by mass	**1, max**
Sodium salts, percent by mass	**0.1, max**
Liquid limit, percent	**27, max**

Note: Sand content is the fraction of sand of the soil that passes 425 micron is retained on 75 microns IS sieve. More than half the material is smaller than 75 micron by mass.

2.2. Soil shall be prepared as per IS 2110: 1980. Cement shall be mixed in proportions as given below:-

(a)For construction of walls 2.5 to 3.5 per cent by mass of dry soil depending on the density to be obtained. For construction of walls below plinth level and for copings. 5 to 7.5 per cent by mass of dry soil, so that the crushing strength of blocks mate shall not be less than 1.4 N/mm2 (14 kg/cm2) for dry condition.

For calculation purposes the unit weight of dry soil shall be taken as 1 300 kg/m3. Properties of soil cement shall be as in IS 2110: 1980.

2.3. Preparatory work:

2.3.1. Shuttering - Any timber planks suitable in local practice may be used for shuttering. The planks shall not be less than 200 mm in



width and 50 mm in thickness. A typical arrangement is shown in Fig. 4

Fig. 4 – Typical details of shuttering for 300 mm thick wall

Note: If the thickness of the wall is greater than 300 mm, shuttering details will have to be suitably modified. The shuttering shall generally be in lengths ranging from 1.8 m to 3.3 m. The height of the shuttering for one lift shall be about 600 mm clear for casting the wall plus 200 mm for holding on to the portion of the compacted wall below in the previous lift. The shuttering may be lifted immediately after first lift is well compacted and the shuttering for next lift arranged.

3. Wall constructions

3.1. Preparation of soil - After the shuttering is erected, the moist stabilized soil shall be poured into the shuttering in layers of 75 mm

at a time. The layer shall be uniform in depth. To control his depth, templates may be used.

3.2. Compaction - Compaction shall be done by iron rammers. Compaction shall be started at the side and worked inwards. Ramming of the sides shall be evenly distributed to avoid tilting of the shuttering. Verticality of the shuttering shall be checked as compaction proceeds.

3.3. Curing - The walls shall be cured for 15 days after removal of shuttering. Curing shall be done by slight sprinkling of water at regular intervals.

3.4. Joints - Vertical joints shall be provided at a spacing of not more than 2 m apart. Vertical joint shall be staggered. Fig. 5 gives details of joint.



A Section of Plank Used for Making Vertical Joint

B Plan of Vertical Tongue and Groove Joint

All dimensions in millimetres.

Fig. 5 – Typical details of construction joints in in-situ of the soil, cement walls of 300 mm thickness

Horizontal joints shall be formed by finishing smooth the rammed surface at the end of each lift.

3.5. Fixing frames - Frames for door and windows shall be fixed by iron hold fasts inserted in the wall before-hand.

3.6. Bearing of roof - Where light roof frame work is to rest on the wall, the portion of the wall directly below it shall be built with

bricks laid in cement mortar 1:6 for a depth of 150 mm; or bricks made out of 7.5 per cent soil cement. Beams shall rest on cement concrete bed plates. Trusses or flat roofs shall rest on brick bearing course to a depth of 150 mm laid in cement mortar 1:6.

3.7. Lintels - Reinforced brick or cement concrete lintels may be used. The space above the lintels shall be filled either with soil cement rammed in-situ, or precast soil cement blocks laid in cement in mortar mix 1:6.

3.8. Parapet - The parapet shall be of brick work. A drip course shall be provided to drain rain water from parapet and away from the lower portions of the walls on to the roof surface. The plaster finish of the roof shall be continued from the roof surface right up to the drip course in the parapet.

3.9. Plastering - Cement plaster of mix hot leaner than 1:5 shall be used. It shall be applied after drying the wall for four weeks at least. The wall surface shall be given a neat cement wash before applying plaster.

4. Preparation of mud plaster:-

4.1. Add cutback bitumen to IS 217: 1988, grade 80/100 to mud with BHUSA which is allowed to rot for a week. About 60 kg of 'Bhusa' should be added to a cubic meter of mud. Bitumen should be around 40 kg/m3 of soil used.

4.2. Surfaces to be plastered shall be moistened before application of mud plaster.

PLASTERING WORK

1.0 INDIAN STANDARDS

Work shall be carried out as per the latest issue of Indian Standards and Code of Practices. List given hereunder is not to be considered as conclusive and is for reference and guidance only. Any discrepancies/ conflict noticed shall be directed to the In-charge /Employer for direction/approval. However as a general rule more stringent specification shall take precedence.

1. IS 383 Specification for coarse and fine aggregates for natural sources for concrete.
2. IS 412 Specifications for expanded metal steel sheets for general purposes.
3. IS 1542 Specifications for sand for plaster
4. IS 1661 Code of practice for application of cement and cement lime plaster finishes.
5. IS 2402 Code of practice for external rendered finishes
6. IS 2645 Specifications for integral cement water proofing compound
7. IS 8112 Specification for 43 grade OPC.
8. SP 27 Handbook of method of measurement of building works.

2.0 MATERIALS

2.1 Cement

2.1.1 Cement shall be ordinary Cement conforming to IS and of grade 43.

2.2 Water

2.2.1 Water used for mixing and curing shall be clean, reasonably clear and free from objectionable quantities of silt, oils, alkalis, acids, salts so as not to weaken mortar.

2.2.2 Water tested shall be in accordance with IS 3025. Maximum permissible limits of deleterious materials in water as given in IS 456 are reproduced for ready reference in table 1 of IS 456.

2.3 Sand (coarse sand FM above 2.25 & Fine sand F M more than 1.25) shall conform to IS 1542 specification for sand for plaster. For white or coloured renderings, only quartz or silica sand shall e used. For textured finishes produced by treatment of freshly applied final or finishing coat with a tool coarser, particles used shall be screened through 3.35 mm IS sieve or 2.36 mm IS sieve. For torn texture a slightly larger portion of material coarser than 4.75 mm IS sieve shall be used.

2.4 Aggregate shall conform to IS 383.

2.5.1 Integral water proofing compound shall conform to IS 2645 (specification for integral water proofing compound).

2.6GI Chicken Mesh

GI Chicken mesh of 20 gauge as approved shall be used over junctions of concrete and masonry or two dissimilar materials about 150mm wide fixed with GI wire nails etc. as directed by the Incharge.

Precaution - Any cracks which appear in the surface and all portions which sound hollow when lapped, or are found to be soft or otherwise defective, shall be cut out in rectangular shape and redone as directed by the engineer.

i) When ceiling plaster is done, it shall be finished to chamfered edge at an angle at its junction with a suitably tool when plaster is being done. Similarly when the wall plaster is being done, it shall be kept separate from the ceiling plaster by a thin straight groove not deeper than 6 mm drawn with any suitable method with the wall while the plaster is green.

ii) To prevent surface cracks appearing between junctions of column/ beam and walls, 150 mm wide chicken wire mesh should be fixed with U nails 150 mm centre to centre before plastering the junction. The plastering of walls and beam/column in one vertical plane should be carried out in one go. For providing and fixing chicken wire mesh with U nails payment shall be made separately.

3. MORTARS

3.0.1 Mortars shall be prepared by mixing fine graded aggregate with cement, the lime or a combination of these in the proportion specified for respective items of work as detailed in the BOQ. Mixing or mortars shall be done by mechanical mixers only. Hand mixing may be permitted in specified cases on the written permission of the Incharge

3.0.2 Mortars shall be specified by proportion only and not by strength. Volumetric mixing shall be based on dry volumes of each ingredient. For convenience, measurement shall correspond to volume of one cement bag i.e. 0.035 cu m. Boxes shall be of size 40 x 35 x 25 cm. These shall be marked as mortar mixing boxes by red paint and shall be used throughout the contract. Hand mixing or mechanical mixing proportions shall be done with the use of these boxes.

3.1 Cement mortar

3.1.1 Cement mortar shall be prepared by mixing cement and sand in specified proportions. Proportioning shall be carried out as detailed above and shall be added suitably to allow for bulkage if required. Bulkage shall be determined as specified in IS 2386 Part III. Cement and sand added to mixer shall be thoroughly mixed and water shall be added to it gradually. After addition of water the mixer shall run for a minimum of 3 minutes. The mortar mixed shall be consumed within 30 minutes of its mixing.

4.0 WORKMANSHIP

Work shall be carried out as per recommendations of code of practices IS 1661 and IS 2402.

4.1 Preparation of mortar mix

4.1.1 The material used in preparation of plastering mixes shall be measured by volume using gauge – boxes or by weight.

4.1.2 When cement is measured by weight, 1440 kg of material shall be taken equivalent to one cubic meter. p

4.2 Mixing

4.2.1 Mixing shall be done mechanically. Each mortar batch shall be used within half an hour. Hand mixing if permitted as special case shall be carried out on a clean, watertight platform. The mixing operation shall be continued with addition of necessary quantity of water until a uniform appearance and consistency of mortar is obtained.

4.2.2 Cement and sand shall be mixed dry in required proportion to obtain a uniform colour and water shall then be added to get the required consistency for the plaster.

4.3 Method of plastering:

4.3.1 Surface to be plastered must be clean and free from dust, loose material, oil, grease, mortar droppings, sticking of foreign matter, traces of algae, etc. It is very important to ensure that there should not be any chance of the plaster getting debonded due to presence of materials harmful for bonding.

4.3.2 Raking out of joints is expected to be carried out along with masonry but it should be checked thoroughly so as to receive good key.

4.3.3 Walls should be sufficiently damp prior to plastering. Water from plastering mortar must not be absorbed by masonry under any condition.

4.3.4 Any unavoidable projections in masonry and concrete surfaces shall be chiseled back. Care shall be taken that surrounding surfaces are not damaged and reinforcement is not exposed.

4.3.5 Thickness of one coat should not be more than 15 mm and less than 8 mm for single coat finished plaster.

4.3.6 In case of multi coat plaster, sufficient time shall be allowed for the undercoat to harden (cured, dried and shrunk properly) before subsequent coats are applied.

4.3.7 Undercoats shall be scratched or roughened before they are fully hardened to form a mechanical key.

4.3.8 The method of application is also important and hence it is recommended that the mix be thrown on the surface rather than stuck with trowel. This increases the adhesion.

4.3.9 Independent double legged scaffolding free of masonry shall be provided. Scaffolding should be rigid, allowing free and safe movement on the platform and it should be at sufficient distance or height from the working areas. Scaffolding with railing gives more confidence to workers and improves the quality of work.

4.3.10 Actual plastering shall be undertaken only on the approval of the Incharge. Plaster work should only follow the steps mentioned below:

a. Surface must be thoroughly cleaned.

b. Plaster area must be provided with level dabs or sports allowing working and checking with 2-3 m straight edge. Depth of plaster must not be less than 8 mm at any point.

c. Required concealing services must be completed and tested.

d. No further cutting of masonry must be required.

e. Repairs carried out to masonry or concealing work must be cured and dry.

f. Surface must be sufficiently damp.

g. Plaster dabs are checked for plumb and level by the Incharge or his representative.

h. Joints, concealing and repairing areas must be covered with 20 gauge GI chicken mesh as per the Incharge's instruction.

4.3.11 Corners, external or internal, shall be finished along with final coat. It is advisable to have rounded corners.

4.3.12 Plaster shall be cured for 14 days by wet curing except in neeru finish plaster. During this period plaster shall be protected from exposure to extremes of temperature and weather.

4.3.13 Plaster shall be leveled and lined by aluminium hollow section, 2-3 m long. (This will give even and leveled surface). There shall not be more than 2 mm difference in level when checked with 3 m straight edge. It is important that enough pressing and beating is done to achieve compact filling of joints and that the area is fully compacted.

4.3.14 Finishing of plaster may be carried out with wooden float (rand has) or trowel led smooth with sheet metal trowels as specified. Care shall be taken to avoid excessive trowelling and overworking of the wooden float.

4.3.15 All corners, internal or external, shall be truly vertical or horizontal. These shall be finished with a proper template to achieve best workmanship for rounding and chamfering as specified or directed.

4.3.16 Plaster shall be cut to correct horizontal or vertical line at the end of the day or if work requires to be suspended for any reason.

4.3.17 It is advisable to limit the area of plaster to 15 sq. m. to avoid cracks due to thermal movements of dissimilar material in contact, it is advisable to provide joints treated with groove or any other detail as suggested. These joints, if not, specified shall be treated with 150 mm wide reinforcing chicken mesh (approved by the Incharge) fixed over joints by GI nails and the area plastered.

5.0 TYPE OF PLASTER

5.1 12 mm thick ordinary cement sand plaster

Single coat cement-sand plaster with cement-sand mix in proportion of 1:4 shall be carried out over the entire area as detailed above. This shall be finished just with wooden float to give the best smooth surface possible. This may be for internal or external areas. Thickness may be from 10 to 15 mm maximum or as specified in the item or drawing.

5.2 18 to 25 mm ordinary cement sand plaster

This is the same as for the 12 mm thick single coat plaster except that this shall be carried out in two coats. Maximum thickness of the undercoat shall be 12 mm and balance in the second finishing coat. All operations remain the same and are as detailed in Clause 3.0 of this section.

5.3 Cement finished plaster

This shall be carried out in the same manner as in Clause 5.1 and 5.2 of this section for specified thickness in single or double coat. Then it shall be finished uniformly over the entire area with a paste of neat cement when the plaster has just hardened and finished smooth with a steel trowel. It shall be worked over again to achieve a smooth leveled surface. Quantity of cement applied shall be about 1 kg/sqm.

5.4 Sand face plaster

5.4.1 This shall generally be carried out on the outside face and exposed area of masonry work and concrete work. It shall be of minimum 22 mm thickness and shall be in two coats (1st coat 16 mm and 2nd coat 6 mm). The coat shall be CM 1:4 (1 cement: 4 sand) mixed with water-proofing compound in proportion specified by the manufacturer by weight of cement and applied as usual and surface shall be keyed.

5.4.2 The second coat shall be applied after 7 to 10 days and shall be of CM 1:4 (1 cement : 4 sand). Mortar shall be mixed with slightly coarse sand. Mix shall be worked over with 3 m gauge or wooden float to achieve an uniform surface.

5.4.3 The surface shall be allowed to harden sufficiently for sponging operation. Sponging shall be done by dipping sponge in cement water and removing fine particles and exposing large sand particles. The movement of sponge shall be such that no parches develop nor excessive material is removed from the surface. There shall not be a difference of more than 7 mm when checked with a 2 m long straight edge.

5.5 Water proof plaster

The water proofing compound shall be mixed with dry cement in the proportion by weight as specified or recommended by the approved manufacturer of water proofing compound. Mixing should be thoroughly well integrated with cement. Addition of water must not allow any slips of mixed cement.

The mix used, in general, shall be CM 1:4 (1 cement : 4 sand) and the balance application, curing, etc. remains the same as detailed above.

6.0 MEASUREMENT

6.1 Plaster work shall be measured in square meter to the second decimal place.

6.2 Thickness of plaster shall be the average depth of plaster as specified. But if extra thickness occurs due to bad quality of bricks, stones or blocks or due to bad workmanship, the repairs or extra thickness required to be carried out shall be at the cost of contractor.

6.3 a) Grooves, pattas in continuation of large areas or plaster areas shall be considered as part of the plaster and not measured separately.

b) Ceiling plaster, including ribbed beam slab shall be measured in square meters.

c) Beams and columns in continuation of masonry shall be measured in square meter.

6.4 Jambs, sills, coves, cornices, etc. shall be a part of plaster and no separate payment shall be made towards these items.

6.5 Deduction

a) Deduction for an opening in plaster shall not be for area less than 0.5 sq. m.

b) In case the opening area is 0.5 sq m. only 50% area shall be deducted from each face.

c) In case the width of door or window frames are equal to masonry, full area of opening shall be deducted.

d) In case of openings of area above 3 sqm each deduction shall be made for opening on each face and jambs, sifts, sills shall be measured.

6.6 Plaster to ceiling and walls shall be measured separately if specified in the BOQ.

7.0 RATE

7.1 Description of item in the BOQ. unless otherwise stated, includes, wherever necessary, conveyance and delivery handling, unloading, storing, fabrication, hoisting, all labour for finishing to required shape and size, setting, fitting and fixing in position, straight cutting and waste, return of packings and other incidental charges.

7.2 Preparation of surface shall be as approved by the Incharge.

7.3 Trimming off the projections on masonry shall be included in the price.

7.4 Scaffolding and working platform shall be included in the price.

7.5 Materials as detailed and as required to complete item as specified shall be included in the price.

7.6 Curing of plaster shall be included in the price.

7.7 Cleaning of adjacent areas, windows, door frames, etc. including masonry surface in exposed masonry work, shall be included in the price.

7.8 Forming grooves for joints between beams/columns and masonry etc. shall be included in the price. Any special treatment if detailed shall be measured separately as billed in BOQ.

7.9 Providing and fixing chicken mesh at junction of R.C.C., brick work, edges, corners, chiseled and repaired brick work prior to plaster over concealed conduit, etc. shall be as directed by the Incharge. It shall be considered as part of item and no separate charge will be payable.

DOORS - WINDOWS AND HANDRAILS TIMBER SUB FRAMES

1.0 INDIAN STANDARDS

1.1 Standard

Work shall be carried out to Indian Standards and Code of Practices. In absence International Standards shall be followed. These shall be latest issue. List given hereunder is not to be considered as conclusive and is for reference and guidance only. Any discrepancies / confect noticed shall be directed to the Incharge for his direction/approval. However as a general rule more stringent specification shall take precedence.

(1) IS 287 Recommendation for maximum permissible moisture content for timber used for different purposes in different zones.

(2) IS 401 Code of practice for preservation of timber.

(3) IS 733 Specification for wrought aluminium, aluminium alloys, bars,

rods, sections (for general engineering purpose)

(4) IS 851 Specification for synthetic resin adhesive for construction (non-structural) in wood.

(5) IS 852 Specification for animal glue for general wood working purposes.

(6) IS 1141 Code of practice for seasoning of timber

2.0 MATERIAL

2.1 Timber

2.1.1 Timber shall be of quality as specified in BOQ and well seasoned. It shall have uniform colour, be free from defects such as cracks, dead knots, soft spongy spots and waves of injurious open shakes. Grains shall be reasonably straight. The individual hard and sound knot shall not be larger than 6 sq. cm. The aggregate area of all knots shall not exceed 0.5% area of a piece.

2.1.2 All timber shall be treated with chemical wood preservatives and be kiln seasoned to IS 1141 and conform to IS 287 for moisture content. Maximum permissible limit shall be +3% for average moisture content of all samples from a given lot and +5% for individual sample of the given lot. This is applicable when thickness of timber is more than 50 mm. Small size tolerance shall be + 2% and +3% respectively.

2.1.3 Timber used shall be treated with a 10 years guaranteed and approved anti-termite treatment. Wood work in contact with masonry of concrete shall be painted with hot bitumen coaltar before being placed in position.

2.1.4 Timber received at site shall be marked and stamped for approval prior to being used at site.

2.1.5 Sizes specified are not indicative and shall be correct finished sizes within allowable tolerances.

2.1.6 All timber shall be finished to required dimension and texture prior to being treated for chemical preservation.

2.2 All nails, screws etc. Shall be hot dip galvanized or of brass or non ferrous material.

2.3 Adhesives and glue shall be as per IS for exterior quality and water repellent.

3.0 WORKMANSHIP

3.1 Timber door windows & hand rail sub frames etc.

3.1.1 Timber brought at site shall be as approved by the Incharge.

3.1.2 No timber shall be painted, tarred, oiled etc. before its inspection by the Incharge. Any effort to hide the defects by plugging, painting, etc. shall render the piece to be rejected by the Incharge.

3.1.3 All rejected timber shall be removed at once from the site of work.

3.1.4 All sawing of timber shall be done in straight lines and planes of uniform thickness.

3.1.5 All joints shall be tongued and grooved or of the type shown in the drawings specified in the item or as directed by the Incharge. All joints shall be glued with approved adhesive.

Joints shall be strong, neat and shall fit without wedging or filling. They shall be pinned with hard wood or bamboo pins of 10-15 mm dia after the members of the frame are glued and pressed together in a suitable vice-mechanism.

3.1.6 Prior to joining, wood members of frame shall be planed smooth and accurate to the full depth. Rebates, roundings, mouldings, etc. as shown in the drawing shall be done before the members are joined.

3.1.7 All timber items shall be subjected to inspection by the Incharge prior to any treatment to be carried out. No. item shall be installed unless it is approved by the Incharge.

4.0 MEASUREMENTS / RATE

4.1 Door sub frames shall be measured in running metres as detailed in the BOQ.

4.2 The price for an item shall include supply of specified quantity and type of timber, sawn, cut, joined, framed and fixed in positron including supply and fixing of approved anti-corrosive treated fixtures, straps, bolts, hold-fasts, spikes, nails, screws, etc. supplying glue, coaltar, paint and anti termite treatment. The items shall also include all materials, labour, scaffolding, use of equipment, etc.

WATER PROOFING WORK

1.0 GENERAL

Work shall be carried out to Indian Standards and Code of Practices. In absence International Standards shall be followed. These shall be latest issue. List given hereunder is not to be considered as conclusive and is for reference and guidance only. Any discrepancies/conflict noticed shall be directed to the Incharge for his direction/approval. However as a general rule more stringent specification shall take precedence.

1. IS 269 Specification for 33 grade ordinary and low heat Portland cement.

2. IS 383 Specification for coarse and fine aggregates from natural sources.

3. IS 2645 Specification for integral cement water proofing compound.

4. IS 6494 Code of practice for water proofing of underground reservoirs and swimming pool.

5. IS 8112 Specification for 43 grade ordinary Portland cement.

6. IS 12118 Specification for two part polysulphide based cement:

Part – I general requirements.

7. IS 13826 Method of Test.

8. IS 3495 Method of Test for Burnt clay building bricks.

1.2 Quality Assurance

1.2.1 Manufacturer's Qualification

a) Not less than five years experience in manufacturing of membrane roofing.

1. Obtain primary materials from single manufacturer. Manufacturer's name shall appear on containers and accessories.

2. Provide secondary materials as required by manufacturer of primary materials.

1.2.2 Applicators Qualification

a) Approved by manufacturer prior to execution of this Contract, with experience on at least five projects.

b) Foreman of Field Crew: Minimum five years experience with system of waterproofing being installed.

1.2.3 Certifications

Manufacturer's certification on manufacturer's letterhead:

1. Certify system design; penetration, transition; and perimeter details; and system specification are appropriate and satisfactory for this particular project.

2. Certify products proposed for use comply with standards.

3. Certify materials ordered and supplied are compatible with each other, suited for local and purpose intended and shipped in sufficient quantity to ensure proper timely installation.

4. Certify materials have express warranty of merchantability and fitness for particular purposes of this Project.

5. Certify manufacturer has reviewed Project and will issue warranty upon successful completion of installation.

6. Certify materials shopped to site meet membrane manufacturer's published performance standards and requirements of this Specification.

7. Membrane manufacturer's approval of insulation type and method of installation.

8. Manufacturer' s approval of installer.

1.3 Submittals

1.3.1 Product Data

Contractor to submit along with his proposal product data for material he proposes to use.

1.3.2 Informational Submittals

a) Certifications specified in quality assurances

b) Manufacturer's instructions

1.4 Waterproofing compounds

1.4.1 Waterproofing compounds shall be compendious (cement based) non-shrinking, self curing mixtures. These shall be

- Free from sodium and chlorides
- Free from material detrimental to concrete and reinforcement.
- Able to create a membrane in one or multiple coats as per manufacturer's instruction.
- Membrane capable to prevent infiltration when applied to interior faces and ponded.
- Permeability, shear bond strength, compressive strength, volume changes meets minimum requirements of codes.

1.4.2 Accessories

All other accessories materials such as primers, bonding agents, polymers etc. shall be as recommended by waterproofing manufacturer.

1.5 Warranty

A. Special Warranty:

1. Warranty with attachments for full replacement value of completed installation signed by manufacturer, applicator and Contractor warranting against water infiltration and defects of materials and workmanship for period of ten years.

2. Provide warranty that covers labour and workmanship, including labour for access to waterproofing, for watertight warranty.

    a) Warrant penetrations, terminations, changes of direction, and membrane.

    b) Warranty shall include removing and reinstalling superimposed work covering waterproofing.

2.0 MATERIALS

2.1 Cement

2.1.1 Cement shall be ordinary Portland Cement conforming to IS and shall be of grade 43 or 33.

It shall be received in bags of 50 Kg and each batch shall be accompanied with a test certificate of the factory. Also it shall be tested before use to ascertain its strength, setting time, etc. In case cement has been stored for over 6 months or for any reasons the stored cement shows signs of deterioration or contamination, it shall be tested as per the direction of the Incharge prior to use in the works.

2.1.2 Cement shall be stored in such locations so as to prevent deterioration due to moisture dampness. A dry and water proof shed shall be provided. Bags shall be stacked on rigid water-proof platforms about 15 to 20 cm clear above the floors and 25 to 35 cm clear or away from the surrounding walls. A maximum high stack of 12 bags is permitted. Stacks shall be so arranged that the first batches are used first (FIFO), and that they permit easy access for inspection and handling.

2.2 Sand (coarse sand FM above 2.25 & Fine sand F M more than 1.25)

2.2.1 Natural sand deposited by stream or glacial agencies as a result of disintegration of rock is the best form of sand and shall be used.

2.2.2 Sometimes it is obtained from crushed stone screenings but often contains a high percentage of dust and clay. It tends to be flaky and angular. This type produces harsh concrete and should be avoided.

2.2.3 Sea sand shall not be used.

2.2.4 Sand shall be hard, durable, clean and free from adherent coatings and organic matter and shall not contain any appreciable amount of clay. Sand shall not contain harmful impurities such as iron, pyrites, coal particles, lignite, mica shale or similar laminated material, alkali, and organic impurities in such form or quantities as to affect the strength or durability of concrete or mortar.

2.2.5 When tested as per IS 2386 Part I and Part II, sand shall not exceed permissible quantities of deleterious materials as given in table 1 of IS 383.

2.2.6 Grading of sand shall conform to IS and shall fall within limits.

2.2.7 Sand shall be stored in such a way that it does not get mixed with mud, grass, vegetables and other foreign matter. The best way is to have a hard surface platform made out of concrete, bricks or planks. It should be to the approval of the Incharge.

2.3 Brick bats (CLASS 150 AS PER U P, L N V)

2.3.1 It shall be prepared from well-burnt bricks. In no case shall under-burnt bricks be used. Flaky and elongated pieces shall be avoided. It should also be free from adherent coatings of soil or silt. Brick bats should be free from alkalies, soft fragments, organic impurities, etc. in such quantities as not to affect strength and durability of concrete.

2.3.2 Water absorption for the bricks after 24 hours immersion in cold water shall not exceed 15%.

2.4 Water

2.4.1 Water used for mixing and curing shall be clean, reasonably clear and free from objectionable quantities of silt, oils, alkalies, acids, salts so as not to weaken mortar, or concrete or cause efflorescence or attack the steel in RCC while curing. It shall be free of elements, which significantly affects the hydration reaction. Potable water is generally satisfactory but it shall be tested prior to use in the works.

2.4.2 Water tested shall be such as to prevent any deleterious materials getting mixed with it.

2.4.3 Water shall be tested and approved in writing by the Incharge prior to use in the works.

2.5 Stone tiles such as kota / shahbad shall be of best quality and free from any defects and of uniform thickness.

2.6 MEMBRANCE

2.6.1 Synthetic elastomeric polymerized semisolid liquid and forming a film on curing.

2.6.2 Properties shall confirm to requirement as under:

1. Material : Free from sodium and chlorines

2. Chemicals : Not detrimental to concrete or reinforcing steel.

3. Colour : Manufacturer's standard

4. Testing Standards

a) Water : IS 3085

b) High temperature stability : ASTM D-794

c) Abrasion : ASTM D-968/57

d) Salt spray test : IS 2074

e) Acid / Alkali resistance : Unaffected over a period of 30 days by sulphuric

acid solution pH 1 and

sodium carbonate solution pH 13.5

f)	U.V. resistance	:	ASTM D-322
g)	Sword hardness after one week	:	50
h)	Elongation	:	20%
i)	Impact	:	25 Lb. test
j)	Abrasion Index	:	10-13

2.6.3 Accessories

Primers, bonding agents, water stops or plugs etc. as per recommendations of the manufacturer.

2.6.4 Mixes

a) Mix materials in accordance with manufacturer's instructions

b) Mix in clear containers

c) Do not re-temper mix after initial set.

2.7 Delivery / Storage

All materials shall be delivered and stored at site conforming to following minimum requirements.

- Material received is approved by Incharge.
- Material is in unopened container and labeled with manufacturer's name, brand name and instruction for use.
- Material received shall be along with manufacturer's certificate for quality and period of manufacture.
- Material shall be stored in dry, well ventilated and covered storage if so desired by manufacturer.
- Primers, adhesives etc. shall be as recommended by the membrane manufacturer.

3.0 SCOPE OF WORK

3.1 Work shall include supply, installation and test proprietary waterproofing systems to underground structure, terraces, toilet sunk slabs, water tanks etc. This shall be guaranteed for 10 years on Rs. 100/- stamp paper in proforma to be approved by the Incharge.

a) Water proofing of basement including sealing of services junctions, drain points, sumps shall be as per approved box type proprietary treatment.

b) Water proofing of terrace inclusive of grouting, sealing rainwater down takes outlets, other services outlets, junctions of walls, slab, beam, columns, parapet wall etc., where required expansion joints all as per approved terrace proprietary treatment.

3.2 Waterproofing of toilet sunk portions and water tanks inclusive of grouting, sealing, outlet pipes of services, junctions of slab, beams, walls and covering with protective cement sand plaster coat / screed.

3.3 Work shall include supply, installation and test proprietary box type system for basement and terrace system for sloped/flat roofs as approved by the Incharge. This shall be guaranteed for 10 years on Rs. 100/- Stamp paper in proforma to be approved by the Incharge.

Work shall conform to minimum standards specified. Systems detailed hereunder are to clarify type of water proofing system expected. Contractor is at liberty to suggest and submit equivalent system with products meeting / exceeding standards.

3.4 Sub Contractor / specialist shall be from the approved list and shall be approved by the Incharge in writing before being employed by the Contractor.

3.5 The Contractor shall submit

1. Statement giving detailed brief of work he proposes to carry out.

a) Name of agency with his experience certificate and quantum of work carried out.

b) Technical Specifications

c) Product data sheets of material to be used

d) Shop drawing detailing

- Sections coordinated with typical installation details
- Vertical termination and sealing
- Laps needed if any
- Typical expansion, construction and control jointing details with minimum requirement.
- Horizontal fixing and laying details.
- Typical finishing arrangement.
- Flashings if required.

e) Protective measures to be taken.

f) Installation guidance

g) Samples of each product in duplicate fixed over plywood boards or similar to enable proper cross sections.

h) Manufacturer's certificate that product and material to be used is correct and shall give intended results when applied through authorized agency.

4.0 WORKMANSHIP

4.1 Preparation of Surfaces

a) The surfaces to receive the treatment shall be thoroughly cleaned of

- Laitances, scales, loose material on surface.

- Grease, oil or other contaminants by etching with 10-15% of solution of muriatic acid using commercial grade alkaline cleaner, flushing with clean water drying and vacuuming.

b) Surfaces shall be examined and well defined cracks grouted by making 'V' groove / notches with cement slurry, shall be cured and dried well before treatment.

c) Any honeycombs shall be carefully cut and plugged, and cured well before treatment.

d) Examination of surface shall account for the fact that,

- Surfaces are cured for 14 days and no condensation has taken place.
- Horizontal and vertical surfaces have smooth finish, free from defects.
- Surfaces are dry, clean, free of grease, oil, dirt, rust, corrosion, other coatings and contaminants which could affect bond of water proofing system.

4.2 Box Type Water proofing installation

A. Stone method

It is a proprietary method. However basic steps (given below just for guide lines) are

FLOOR

1) Preparation of surface by cleaning, leveling etc.

2) 20 mm thick cement-sand-bedding mortar 1:3 (1 cement : 3 coarse sand) mixed with water proofing powder 4% by weight of cement shall be laid on surface and 20 mm graded aggregate free from impurities shall be spread on the floor. It shall be cured for 3 days.

3) Provide insert socket and pipes to release the sub soil water pressure.

4) Then 20 mm thick rough kota or similar stones of approximate 600x600 mm in size shall be laid flat over 20mm th. 1st layer mortar and joints sealed & grouted with cement slurry mixed with WPC. This shall project 300 mm all around RCC raft.

5) Then the surface shall be screened with 25mm th. cement- coarse sand-1:3 mortar and finished smooth.

6) RCC raft, walls or masonry shall be constructed as per design and standard specification.

7) The sockets / pipes are grouted with pressure.

8) Columns or any support etc. coming out of raft shall be sealed properly with aforesaid treatment / polysulphide sealant at all levels including and at top of raft / design foundation.

WALL

When walls are fully examined and prepared as detailed above, the treatment shall be

1) About 20 mm thick stone slabs shall be fixed with cement slurry grout. Grout mixed with water proofing compound 4% by weight of cement and joint 20mm thick (min) are well grouted and cured properly with 1:3 (cement : 3 coarse sand) mortar mixed with WPC.

2) External surface shall be plastered 20 mm thick with cement sand mortar 1:4 (1cement: 4 coarse sand) mixed with 4% by weight of water proof compound with heat cement punning mixed with WPC complete at all levels as directed by E/I .

3) Vertical joint shall be well cleaned and grouted to make sure it forms a continuous treatment. If required joint may be treated with sealant.

4) Treatment shall be taken about 300 mm above finished level.

5) All pipes etc. coming out of walls shall be sealed by grouting with sealant.

4.3 Terrace waterproofing (Block bat coba - CLASS 150 AS PER U P, L N V)

4.3.1 Experienced water proofing specialists shall carry out the following or similar types of water proofing treatments. Terraces and roof slabs shall be treated with integral cement based waterproofing consisting of block coba concrete laid to slope. The treatment shall be taken over vertical surfaces as required / specified. Final finished surfaces may be laid with paving tiles, stones or finished smooth in cement and marked with false chequered marking. Points given below are just for guidelines. The actual steps and details shall be as per standard specifications and accordingly submitted by the contractor for approval of the Incharge. Work shall be carried out as per Indian standards approved method by the Incharge.

4.3.2 Surface preparation

The surface to be treated shall be cleaned and inspected thoroughly

a) All minor, medium cracks shall be marked.

b) All cracks shall be well defined and 'V' groove made. These shall be cleaned with compressed air, grouted with cement sand mortar 1:4 (1 cement: 4 sand) slurry mixed with non shrinking and waterproofing compound. Areas well cured.

c) Then again surfaces shall be well cleaned of all loose particles, laitance, moss, oil / greasy material, cement etc.

d) Roof areas shall be well marked with spot datums to create ridge, lines, slopes and drain points for easy draining of water (Nominal slopes shall be about 1:100).

e) Cement sand mortar mixed in ration 1:4 along with water proofing and non-shrinking compound as specified by manufacturer shall be mixed with clean water and layer of

about 20 to 30 mm laid over the entire area to be treated; then well soaked saturated block bats shall be arranged by proper placing to create required slope as per datum established. Minimum thickness at draining point shall be 75 mm.

Rain water inlet, pipes etc. shall be well grouted; edge, corners shall be well rounded (watta) by taking up treatment about 300 mm above proposed finished level.

f) These mortar laid and bat fixed area shall be kept dipped in water for atleast 3 days.

g) Slab and roof sofits shall be examined for dampness from under. Any leakage / dampness noticed shall be treated with pressure grouting and again checked by dipping the area for 3 days.

h) When no dampness noticed, area shall be drained out and cement sand mortar mixed in ratio 1:4 (1 cement: 4 sand) shall be spread over the entire area and bats well grouted.

The top surfaces shall be finished to a neat horizontal datum level to achieve well defined ridges, gutters, watta etc. Edges shall be tucked in grooves in wall / parapet about 300 mm above proposed finished level.

i) Surfaces shall be finished / prepared to receive about 40 mm thick IPS (Indian patent stone) or China mosaic etc.

j) All expansion joints shall be cleaned, primed and finished with sealant as specified by manufacturer of sealant and approved by Incharge.

4.3.3 Products and Manufacturers

Acceptable Products:

1. Distilment DS+ MC-Bauchemie (India) Pvt. Ltd.

Nafufill – VV2

2.	Formak 629	Aqua Alliance Agencies
3.	Tapecrete	CICO
4.	Hydro-tight	Xypex
5.	Polyakk-WP	Sunanda Speciality Coatings
6.	Mastercrete M-81	Choksey Chemicals Pvt. Ltd.

4.4 Basement Top terrace waterproofing

4.5 Experienced water proofing specialist shall carry out the above or similar types of waterproofing treatments. Terraces and roof slabs shall be treated with integral cement based waterproofing consisting of light weight Perlite brick bat coba concrete laid to slope. The treatment shall be taken over vertical surfaces as required / specified. Final finished surfaces may be laid with flooring / paving tiles, stones or finished smooth with cement.

4.5 Points given below are just for guide lines. The actual steps and details shall be as per standard specification submitted by the contractor for approval of the Incharge. Work shall be carried out as per Indian standards approved method by the Incharge.

4.4.3 Surface preparation

The surface to be treated shall be cleaned and inspected thoroughly

a) All minor, medium cracks shall be marked.

b) All cracks shall be well defined and 'V' groove made. These shall be cleaned with compressed air, grouted with cement sand mortar 1:4 (1 cement: 4sand) slurry mixed with non shrinking and waterproofing compound. Areas well cured.

c) Then again surfaces shall be well cleaned of all loose particles, laitance, moss, oil / greasy material, cement etc.

d) Roof areas shall be well marked with spot datum to create ridge, lines, slopes and drain points for easy draining of water (Norminal slopes shall be about 1:100).

e) Light weight Perlite concrete having density 450kg/Cum shall be mixed as specified by the manufacturer, with clean water and layer of about minimum 75 mm laid over the entire area to be treated; creating required slopes as per datum established. Rain water inlet, pipes etc. shall be well grouted; edge, corners shall be well rounded (watta) by taking up treatment about 300 mm above proposed finished level.

f) 4 mm thick APP Polymer modified polyester reinforced torch on membrane (Garden Moply FP 4) of STP Texsa Ltd., 16, NGN, Vaidya Marg, Bank Street, Fort, Mumbai- 400 023 (Tel: 022 22664643, Fax: 022 22661730) or equivalent approved; is laid over light weight concrete, Control and construction joint shall be reinforced with memberane strip as specified by manufacturer. All corner joints between vertical and horizontal surfaces shall be reinforced with strip as specified by the manufacturer. Expansion joints are formed as detailed and approved by structural consultant. Drains shall be sealed with proper flashings and laps as per details approved in shop drawing.

g) Slab and roof shall be examined for dampness from under. Any leakage / dampness noticed shall be treated with pressure grouting and again checked by dipping the area for 3 days.

h) When no dampness noticed, area shall be drained out and cement sand mortar mixed in ratio 1:4 (1 cement : 4 sand) shall be spread over the entire area and well grouted.

The top surfaces shall be finished to a neat horizontal datum level to achieve well defined ridges, gutters, watta etc. Edges shall be tucked in grooves in wall / parapet about 300 mm above proposed finished level.

i) Surfaces shall be finished / prepared to receive about 30 mm thick cement sand mortar screed about 30 mm thick over laid membrane and cured.

j) All expansion joints shall be cleaned, primed and finished as per specification and grouted with sealant as specified by manufacturer of sealant and approved by Incharge.

4.5 Waterproofing to water retaining structures

4.5.1 Crystalline waterproofing of Xypex or equivalent approved; waterproofing compound one / two coat shall be applied to water retaining structures.

4.5.2 Steps followed shall be as per the directions of the manufacturers and approval of the In charge. For guideline following steps may be followed.

1. Surface preparation

   Clean the surface to remove dust, loose particles and laitance.

2. Apply Crystalline waterproofing compound one / two coats at specified intervals as recommended by the manufacturer on concrete / plastered surface.

3. Protect horizontal surfaces with 30 mm thick IPS 1:2:4 (1 cement : 2 sand : 4 aggregates) laid to gradient; with adding waterproofing compound 2% by weight of cement and vertical surfaces shall be plastered with cement sand mortar in a ratio of 1:4 (1 cement : 4 sand) with using 2% waterproofing compound by weight of cement.

4. Wattas and rounding of corners, junctions with walls and floors and finished smooth and cured.

5. Curing shall be done for 7 days.

4.5.3 Treatment shall be tested by ponding water about 250 mm high for 72 hours. Surfaces shall be examined for leakage seepage, dampness, sweating etc.

4.5.4 Measurements shall be in square metre for finished surface area. Rates shall include all items right from cleaning of surface to

completion and testing required against defects such as leakage, seepage, dampness, sweating etc. and providing guarantee of employer's.

5.0 TESTING

5.5.1 On completion of installation and prior to next operation or as directed by Incharge work shall be tested by the Contractor. Required water shall be arranged and disposed of by the contractor at his cost.

a) All openings, drains etc. shall be plugged.

b) Water shall be flooded about 200 mm over the Sunk portion. Water shall be kept for 72 hours.

c) Surfaces shall be observed critically and incase any leakage is observed areas shall be treated again and tests to be carried out again to the satisfaction of the Incharge.

5.5.2 Approval of water test does not relieve the contractor of his obligation of providing installed water proofing guaranteed for 10 years as per contract.

5.5.3 All arrangement of material, labour etc. required including preserving and maintaining areas flooded shall be carried out by the Contractor at his cost.

6.0 GUARANTEE

6.1 All waterproofing systems described above are to be referred as guide-lines only. The contractor may propose the system along with his tender, giving full descriptions.

6.2 The system shall be guaranteed for 10 years against all defects and liabilities thereof from the date of completion of project. The guarantee shall be on Stamp Paper of Rs. 100/- in Performa to be approved by Employer / Incharge. (The contractor shall submit Performa to PM/ RE for approval of Employer before being written on Stamp Paper). The cost of Stamp Paper shall be to the contractor's account.

6.3 Work shall be carried through approved specialist agency as per method of working approved in writing by the Incharge.

REINFORCED CEMENT CONCRETE PIPES

Manufacture of pipe

The RCC pipes to be used for lateral, branch and trunk / outfall sewers shall be of class NP-3, Spigot and Socket (S&S) type, RCC SPUN / VIBRATED CAST PIPES (REINFORCED), with rubber gasket jointing, manufactured in Conformity with IS 458. All the Pipes shall be manufactured using Sulphate Resisting cement only. The ends of the pipes shall conform to Clause 5.3 of IS 458 as applicable for S&S joints. The rubber ring shall conform to IS 5382 and IS 12820 as applicable for sewer lines and shall be of type ‘IA’. The diameters of pipes shall be as required for sewers as per designs and drawings.

The method of manufacture shall be such that the form and dimensions of the finished pipes are accurate within the limits specified in relevant IS: 458. Pipes manufactured in compliance with IS: 458 shall be either water cured or steam cured in accordance with the relevant requirements of IS: 458.

The Internal diameter, wall thickness, length of barrel, reinforcement (longitudinal and spiral), type of ends and minimum clear cover to reinforcement, strength test requirements, tolerances

on - overall length, internal diameter or dimensions of sockets / spigots of pipes shall be as per the relevant clauses / tables of

IS: 458. Minimum clear cover to reinforcement shall be 15 mm. The tolerances regarding overall length, internal diameter of pipes or socket and barrel wall thickness shall be as per relevant clauses of IS: 458. Each pipe unit shall be in lengths of 2 m to 4 m based on availability, ease in handling, transportation and laying.

The workmanship and finish for the pipe will conform to the relevant Indian standard specification; Cleaning of pipes shall conform to relevant Indian Standard specification.

Special coating for Inside Surface of RCC Pipes.

The RCC pipes shall be provided with special coatings wherever there is possibility of excess generation of hydrogen sulphide gas during transportation of sewage through sewers. The location, length of coatings shall be as given in construction drawings or as approved by the Engineer.

The work involves

i). Supply and application of Polymer based protective Elastomeric coating / Lining with zero V.O.C. for complete inside surface of RCC sewers, with minimum dry film thickness of 1mm, Acid resistant, Abrasive resistant, Adhesive to concrete surface, Durable and pinhole / break free, with smooth surface after application, complete as per the Clauses in this Section, including all labour, HOM of machinery, with all lead lifts, taxes etc. complete. spray coating / Lining shall be applied by approved and controlled mechanical spray method, for RCC sewers of diameters 400mm to 800 mm prior to delivery of sewers to site or applied at site, as approved by approving authority, including all surface preparation, testing, as per directions of the Engineer in charge. Rate shall be inclusive of cost of all materials, tools and plants, testing and inspection etc. complete.

ii) Supply and application / lining of Polyvinyl chloride sheet, having T-shaped protections on the back, keyed into the RCC Sewer walls at the time of manufacture, of thickness not less than 1.5mm or Polymer based protective Elastomeric smooth coating / Lining with zero V.O.C. by spray method for complete inside surface of RCC sewers, with minimum dryfilm thickness of 1mm, Acid resistant, Abrasive resistant, Adhesive to concrete surface, Durable and pinhole / break free, smooth surface after application, complete as per the Clauses in this

Section, including all labour, HOM of machinery, with all lead, lifts, taxes etc. complete, spray coating / Lining applied by approved method, for RCC sewers of diameters equal to and greater than 900mm prior to delivery of sewers to site or applied at site, as approved by approving authority, including all surface preparation, testing, and directions of the Engineer in charge, Rate shall be inclusive of cost of all materials, tools and plants, testing and inspection etc. complete.

Specifications for Protective Coating to inside surface of RCC sewers:-

A). POLYMER BASED COATING :

a) The inside of RCC pipes (of dia 400mm & above) & manholes (if required) shall be coated with an approved dual-component, solvent-free polymer protective coating of minimum 1mm dry film thickness. The protective coating shall be spray-applied to the inside of the pipes using suitable plural component spray equipment so as to form a completely impermeable, pin-hole-free & seamless lining. It shall form a good bond with host concrete surface, be resistant to acids & abrasion. It shall meet the following properties.

A – ACID RESISTANCE	
Acid & Chemical Resistance (to ASTM 3908- mod 365d immersion)	Change in weight (not more than).
Sulphuric Acid 22%	0.07%
Hydrochloric Acid 10%	0.07%
H2S-120,000ppm (Sour Brine)	0.66%
Sodium Hydroxide 25%	0.07%
Sodium hypochlorite(sat sol)	0.66%
Salt water – 310g/l (Sat. Sol)	0.22%
Ammonium Hydroxide-20%	nil
Nacl/water-solution -10%	nil
Wastewater anaerobic digesters	0.37%
Wastewater API mo	1.1%
B – BOND	
Bond / Adhesion to concrete (to ASTM D 4541)	> 1.5 N / Sq mm

C - ABRASION RESISTANCE	
Abrasion resistance (to ASTM D 4060 with Taber CS17-1000/1000rev)	< 15 mg loss
Shore D Hardness (to ASTM D-2240)	> 60
D - DURABALITY	
Volume solids %	100
Tear resistance (to Die Cast ASTM D 624)	> 30 KN / m
Tensile strength (to ASTM D412)	>17 N / Sq mm
Elongation (to ASTM D-412)	> 30%
Water absorption(to ASTM D 570 (2hr @95 C)	0.16
Flash Point (Pensky martin)	>93 deg C
E – SETTING TIME	< 1 minute

b) The coating shall be moisture sensitive,suitable for long term service at any temperature within the range between -10 Deg C and 100 Deg C and resistant to raw sewer, industrial sewer, treated sewer, effluents, chemicals, sea water, abrasives. The coating shall not be affected by high humidity or moisture during application.

c) All the coating materials including primer & finish coats shall be from a single manufacturer of repute certified to ISO 9002 standards having a minimum 10 years experience in similar products & in projects of similar size and value as this project.

d) The material provided shall be tested in both liquid (lab-draw down films) and field applied samples and shall meet the properties specified for the project and defined in the approved manufacturer’s product data sheet.

e) All pre-coating concrete repairs, coating and lining works shall be carried out only by experienced & reputed contractors who are authorized, approved, and certified applicators of the approved coating manufacturer & certified by the manufacturer for the type of application detailed in this project.

f) The contractor should submit, the approved coating manufacturer's detailed Method Statement for Coating Application along with their Quality Assurance / Inspection & Testing Plan to engineer in charge prior to commencement of coating activity.

Surface Preparation & Primer application

Prior to commencement of coating activity, all concrete surfaces to be coated shall be free from oil, grease, loose particles, decayed matter, moss, curing compound residue or algal growth. All such contamination and laitance must be removed by use of abrasive sweep blasting, high pressure water jetting, or other approved manual/ mechanical means.

Concrete element's surface irregularities, honeycombs spews must be removed and repaired by a method approved by the engineer.

Primer as recommended by the approved coating manufacturer shall be applied prior to coating application & the correct over coating time intervals shall be followed as per manufacturer's approved method statement of application.

The coating system shall be spray applied & shall gel/set rapidly. It shall form a uniform monolithic film without any layering.

The pipes shall be coated either at pipe factory or at other department-approved coating yard prior to actual laying.

Testing:-The finished coating shall be uniform, smooth & have a dry film thickness of minimum 1000 microns, when tested with a standard dft gauge/ Elcometer.

The dry film thickness shall be measured at points as instructed & predetermined by the engineer in charge by fixing SS strips. The coating shall be uniform, smooth & pin hole free.

Personal Safety Requirements:- The personnel at site shall strictly adhere to Standard guidelines during the chemical coating activity, at all times. The approved coating manufacturer shall supply complete standard requirement schedules for the personnel to follow, prior to start of any coating application. The general requirements are:-

a. Observe the owners standard policy at all times and obey all written and verbal instructions from site managers and representatives.

b. Wear all PPE at all times including Hard Hat, Safety glasses, Boots, Gloves and masks as required.

c. When preparing and applying coatings and chemical materials all PPE must be worn including Gloves, safety glasses and protective paper masks.

d. When using high pressure plural component spray equipment, all personnel working in the application area must wear double filter breathers with OSHA or of atleast equivalent make.

B). P.V.C. LINING FOR RCC PIPES:

Scope of work for PVC lining in RCC pipes,

Reinforced concrete pipes of diameter 900mm and above is to be lined with PVC of minimum thickness of 1.5 mm. The lining shall be fixed to concrete surface be mechanical keys and cover complete internal circumference of the pipes. Care shall be taken to see that the resulting wall thickness, internal diameter & length of barrel does not become less than the minimum specified in IS 458. The tolerances regarding overall length, internal diameter of pipes or socket and spigot wall thickness shall be as per IS: 458. However, due to providing of PVC lining, negative tolerance for internal diameter of pipe upto maximum 3 mm is permitted.

Drawings and details indicating method of manufacture, lining, welding of joints, etc., together with test certificates of physical, chemical and biological properties of the PVC shall be submitted for Engineers in charge's approval prior to manufacturing of any pipe.

The internal surface (PVC lining and unlined concrete surface) of the pipe shall be free from wrinkles, bulges, corrugations, burnt surfaces and imperfection. The lining shall be firmly keyed into the concrete with the back face of the lining flush against the concrete surface. The keys shall be continuous and capable of withstanding a back pressure of not less than 0.48 N/ mm2. Partially embedded keys will not be acceptable. There must be complete bonding in all welds.

Only pipes manufactured and lined to the satisfaction of the Engineers in charge are acceptable. Minor defects may be repaired with approval of Engineers – In charge but each defect must be made good to the complete satisfaction of the Engineer in Charge who reserves the right to reject any pipe (or pipes) which in his opinion do not comply with this Specification and the required standard.

Approved PVC lining should not be less than 1.5 mm thickness. In the event of the PVC lining being damaged during the construction of the sewer, the whole pipe shall be replaced entirely at the Contractor's expense.

When pipes are laid, care shall be taken to keep the cover flaps clear of the adjoining pipe socket and to place the pipe in the correct position so that the PVC sheeting is evenly divided by the vertical pipe centre line.

At regular intervals the Contractor shall arrange for his pipe supplier to visit the site and weld up and test the PVC joint flaps and end cover fillets. Not more than three (3) pipes shall be laid before the joints are welded up.

The Contractor will be required to afford all necessary assistance in keeping the pipes clear of mud and water during the jointing of the PVC flaps.

The Contractor will be required to make arrangements for the supply of water and power and for the proper ventilation of the pipeline during cleaning, tacking and welding and testing of the PVC joints.

On completion of the laying, jointing and welding, the Contractor will be required to carry out a detailed inspection and test of the PVC lining and joint welding in the presence and to the satisfaction of the Engineer in charge.

Physical & chemical properties & testing methods.

TABLE A – PHYSICAL PROPERTIES

Property	Allowable Standard		Method
Tensile Strength	Longitudinal	17.25 Mpa	ASTM D 638
	Transverse	17.25 Mpa	
Elongation at break	Longitudinal	225%	ASTM D 638
	Transverse	225%	
Hardness	54-62		Din 535.5
Plasticier Permanence	0.4%		ASTM D 1203
Water Absorption	0.1%		ASTM D 570
Water soluble matter	0.05%		ASTM D570
Porosity	No pin holes		Spark Tester 7 KV

TABLE B – CHEMICAL PROPERTIES

Chemical Agent	Test Method	Change in Weight Not more than
Sodium Hypo–Chloride 1%	ASTM D 543 (7 days at 20 degree C)	0.20%
Ferric Chloride 1%		0.60%
Sodium Chloride 5%		0.15%
Sulphuric Acid 20%		0.12%
Nitric Acid 1%		0.20%
Sodium Hydroxide 5%		0.10%
Ammonium Hydroxide 5%		0.40%
Soap & Detergent Solution 2%		0.40%

Testing of pipes at manufacturing unit.

During manufacture, tests on concrete shall be carried out as per IS: 456, IS 458 / relevant IS with latest revisions and amendments.

The specimen of pipes shall be tested in accordance with clause 1.2.8 of this Technical specification and with IS: 458 and tested in accordance with the methods described in IS: 3597 including the following,

1. Hydrostatic test.

2. Three edge bearing test

3. Absorption test.

3.3. Marking

Marking shall be done as per IS: 458 or any other relevant IS codes approved by the Engineer. The following information shall be clearly marked on each pipe,

a). Internal diameter of pipe.

b). Class of pipe.

c). Date of manufacture and

d). Name of manufacture or his registered trade-mark or both.

a. Carting & Handling

Carting and handling of RCC pipes and fittings shall be in accordance with the clause 3.4. of GSW pipes specifications.

b. Trenching.

Trenching includes all excavation which shall be carried out either by hand or by machine and shall be carried out in accordance with all requirements of Earth work excavations clause 2.0 to 2.17. Wherever a socket or collar of pipe or fitting / special occurs, a grip is to be cut in the bottom of the trench or concrete bed to a depth of at least 75 mm below the bed of the pipe so that the pipe may have a fair bearing on its shaft and does not rest upon its socket. Such grip shall be of sufficient size in every respect to admit the hand all round the socket in order to make the joint, and the grip shall be maintained clear, until the joint has been approved by Engineer.

c. Bedding

Necessary bedding (granular, concrete cradle, concrete arch etc.) shall be provided in accordance with approved construction drawings and specifications in the following clauses 6.1. to 6.1.5 of this specifications before laying of RCC sewer pipes.

d. Laying of the pipe

Laying of concrete pipes shall conform to the Code of practice of IS: 783. Pipes shall be laid underground with a minimum earth cover of 1m. Pipes shall be generally laid in sections as per standard practices and as directed by the Engineer. The RCC pipes shall be laid with sockets facing up the gradient, on desired bedding. All pipes shall be laid perfectly true, both to line and gradient. At the close of each day’s work or at such other times when the pipe is not being laid, the end of the pipe should be protected by a close fitting stopper. All pipes, fittings and material shall be tested and approved by the Engineer before being laid. Any pipes, fittings or material placed before they are tested and approved shall be removed and replaced with tested and approved material. Before laying the pipe, necessary bedding shall be provided wherever required as per Sub-Clauses 6.1. to 6.1.5 of this section.

e. Jointing of pipes

The pipe joints shall be flexible joints, jointed by rubber ring of type 'IA', as per IS 783-1985. The sections of the pipe shall be jointed in such a manner that there shall be as little unevenness as possible along the inside of pipe. Care should be taken while jointing to provide the correct gap between the end of spigot and back of the socket to ensure flexibility at each joint and correct location. The joints shall be finished as directed by the Engineer.The quality of rubber rings, tolerances, etc., shall be in conformity with IS 5382-1985 and latest revisions.After jointing, extraneous material, if any, shall be removed from the inside of the pipe.

f. Measurement of pipes

The length of the sewer pipes shall be measured between the inner surfaces of consecutive manholes at the invert level of the pipes along the central line of pipeline to the nearest centimeter.

g. Testing at work site.

After laying and jointing of pipes is completed, the pipe line shall be tested at work site as per all the requirements in clause 9.0 to 9.5 of this specifications and as approved by the Engineer.

h. Backfilling.

Backfilling shall be in accordance with requirements specified in clause 6.3 to 6.3.4. of backfilling.

Measurement of pipes

The length of the sewer pipes shall be measured between the inner surfaces of consecutive manholes or start to end points of laid alignment (at road crossings and Nala Crossings) at the invert level of the pipes along the central line of pipeline to the nearest centimetre.

ANCILLARY STRUCTURES – MANHOLES, DROP MANHOLES AND VENTILATING SHAFTS.

The Contractor shall construct Wire cut brick, RCC-Manholes, Drop arrangements with HDPE pipes, Cast iron Ventilating shafts, Valve Chambers, at the locations shown on approved construction drawings, as directed by the Engineer as per the specification in the applicable Indian standards mentioned and as mentioned hereafter.

The materials used and construction procedure adopted for the ancillary structures shall comply to the specifications as mentioned below and clause in standard specifications for civil works.

Excavation

Earth work excavations for the Manholes, Drop arrangements and C.I. Ventilating shaft arrangements etc. shall be carried complying to specifications in clause 2.0 to 2.17 and specifications in bill of quantities.

Backfilling.

Backfilling for sewer ancillary structures shall be in accordance with requirements specified in clause 6.3 to 6.3.4 of Backfilling.

Manholes

Manholes shall be built at every change of alignment, gradient or diameter, at the head of all sewers and branches, at every junction of two or more sewers as shown on the drawings complying to IS: 4111 Part1-1967 and latest revisions and as per specifications in this section or as directed by Engineer. Sulphate resisting cement confirming to IS: 12330 shall be used for all the items of works for manholes. The shape of the manholes generally is circular with conical shape at top for Brick manholes, unless specifically stated as on drawings.

The Contractor shall be wholly responsible for giving suitable connections at the junctions of sewer lines with the manholes. The minimum depth of manhole shall be one meter or as in construction drawings or as directed by Engineer.

The Manholes have been divided into different categories based on depth, diameter and material of construction. Any manholes required to be provided extra, at the locations shown by the Engineer, shall be provided by the Contractor, for which payment shall be made at the quoted rates.

Wire cut Brick Manholes.

Construction.

The work shall be executed in accordance with the approved construction drawings and specifications involving,

a). Providing and constructing of 1:3:6 Cement Concrete foundation using approved quality aggregates of 40mm and downsize with an offset of 150mm all round the chamber.

b). Providing and constructing wire cut brick masonry in C.M 1:4 proportion using modular wire cut bricks of class designation 75 of approved quality and confirming to IS : 1077 with a tapering top portion as per approved construction drawings and providing cement mortar plaster in CM 1:3 proportion, 12mm thick inside and outside except for the conical surface outside, where the thickness of plaster shall be 20mm thick.Samples of bricks shall be tested as per IS : 3495 by the Contractor. Bricks rejected by the Engineer shall be removed from the site within 24 hours.Construction of Brick works shall be in accordance with IS 2212:1962 and latest revisions.

c). Providing and constructing benching with Cement Concrete 1:2:4 to the dimensions as on drawings with 1:6 slope in the concrete towards the central drain, plastered with CM 1:3 proportion, 20mm thick and finished with smooth coat of neat cement and fixing of inlet and outlet sewers in the walls with the internal periphery protected with an arch of 1:2:4 Cement Concrete with graded metal of 10mm to 20mm size.

d). Supplying and fixing of, 3 mm thick plastic (as per IS: 10910) encapsulated over 12mm dia. Fe-415 steel (as per IS: 1786) bar footsteps staggered at 300mm apart and providing and fixing of heavy duty circular steel fibre reinforced concrete (SFRC) manhole frame and covers of 560 mm diameter conforming to IS 12592 and the payment for providing of SFRC heavy duty manhole frame and covers shall be paid separately as per quoted rate for the item in bill of quantities.

e). The channel for the manhole shall be constructed in cement concrete of M15 grade. Both sides of the channel shall be taken up to the level of the crown of the outgoing sewer. They shall be benched up in concrete and rendered in cement mortar (1:1) of 20 mm thickness and formed to a slope of 1 in 12 towards the channel.

f). The manhole construction work includes curing, pouring tar over MH frame and cover, cost of tar, engraving manhole number and flow direction on the inner surfaces etc., with all lead and lifts, finishing etc complete. The cement used for the construction of masonry works and internal & external

plastering works of manholes shall be of sulphate resisting cement only confirming to IS:12330.

Testing.

All Brick Manholes shall be tested as per relevant provisions in CPHEEO Manual & relevant IS with latest revisions & amendments and specifications in clause 9.0 of Testing and commissioning.

Measurement & payment.

The depth of manhole shall be measured from the top of cover to the invert level of the deepest outgoing sewer from the manhole.The quoted rate for the Manholes for various depths as per the specifications and drawings shall include the cost of sulphate resisting cement, bedding concrete, benching concrete, wire cut brick masonry, plastering, foot steps, fixing SFRC manhole frame with cover, dewatering to keep the manhole dry until final testing etc complete.

The Rates for any fractional variation (increase or decrease) in the depth of the manhole on decimetre basis, shall be paid as per actuals, by adding the difference in rates between the immediately preceding and succeeding depths of such fractional depth of manhole on linear basis.

For Example: To pay 1.22M depth manhole:

Rate for 1M depth Manhole excluding manhole frame & cover and including encapsulated foot steps rate Rs. X.

Rate for 2 M depths Manhole excluding manhole frame & cover and including encapsulated foot steps rate Rs. Y.

Therefore rate for 1.22M depth Manhole

= Rs. X + (Y-X)/1.00 x 0.22.

Note: For the depths of manholes less than the lowest depths of Bill of Quantities item, the preceding manhole depth shall be taken as zero with zero value to arrive at the rate

RCC Manholes.

Construction.

The construction of RCC manholes shall be by Cast In-situ of Circular in shape or approved type Pre-Cast RCC, constructed using form vibrators of standard type, using SRC Cement confirming to IS: 12330. The type of manhole to be constructed shall be as approved by BWSSB, Contractor shall take prior approval for the Design and Process of manufacture of the Pre-cast RCC manholes, the type of

vibration for compaction of concrete for pre-cast manholes shall be invariably of form or table vibrator type.

The work of Cast In-situ RCC manholes includes,

a). Providing and constructing of 1:3:6 Cement Concrete foundation using approved quality aggregates of 40mm and downsize with an offset as given in the drawings.

b). Providing and laying granite jelly cement concrete 1:1.5:3 for beds of manholes etc., using 20mm and down size jelly including laying, tamping, etc. for a depth, as per drawings, with water proof compound for top plaster in CM 1:3 curing and smooth finishing for exposed faces with necessary centering and form work etc., complete as per specification, drawing and as directed by the Engineer.

c). Providing and laying cement concrete of 1:1.5:3 proportion for vertical walls using 20mm and down size jelly including laying, tamping, mixing of required quantity of water proof compound for every one bag of cement for plastering in CM 1:3 curing and smooth finishing for exposed faces with necessary centering and form work etc., complete as per specification, drawing and as directed by the Engineer.

d). Providing and constructing benching with Cement Concrete 1:1.5:3 to the dimensions as on drawings with 1:6 slope in the concrete towards the central drain, plastered with CM 1:3 proportion, 20mm thick and finished with smooth coat of neat cement and fixing of inlet and outlet sewers in the walls with the internal periphery protected with an arch of 1:1.5:3 Cement Concrete with graded metal of 10mm to 20mm size.

e). Providing and laying cement concrete of grade 1:1.50:3 proportion with 12mm to 20mm I.S.I gauge of approved gradation hard broken granite/aggregate including cost and conveyance of all materials with wood or steel shuttering form work including machine mixing , centering form work, scaffolding, tamping , vibrating , curing and smooth finish with CM 1:3, 12mm thick for inside surface for RCC Covering Flat Slab with all lead and lifts, etc. complete as per drawing, specification and as directed by the Engineer.

f). Providing, Supplying and fabricating of TMT (Fe-500) reinforcement steel of all sizes, including straightening, cutting, bending, hooking, lapping and/or welding wherever required,

placing in position, tieing with binding wire of approved quality and gauge including the cost of binding wire and anchoring to adjoining members wherever necessary including all laps and wastages etc., with all lead and lifts, complete as per design, specification and directed by Engineer.

g). Supplying and fixing of, 3 mm thick plastic (as per IS: 10910) encapsulated over 12mm dia. Fe-415 steel (as per IS: 1786) bar footsteps staggered at 300mm apart and providing and fixing of heavy duty circular steel fibre reinforced concrete (SFRC) manhole frame and covers of 560 mm diameter conforming to IS 12592 and the payment for providing of SFRC heavy duty manhole frame and covers shall be paid separately as per quoted rate for the item in bill of quantities.

h). The RCC Manhole cost includes all materials, steel, curing, pouring tar over MH frame and cover, cost of tar, engraving manhole number and flow direction on the inner surfaces etc., with all lead and lifts, finishing etc complete. The cement used for the construction of RCC manhole and internal & external plastering works of manholes shall be of sulphate resisting cement only, confirming to IS:12330.

The work of construction of Pre-cast RCC manhole includes,

a). Providing & laying mechanically mixed cement concrete of M-15 grade with stone aggregate (with 20 mm nominal size graded stone aggregate) in benching, Neat cement punning over PCC benching, as given in the drawings.

b). Construction of approved type vibrated Pre-Cast RCC Manhole Chambers constructed using Sulphate resistant Cement & form vibrator of standard type for Circular Manhole Chambers of various internal dia (as indicated in BOQ) at bottom and 0.50 dia at top made up of pre-cast monolithic base, modular riser and top cone in M- 30 grade concrete placed & aligned to provide vertical sides, with O ring rubber gasket at each joint, water tight & adjustment rings over top cone, complete and all connections shall have, a water tight seal between the pipe and the manhole complete as per standard design & drawing.

c). Making connection of drain or sewer line with existing manhole including breaking in to and making good the walls, floors etc. with CC 1:1:5:3. Finishing with CM 1:3 with a floating coat of neat cement and making necessary channels for drain etc. as per specification, drawing and as directed by the Engineer.

d). Providing, Supplying and fabricating of TMT (Fe-500) reinforcement steel of all sizes, including straightening, cutting, bending, hooking, lapping and/or welding wherever required, placing in position, tieing with binding wire of approved quality and gauge including the cost of binding wire and anchoring to adjoining members wherever necessary including all laps and wastages etc., with all lead and lifts, complete as per design, specification and directed by Engineer.

e). Providing MS Foot rests and fixing in manhole with CC Block of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate of 20 mm nominal size) of size 20x20x10 cm with 20mm square bar foot rest, and providing and fixing of heavy duty circular steel fibre reinforced concrete (SFRC) manhole frame and covers of 560 mm diameter conforming to IS 12592 and the payment for providing of SFRC heavy duty manhole frame and covers shall be paid separately as per quoted rate for the item in bill of quantities.

f). The RCC Manhole cost includes providing danger lighting & use of sight rails & boning roads shoring & strutting wherever required, including sand bedding, watering, curing, cost of all materials, labour, supply & fabrication of steel, pouring tar over MH frame and cover, cost of tar, engraving manhole number and flow direction on the inner surfaces etc., with all lead and lifts, finishing etc complete. The cement used for the construction of RCC manhole and internal & external plastering works of manholes shall be of sulphate resisting cement only, confirming to IS:12330.

Testing.

All RCC Manholes shall be tested as in specifications in clause 9.1.3. of Testing of manholes.

Measurement & payment.

The depth of manhole both for Cast In-Situ / Pre-Cast RCC manholes shall be measured from the top of cover to the invert level of the deepest outgoing sewer from the manhole. The quoted rate for the Manholes for various depths as per the specifications and drawings shall include the cost of sulphate resisting cement, bedding concrete, benching concrete, RCC floor & roof slab, shaft walls, plastering, foot steps, fixing SFRC manhole frame with cover, dewatering to keep the manhole dry until final testing etc complete.

The Rates for any fractional variation (increase or decrease) in the depth of the manhole on decimetre basis shall be paid as per actuals, by adding the difference in rates between the immediately preceding and succeeding depths of such fractional depth of manhole on linear basis.

For Example: To pay 1.22M depth manhole:

Rate for 1M depth Manhole excluding manhole frame & cover and including encapsulated foot steps rate Rs. X.

Rate for 2 M depths Manhole excluding manhole frame & cover and including encapsulated foot steps rate Rs. Y.

Therefore rate for 1.22M depth Manhole

= Rs. X + (Y-X)/1.00 x 0.22.

Note: For the depths of manholes less than the lowest depths of Bill of Quantities item, the preceding manhole depth shall be taken as zero with zero value to arrive at the rate.

Drop Manholes.

In a manhole, wherever the difference between the invert level of downstream sewer and the invert level of the upstream sewer is greater than 60 cm, a drop manhole shall be provided at that position. The locations and construction of the drop manholes shall be provided as on drawings.

HDPE Grade PE-100 pipes confirming to PN 6 as per IS:4984 with latest revisions and amendments suitably supported with MS fasteners at 300 mm c/c. for diameters pipe line as per Bill of Quantities, construction drawings and as directed by Engineer, specials conforming to IS: 1729 shall be used for providing the drop in the manhole & a suitable expander/reducer T-Joint at the top with incoming sewer and 45 degree bend at the bottom with HDPE specials to the direction of flow in the receiving sewer, encasing the pipe with cement concrete of 1:2:4 proportion including necessary centering and form work, vibrating, curing, including cost and conveyance of all materials, labour with all lead and lifts, etc., complete as per specification and as in construction drawing. The benching concrete in the manhole should surround the joint of the terminating bend and a neat channel shall be made in the benching concrete to direct the flow to the receiving sewer. A continuation of the incoming sewer should be built through the shaft wall to form a rodding and inspection eye, which should be provided with half blank flange as on drawing. The drop manhole arrangements shall be tested along with sewer lines.

TESTING AND COMMISSIONING.

Testing at site.

All sewers and appurtenances shall be tested before commissioning and trial run as per the specifications in this section. After laying and jointing of sewer pipes and before backfilling the trenches, the complete length of the sewer is to be checked for water tightness and the sole responsibility of arranging the necessary equipments and apparatus lies with the contractor at his own cost. Any damage during testing shall be contractor's responsibility and shall be rectified by him free of cost. Water for testing shall be arranged by the Contractor at his own cost.

Water Test for Sewers.

After laying and jointing of sewer pipes and before backfilling the trenches, the complete length of the sewer is to be checked for water tightness.

The procedure for testing is as detailed below,

Each section of sewer shall be tested for water tightness from manhole to manhole To prevent change in alignment and disturbance after the pipes have been laid, it is desirable to backfill the pipes up to the top keeping at least 90cm length of the pipe open at the joints in case of longer length pipes.

In case of concrete and stoneware pipes with cement mortar joints, pipes shall be tested three days after cement mortar joints have been made. It is necessary that the pipelines are filled with water for about a week before commencing the application of pressure to allow for the absorption by pipe wall.

The sewers are tested by plugging the upper end with a provision for an air outlet pipe with stop cock.. The water is filled through a funnel connected at the lower end provided with a plug. After the air has been expelled through the air outlet, the stop cock is closed and the water level in the funnel is raised to 2.50m above the invert at the upper end. Water level in the funnel is noted after 30 minutes and quantity of water required to restore the original water level in the funnel is determined. The pipeline under pressure is then inspected while the funnel is still in position. There shall not be any leaks in the pipe or the joints (small sweating on the pipe surface is permitted). Anysewer or part there of that does not meet the test shall be emptied and repaired or re-laid as required and tested again.

The leakage or quantity of water to be supplied to maintain the test pressure during the period of 10 minutes shall not exceed 0.2 lit/mm dia. of pipe per kilometer length per day.

Exfilteration test for detection of leakage shall be carried out at a time when the ground water table is low.

For concrete, R.C.C. pipes of more than 600mm dia. the quantity of water inflow can be increased by 10% for each additional 100mm of pipe dia.

After completion of the test all temporary seals shall be removed, the test water shall be drained out / pumped out and the line cleaned properly.

Test for Straightness and obstruction

As soon as a stretch of sewer is laid and tested, before commissioning the cleanliness of the pipeline is to be checked by the following tests as applicable and as decided by the Engineer.

a). Torch & Mirror Test

In this method of testing, a torch will be held one end of the pipeline inside a manhole and its image through the pipeline will be reflected and seen on a mirror held at the opposite end of the pipeline, inside the next manhole. Any obstruction / debris / major mis-alignment will not give a clear image in which case the pipeline will again be cleaned / rectified and the tests re-done.

b). Ring Test

In this method of testing two steel/ wooden rings of suitable thickness and design shall be fixed facing each other at a distance of 2 feet or more. The block of rings shall be inserted from one end of the pipeline, inside manhole and pulled by a rope fixed to the block from the other end of the pipeline, inside the next manhole. The rings shall be of dia 75 mm less than the inside diameter of pipe under testing. The rope used for pulling the ring block may be inserted in the pipeline by suitable means. Any construction / debris / major misalignment will prevent the ring to pass through the pipeline in which case the pipeline will again be cleaned / rectified and the test redone, and no extra payment will be made. Alternately upon the approval of the Engineer, the sewer may be tested by inserting at the high end of the sewer, a smooth ball of a diameter 13 mm less than the pipe bore. In the absence of obstruction, such as yarn or mortar projecting through the joints, the ball should roll down the invert of the pipe and emerge

at the lower end. Any construction / debris / major misalignment that prevent the ball to pass through the pipeline in which case, the pipeline shall be again cleaned / rectified and the tests redone, and no extra payment will be made.

Water Test for Manholes.

The entire height of Brick and RCC manhole shall be tested for water-tightness by closing both the incoming and outgoing ends of the sewers and filling the manhole with water. A drop in water level not more than 50mm per 24 hours shall be permitted. In case of high subsoil water it should be ensured that there is no leakage of ground water into the manhole by observing the manhole for 24 hours after emptying it.

Test Records

Complete test records shall be maintained for all tests carried out for sewers both during construction and after being in service. The tests carried out as in specifications, approved QAP shall be documented in the formats as approved by the Engineer and shall be carried out in the presence of the Engineer or his representative and shall be certified by the Engineer or his representative and the Contractor. All completed Test records/documents shall be submitted to the Engineer before submission of bills.

Commissioning

After satisfactory completion of works and Testing of the sewer lines and appurtenances as per specifications in above clauses, the system shall be commissioned for trial run and operation.

Final Finishing

The contractor will ensure that the entire structure along with all its installations is in finished and in new and fully operative condition when handed over. He shall have repaired and removed all signs of damage that might have been done during the course of construction of manholes and laying of sewers. He shall also see that the entire exterior has been finished properly and the entire site is cleared of all extra construction material, debris, and excavated soil. This shall have to be done to the satisfaction of the Engineer.

As Built Drawings

The contractor shall submit to the Engineer within two months of actual completion of the work, “As Built” Drawings as specified below and operation and maintenance instructions for the whole of the

Works. These Drawings shall be accurate and correct in all respects, including the existing sewer network for which the contractor has done the condition assessment survey, shall be submitted to, and approved by the Engineer. Completion Drawings as below on two prints and one polyester film shall be supplied by the contractor, along with a soft copy in CD. These drawings shall be developed in Auto CAD. Drawing shall be of standard size as below,

i). Strip Plans and L-sections of Under Ground Drainage system showing pipe work in package area on scale as per standard practices to the satisfaction of the Engineer, showing sewer alignments, levels, appurtenances, sizes and material of pipe etc. complete.

ii). Structural Drawings showing reinforcement details of all the components covered under this contract as per standard practices.

Inspection

All works and material under specification will be rigidly inspected during all phases of manufacture and testing and such inspection shall not relieve the contractor of his responsibility to furnish materials and performed work in accordance with this specification.

The contractor will notify the engineer, in advance of the procurement of materials and fabrication thereof, in order that the employer may arrange for mill and shop inspection. The engineer may reject any or all materials or work that does not meet with any of the requirements of this specification. The contractor shall rectify or replace such rejected material/performed work at his own cost, to the satisfaction of the engineer.

The Engineer shall have free access to those parts of all plants or any other premises and sites that are concerned with the furnishing of materials or the performance of the work under this specification.

The contractor shall supply free of cost required specimen of materials for testing by the employer at any time during the progress of work and shall bear the cost of all such tests or retests to the satisfaction of engineer.

SECTION 8:

DRAWINGS

SECTION 9:

BILL OF QUANTITIES

Note:

(1) Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities (refer: ITB Clause 11.2 and CC Clause 37.2).

(2) Unit rates and prices shall be quoted by the Tenderer in Indian Rupees.

(3) Where there is a discrepancy between the rate in figures and words, the lower of the two will govern. [ITT Clause 24.1(a)]

(4) Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity, the unit rate quoted shall govern [ITT Clause 24.1 (b)]

SECTION 10:
FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT

To: _____ [name of Employer]
_____ [address of Employer]
WHEREAS _____ [name and address of Contractor] (hereinafter called "the Contractor") has undertaken, in pursuance of Contract No. _____ dated _____ to execute _____ [name of Contract and brief description of Works] (hereinafter called "the Contract");
AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with a Bank Guarantee by a recognized bank for the sum specified therein as security for compliance with his obligations in accordance with the Contract;
AND WHEREAS we have agreed to give the Contractor such a Bank Guarantee;
NOW THEREFORE we hereby affirm that we are the Guarantor and responsible to you, on behalf of the Contractor, up to a total of Rs._____ [amount of guarantee] [63]_Rupees_____ _____[in words], and we undertake to pay you, upon your first written demand and without cavil or argument, any sum or sums within the limits of _____ [amount of guarantee][64] as aforesaid without your needing to prove or to show grounds or reasons for your demand for the sum specified therein.
We hereby waive the necessity of your demanding the said debt from the Contractor before presenting us with the demand.
We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.
This guarantee shall be valid until 30 days from the date of expiry of the Defects Liability Period.
Signature and seal of the guarantor _____
Name of Bank _____
Address _____
Date _____

[63] An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract

[64] An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract